

# **Bryant Development and Review Committee Meeting**

Boswell Municipal Complex - City Hall Conference Room

210 SW 3rd Street

Date: June 03, 2022 - Time: 9:00 AM

#### Call to Order

#### **Old Business**

#### **New Business**

#### 1. Midtown Bryant - Phase 3 - Preliminary Plat

Hope Consulting - Requesting Recommendation for Approval of Preliminary Plat

- · 0561-PLN-01.pdf
- 0561-APP-01.pdf
- <u>0561-LTR-01.pdf</u>

#### 2. Five Star Fireworks - 23101 I-30

Mark Bradford - Requesting Approval for Temporary Business Permit

- 0564-APP-02.pdf
- <u>0564-APP-01.pdf</u>

#### 3. Buffalo Wild Wings - Alcoa Road - Sign Variance

Siez Sign Company - Requesting Sign Variance for Height of Pole Sign

- · 0563-APP-01.pdf
- 0563-PLN-02.pdf
- 0563-PLN-01.pdf

#### 4. Splash Carwash - Reynolds Road

Phillip Lewis Engineering - Requesting Site Plan Approval

- 0559-SWPPP-01.pdf
- 0559-PLN-03.pdf
- · 0559-DRN-02.pdf
- <u>0559-ELV-02.pdf</u>
- · 0559-RSP-01.pdf

#### **Staff Approved**

#### 5. Vape City Smoke and Tobacco - Sign Permit

L Graphics - Requesting Sign Permit Approval - STAFF APPROVED


• 0562-APP-01.pdf

# **Permit Report**


# Adjournments

# CONSTRUCTION PLANS MIDTOWN BRYANT PHASE-3

BRYANT, AR



VICINITY MAP




# PREPARED BY:



117 S. Market Street, Benton, Arkansas 72015 PH. (501)315-2626 FAX (501) 315-0024 www.hopeconsulting.com

# DRAWING INDEX

DRAWING INDI	
SHEET NO.	TITLE
	PLAT
C-1.0	STREET PLAN
C-1.1	STREET PLAN & PROFILE
C - 2.0	UTILITY PLAN
C - 2.1	SEWER PLAN & PROFILE
C - 3.0	DRAINAGE PLAN
C - 4.0	CIVIL SPECIFICATIONS
C - 5.0	EROSION CONTROL PLAN



CIVIL ENGINEER HOPE CONSULTING INC 117 S. MARKET STREET BENTON, AR 72015

STRUCTURAL ENGINEER N/A

ARCHITECT

GEOTECHNICAL ENGINEER




FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC

MIDTOWN BRYANT, PHASE-3

C.A.D. BY: 05-25-2022 CHECKED BY: REVISED:


DRAWING NUMBER: 07-0032





PRELIMINARY PLAT OF

# MIDTOWN BRYANT, PHASE 3

A SUBDIVISION IN THE CITY OF BRYANT, SALINE COUNTY, ARKANSAS










By affixing my seal and signature, IJonathan l. Hope, PLS No. 1762, hereby certify that this drawing correctly

NOTE: This survey was based on legal descriptions and title work furnished by others and does not represent a

According the the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) for Saline County unincorporated areas, panel # 05125C0225D, dated 06/19/2012, no portion of the property described hereon does lie within the 100 year flood hazard boundary.



DEVELOPER:

GRAHAM SMITH

12 PINE MANOR 12 PINE MANOR LITTLE ROCK, AR 72207 LITTLE ROCK, AR 72207

GRAHAM SMITH

## CERTIFICATE OF OWNER:

We, the undersigned, owners of the real estate shown and described herein do hereby certify that we have caused to be laid off, platted and subdivided, and to hereby lay off, plat and subdivide said real estate in accordance with the plat.

Source of Tile:

# CERTIFICATE OF SURVEYING ACCURACY:

I, Jonathan L. Hope, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their location, size, type and material are correctly shown; and that all interior lot lines have been adjusted to "as built conditions" and are accurately described on the plat and identified on the ground in terms of length and direction of the property side as required in accord with the City of Bryant Subdivision Regulation Ordinance.

Jonathan L. Hope Registered Professional Land Surveyor No. 1762 Arkansas

## CERTIFICATE OF PRELIMINARY ENGINEERING ACCURACY:

I, William W. McFadden, hereby certify that this plat correctly represents a plan made by me, and that the engineering requirements of the City of Bryant Subdivision Rules and Regulations have been complied

Date of Execution

William W. McFadden Engineer, No. 14048 Arkansas

# CERTIFICATE OF PRELIMINARY PLAT APPROVAL:

Pursuant to the City of Bryant Subdivision Rules and Regulations, and all of the conditions of approval having been completed, this document is hereby accepted. This certificate is hereby executed under the

Date of Execution

Bryant Planning Commission

Name, Chairman

# PROPERTY SPECIFICATIONS:

GRAHAM SMITH 12 PINE MANOR LITTLE ROCK, AR 72207 DEVELOPER/: GRAHAM SMITH SUBDIVIDER 12 PINE MANOR ENGINEERS: HOPE CONSULTING INC. 117 S MARKET STREET

BENTON, AR 72015 NAME OF SUBDIVISION: MIDTOWN BRYANT

ZONING CLASSIFICATION: TND OVERLAY DISTRICT SOURCE OF TITLE:

NUMBER OF LOTS: 29 SOURCE OF WATER: CITY OF BRYANT SOURCE OF SEWER: CITY OF BRYANT BUILDING SETBACKS: PER TND OVERLAY ORDINANCE T-4 FRONT - 6' MIN. 18' MAX

SIDE - 0' TOTAL MIN.

SETBACKS ARE MEASURED FROM BACK OF CURB EASEMENTS: (UTILITY & DRAINAGE)

. ALL ALLEYWAYS & COMMERCIAL PARKING LOTS ARE CONSIDERED UTILITY & DRAINAGE EASEMENTS.

ANY UTILITY OR DRAINAGE STRUCTURES OUTSIDE OF EXISTING R/W; ALLEYWAY OR PARKING LOT WILL BE WITHIN A 10' EASEMENT.




117 S. Market Street, Benton, Arkansas 72015 PH. (501)315-2626 FAX (501) 315-0024 www.hopeconsulting.com

FOR USE AND BENEFIT OF:

**GRAHAM SMITH** 

PRELIMINARY PLAT MIDTOWN BRYANT, PHASE 3 A SUBDIVISION IN THE CITY OF BRYANT, SALINE COUNTY. ARKANSAS.


DATE:	05-23-2022	C.A.D. BY: B.JOHNSON	DRAWING NUMBER:
REVISED:		CHECKED BY:	07-0032
KEVISED:		SCALE: 1"=40'	07-0032
		0	














FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC


MIDTOWN BRYANT, PHASE-3

STREET LAYOUT BRYANT, SALINE COUNTY, ARKANSAS


DATE:	5/25/2022	C.A.D. BY:	DRAWING NUMBER:
REVISED:		CHECKED BY:	07-0032
SHEET:	C-1.0	SCALE:	07-0032
	1		

TYPICAL STREET CROSS SECTION 50' R.O.W 1.5" ACHM SURFACE COURSE 1.5" ACHM SURFACE COURSE 7" OF CLASS 7 AGGREGATE BASE COURSE COMPACTED TO 98% MODIFIED PROCTOR SUBGRADE COMPACTED TO 95% MODIFIED PROCTOR — TO A DEPTH OF 18" — UNDERCUT 2' DEPTH WHERE DIRECTED






# COURT STREET PROFILE














ENGINEERS - SURVEYORS www.hopeconsulting.com


FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC


> MIDTOWN BRYANT, PHASE-3 STREET PROFILE


BRYANT, SALINE COUNTY, ARKANSAS

ATE:	5/25/2022		C.A.D. BY:				DRAWING	G NUMBER:
EVISED:	EVISED:			CHECKED BY:			07-0032	
HEET:	C-1.0		SCAL	E:			U / ·	<u>-UU3Z</u>
500	1S	15	W	0	34	230	62	1807




















DUAL WATER METERS SINGLE WATER METER


90º FITTING TEE FITTING CROSS FITTING

FIRE HYDRANT

# FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC

MIDTOWN BRYANT, PHASE-3 SEWER PLAN AND PROFILE BRYANT, SALINE COUNTY, ARKANSAS

			· · · · · · · · · · · · · · · · · · ·						
DATE:	5/25/2022		C.A.D	. BY:			DI	RAWING	NUMBER:
REVISED:		(	CHECKED BY:		CHECKED BY:		0032		
SHEET:	C-2.1	5	SCALE:			U / -	-0032		
500	1S	15V	V	0	34	230		62	1807





CONSULTING,

WATER LEGEND:

FIRE HYDRANT





- ALL SEWER INSTALLATION TO BE IN ACCORDANCE WITH THE CITY OF BRYANT " STANDARD SPECIFICATIONS FOR DESIGN AND CONSTRUCTION OF WATER LINES AND SEWER LINES, 2015
- ALL SEWER LINES CROSSING UNDER ALL CONCRETE STORM DRAINS OR ANY STORM DRAIN 30-INCH DIAMETER AND LARGER, OR ALL STORM DRAINS WITH MULTIPLE PIPE RUNS, SHALL BE STEEL ENCASED A MINIMUM OF 5 FEET EITHER SIDE OF THE STORM DRAIN.
- FORCE MAIN WILL BE TESTED IN ACCORDANCE WITH BRYANT WATER/WASTEWATER SPECIFICATION SECTION 5200-1.03.A.4
  - SANITARY SEWER FORCE MAIN SHALL BE INSTALLED IN ACCORDANCE WITH BRYANT WATER/WASTEWATER SPECIFICATIONS.
- CONNECTING MANHOLE FROM FORCE MAIN SHALL BE REQUIRED TO BE COATED WITH AN EPOXY COATING ACCORDANCE WITH BRYANT WATER/WASTEWATER SPECIFICATION SECTION

# WATER UTILITY NOTES:


ALL NEW 8-INCH AND 6-INCH WATER MAINS TO BE C900 DR 14 PVC

ALL WATER AND SEWER INSTALLATION TO BE IN ACCORDANCE WITH THE CITY OF BRYANT "STANDARD SPECIFICATIONS FOR DESIGN AND CONSTRUCTION OF WATER LINES AND SEWER LINES, 2015 EDITION"

WATER LINES UNDER CULVERTS, CREEKS, CONCRETE CHANNELS, RETAINING WALLS, OR OTHER DIFFICULT AND/OR DANGEROUS TO MAINTAIN AREAS SHALL BE ENCASED IN A SMOOTH STEEL ENCASEMENT PIPE. THE STEEL ENCASEMENT SHALL EXTEND FIVE FEET EITHER SIDE OF THE AREA. EACH WATER SERVICE METER MUST HAVE ITS OWN SERVICE LINE CONNECTION TO THE MAIN

(INCLUDES DOUBLE METERS DISPLAYED AS ONE SERVICE LINE ON THE PLAN). THE SEWER/WATER MAIN CROSSINGS THAT REQUIRE ENCASEMENT REQUIRE TEN (10) LINEAR FEET OF PIPE ON EITHER SIDE OF THE CROSSING.

ADH RULES PERTAINING TO PUBLIC WATER SYSTEMS NOTES REGARDING CROSS-CONNECTIONS AND SEPARATIONS OF WATER AND SEWER- WATER AND SEWER WILL BE 10 FEET APART IN PARALLEL AND IN THE CASE OF WATER CROSSING SEWER WATER LINE SHOULD BE MINIMUM 18" ABOVE SEWER LINE. AT THE EVENT OF WATER CROSSING BELOW SWER EITHER ONE OF THE PIPE WILL NEED TO BE ENCASED.



USE SDR-26 PVC SEWER PIPE EXCEPT WHERE DUCTILE IRON PIPE REQUIRED FOR COVER. USE DUCTILE IRON PIPE WHERE 3' MINIMUM COVE CANNOT BE MAINTAINED. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL BURIED UTILITIES PRIOR TO CONSTRUCTION.







FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC

> MIDTOWN BRYANT, PHASE-3 UTILITY PLAN

BRYANT, SALINE COUNTY, ARKANSAS C.A.D. BY: DRAWING NUMBER: REVISED: CHECKED BY: 07-0032 SHEET: C-2.0





DRAINAGE NOTES

No fences, pools or permanent obstructions may be placed in any access or drainage easements.

Dead Storage of pond will be used as a sediment pond at the time of construction later it will remain as a water feature.

Filter fabric shall be placed under all riprap areas.

All drainage ditches and swales that are not concreted will be required to be stabilized with solid sod stabilization per the Stormwater Management Manual.

Any new drainage ditches or swales, new or that have been disturbed during construction are required to have solid sod stabilization per Section 500.7.2 of the Stormwater management Manual. (This is required to be show in detail on the plans).









PP DUAL WATER METERS SINGLE WATER METER ▼ GATE VALVE

WATER LEGEND:

45º FITTING ♦ 90º FITTING TEE FITTING

CROSS FITTING FIRE HYDRANT

MIDTOWN BRYANT, PHASE-3 STORM DRAINAGE PLAN AND PROFILE

FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC

BRYANT, SALINE COUNTY, ARKANSAS DRAWING NUMBER: C.A.D. BY: REVISED: CHECKED BY: SHEET: C-3.01S 15W 0 34 230 62 1807

#### SUBGRADE MATERIAL

- A. Subgrade soils shall be all materials used for subgrade including in-situ materials and fill materials.
- B. Subrades for pavement shall be stabilized by mechanical compaction. Stabilization methods such as fabrics and chemical stabilization may be submitted for approval when supported by engineering data and calculations to substantiate the adequacy of the stabilized procedure.
- C. Subgrade shall be compacted to 95 percent modified proctor density minimum. Moisture content shall be +/- 3% of optimum moisture unless otherwise supported by the site specific geotechnical data and approved by City. D. Subgrade shall be prepared in such a manner that the base course shall be placed on a firm foundation that is stable and free from soft spots, pumping, dust pockets, wheel ruts, or other defects.
- E. The top 24 inches of the subgrade shall be a material not susceptible to frost action unless modified with cement, lime or another method approved specifically by the City to resist frost action. Soils classified as A-4 and A-5 including sandy silts, fine silty sand or lean clays are highly susceptible to frost
- F. In-situ soils meeting the requirements outlined in these specifications may be utilized as subgrade shall be scarified to a minimum depth of 8-inches below finish subgrade, recompacted and tested as described below. Fill material for subgrade shall be placed in lifts not to exceed 8-inches compacted depth.
- G. Methods and procedures for establishing the total depth of soil replacement and/or modification shall be as specified by the design engineer and geotechnical investigations. The adequacy of in-situ soils and fill materials as pavement subgrade shall be evaluated based upon the soils classification, liquid
- H. Soils with a liquid limit greater than 40, or a plasticity index greater than 15 shall be undercut and removed from the street section or improved by a design method of stabilization approved by the City.
- I. Quality control testing shall be as specified below.
- Undercut 24" of soil below finished street base course. Proof roll to verify stability
- K. Backfill the undercut subgrade with Class 7 aggregate or soil meeting the requirements of this section and compact in lifts not exceeding 8".

#### BASE COURSE

- A. Base course material shall be crushed stone meeting the requirements of ArDOT Class 7 aggregate base course as specified in the latest edition of ArDOT Standard Specifications.
- B. Base course shall be compacted to 98 percent modified proctor density minimum. Moisture content shall be +/- 3% of optimum moisture.

#### SURFACE COURSE

A. Surface course for flexible pavement designs shall utilize plant mix bituminous base and binder courses conforming to ArDOT Standard Specifications.

# CURB AND GUTTER

- A. Curb and gutter shall be Portland Cement Concrete with a minimum 28-day compressive strength of 4,000 psi. Concrete shall be air-entrained with a maximum of 4-inch slump.
- B. Compaction requirements under curb and gutter shall conform to the requirements for street subgrade materials. Compaction requirements shall extend to a minimum of 1 foot behond the back of curb and gutter removing all soft spots and replacing with suitable materials. C. Curb and gutter shall conform to the typical detail within these specifications or ArDOT Standard Roadway Drawing Details for curbing.
- D. Expansion joints shall be made with 1/2-inch preformed expansion joint filler of a non-extruding type. Expansion joints shall be placed at intervals not exceeding 195 feet, intersection radii, driveways, stationary structures, and sidewalks.
- E. Contraction joints shall be sawed or fromed at intervals not greater than 20 feet. Depth of saw-cut hall be 1 1/2-inch and have a width of 1/4-inch. Contraction joints shall be sealed in accordance with ArDOT Standard Specifications.
- F. Forms shall be made of metal or wood and shall be properly braced. The minimum length of each section of form used shall be uniform and free from undesirable bends or warps. Forms shall be of such cross section and strength and so secured as to resist the
- G. Curb and gutter placed with slip form or extruding equipment will be acceptable providing it complies with all of the above requirements.
- H. After curing, the curb shall be immediately backfilled to within 4 inches of the top curb to eliminate the possibility of washing beneath the curb. The remaining 4 inches shall be topsoil. I. Cold weather protection shall meet the requirements of the latest edition of ArDOT Standard Specifications.

pressure of the impact and vibration on any equipment which they support without springing or settlement.

#### **SIDEWALKS**

#### General

- A. Sidewalks shall be Portland Cement Concrete with a minimum 28-day compressive strength of 4,000 psi.
- B. Sidewalks shall be on both sides of streets in line with sidewalks on opposite corners of roads.
- C. All sidewalks including ramps shall meet all current Federal Americans with Disabilities (ADA) design guidelines or requirements.
- D. Traverse slopes shall not exceed 2 percent.
- E. Subgrade under sidewalks shall be compacted to 90 percent modified proctor density minimum.
- F. Sidewalks shall not be placed upon grassy or organic materials.
- G. Sidewalks which extend or link existing sidewalks shall adjoin the existing sidewalks to form a continuous, even pathway.
- H. Utility poles, utility boxes, mailboxes, fire hydrants, and other similar obstructions shall not be located in sidewalks Sidewalk location may vary at the discretion of the City to avoid such obstacles.

#### Minimum thickness and reinforcement

- A. Sidewalks shall have a minimum thickness of 4 inches.
- B. Sidewalks shall be reinforced, at a minimum, with woven wire fabric reinforcement.

#### Contraction and expansion joints

- A. Contraction joints shall be provided perpendicular to the sidewalk at intervals equal to the sidewalk width.
- B. Expansion joints shall be constructed perpendicular to the sidewalk at intervals equal to five times the sidewalk width. Expansion joints shall be made with 1/2-inch preformed expansion joints shall be placed at driveways, drop inlets, and curbs.

# Quality control testing and inspection by the City


- A. Subgrade and formwork for sidewalks shall be inspected by the City prior to pouring of the sidewalk.
- B. All testing of materials and construction shall be provided and paid for by the Developer/Owner.
- C. All field tests required for a project shall be witnessed by the City, contractor, or their authorized representatives.
- All testing shall be accomplished by a testing firm approved by the City and shall be performed under the supervision of a licensed Professional Engineer.
- E. Sampling and testing locations shall be subject to approval by the City.
- F. Density tests on subgrades shall be taken every 300 feet or portion thereof.
- G. The City shall be notified at least one day in advance of the need to inspect subgrade and formwork of sidewalks.


- A. Subgrade soils shall be all materials used for subgrade including in-situ materials and fill materials.
- B. Subgrade shall be compacted to 90 percent modified proctor desnity minimum. Moisture content shall be +/- 3% of optimum moisture unless otherwise supported by the site specific geotechnical data and approved by City.
- C. Subgrade shall be prepared in such a manner that the base course shall be placed on a firm foundation that is stable and free from soft spots, pumping, dust pockets, wheel ruts, or other defects.
- D. The top 24 inches of the subgrade shall be a material not susceptible to frost action unless modified with cement, lime or another method approved specifically by the City to resist frost action. Soils classified as A-4 and A-5 including sandy silts, fine silty sand or lean clays are highly susceptible to frost

# QUALITY CONTROL TESTING AND INSPECTIONS

# General

- A. Materials and construction employed in street improvements shall be subject to inspection and quality control testing. All testing of materials and construction shall be provided and paid for by the Developer/Owner.
- B. The Developer/Owner shall provide for inspections of street improvements during construction. The Engineer of Record. The Engineer of Record shall provide certification that all materials and construction conform to the approved plans and specifications and with these minimum street standards.
- C. The Engineer of Record shall furnish inspection whenever a critical construction activity is taking place. This means that a representative of the Engineer of Record must be on-site whenever a critical construction activity is taking place.
- D. All field tests required for a project shall be witnessed by the City, Engineer of Record, contractor, or other authorized representatives. E. The City shall be notified at least one day in advance of any test(s). It is the responsibility of the contractor to coordinated the scheduling of all tests with the City.





TYPICAL CURB DETAILS & NOTES

# Typical Sidewalk Detail

# Typical Curb & Gutter Detail

4,000 psi concrete










FOR USE AND BENEFIT OF: GRAHAM SMITH CONSTRUCTION, LLC

# MIDTOWN BRYANT, PHASE-3

CIVIL SPECIFICATIONS

5/25/2022 C.A.D. BY: DRAWING NUMBER: REVISED: CHECKED BY: 07-0032 SCALE: SHEET: C-5.0

BRYANT, SALINE COUNTY, ARKANSAS



TRENCH WITH GRAVEL

NOTE:
1.) INSPECT AND REPAIR FENCE AFTER EACH
STORM EVENT AND REMOVE SEDIMENT WHEN


TRENCH WITH NATIVE BACKFILL

NECESSARY.

2.) REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY

3.) SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.


STABILIZED.



VIEW LOOKING UPSTREAM

NOTES:

1.) POINT 'A' MUST BE HIGHER THAN POINT 'B' (SPILLWAY HEIGHT)
2.) PLACE RIP-RAP BARRIER PERPENDICULAR TO THE FLOW WITH TIGHT GROUPING.
USE STRAW, ROCKS, OR FILTER FABRIC TO FILL ANY GAPS AND TAMP
BACKFILL MATERIAL TO PREVENT EROSION OR FLOW AROUND THE DAM.
3.) SPILLWAY HEIGHT SHALL NOT EXECU 18\*-24\*.
4.) INSPECT AFTER EACH SIGNIFICANT STORM, MAINTAIN AND REPAIR PROMPTLY.





# EROSION CONTROL NOTES

SOD OR SEED DETENTION AREA POST—CONSTRUCTION (IF APPLICABLE)

MAXIMUM SLOPE OF 3H:1V ON DETENTION POND LEVEES

CONTRACTOR MUST HAVE INLET PROTECTION MEASURES
INSTALLED IMMEDIATELY AFTER CONSTRUCTION OF DRAINAGE


INLETS/STRUCTURES IS COMPLETE. SEDIMENT BARRIERS SHALL
BE MAINTAINED THROUGHOUT AND INSPECTED THROUGHOUT
CONSTRUCTION PROCESS UNTIL PROJECT IS COMPLETE
RIP RAP SEDIMENT BARRIERS SHALL BE USED AT ALL

STORMWATER DISCHARGE POINTS SHOWN ON PLANS ASAP

CONTRACTOR SHOULD WORK WITH ENGINEER TO ESTABLISH
EFFECTIVE AND EFFICIENT PLAN TO PREVENT SEDIMENT RUNOFF
BY DETERMINING WHERE SILT FENCING OR OTHER TYPES OF
CONTROLS ARE NECESSARY


SOME EROSION CONTROL MEASURES, SILT FENCING, OR CHECK DAMS MAY NOT BE NECESSARY DURING INITIAL ROW CLEARING BUT MAY BE NEEDED ONCE LOT CLEARING AND HOME BUILDING BEGINS

EXISTING VEGETATION WILL ONLY BE REMOVED INSIDE ROW AND WITHIN HOUSE FOOTPRINTS AS THEY ARE CONSTRUCTED.
ADDITIONAL SILT FENCING WILL BE ADDED TO INDIVIDUAL LOTS AS HOME CONSTRUCTION TAKES PLACE.



# ERC LEGEND

SITE POSTING



DISTURBED AREA

CONC. WASHOUT DETENTION AREA

— SILT FENCE

RIP RAP CHECK DAM


CONSTRUCTION ENTRANCE



BRYANT

QUAPAW Q





117 S. Market Street,
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
Www.hopeconsulting.com

FOR USE AND BENEFIT OF:
GRAHAM SMITH CONSTRUCTION, LLC

MIDTOWN BRYANT, PHASE-3
EROSION CONTROL PLAN

	BRYANT, SALINE COUNTY, ARKANSAS						
DATE:	5/25/2022	C.A.D. BY:	DRAWING NUMBER:				
REVISED:		CHECKED BY:					
SHEET:	C-5.0	SCALE:	0'/-0032				



#### **Subdivision Checklist**

Approved by Bryant Planning Commission 07/14/2003 Revised 6/18/2007

#### Instructions

The attached checklist must be completed by the owner and subdivision engineer and must be submitted along with the Preliminary Plat Plan and other specified documentation for review and approval by the Planning Commission. The owner may not begin developing the subdivision until the review of the Preliminary Plat plan is approved.

No changes or alterations can be made to the approved Preliminary Plat Plan without Planning Commission approval.

When all lots have been surveyed, the utilities and drainage measures are in place, and roads have been constructed, the owner and engineer will submit a Final Plat Plan for approval by the Commission. This Final Plat Plan will incorporate all approved changes and will be verified by the City Engineer. No lots will be sold or rights-of-way and easements conveyed until the Final Plat has been submitted and approved.

#### Fees due to City of Bryant upon submission of Preliminary Plat application

- \$300.00 + \$3.00 per lot for Subdivision preliminary plat review \$300+(29\*\$3)=\$387
- \$250.00 or \$25.00 per lot (whichever is greater) Stormwater Detention and Drainage Plan Engineering Fee 29\*\$25.00=\$725
- A Surety Bond or Cashier's check in the amount of 10% of the estimated development cost must be furnished within 10 days after Preliminary Plat approval.

#### Fees due to Bryant Water and Sewer Department upon submission of Final Plat application

- \$100 per lot Water/Sewer Impact Fee
- \$100 per Subdivision Phase Water/Sewer Flushing Fee

#### Fees due to City of Bryant upon submission of Final Plat application

\$25.00 + \$1.00 per lot - for Subdivision Final Plat review

Subdivision Review= \$387 Stormwater Review= \$725 **Total Fee Required= \$1,112** 

# City of Bryant Subdivision Checklist

Subdivisi	on/Project NameMidtown Pha	se 3	
Contact I	PersonJonathan Ho	pe Phone _	501-860-0467
Mailina A	117 South Market Street Be	nton, Arkansas	
Mailing A	daress		
I. BASIC	INFORMATION NEEDED ON THE PLAT		
<b>1</b> .	Name of Subdivision/Project		
<b>2</b> .	Current zoning PUD		
<b>3</b> .	Name and Address of owner of Record		
<b>4</b> .	Illustrate Source of Title giving deed re	cord book and page number	
<b>▲</b> 5.	Name & address of the sub-divider		
<b>▲</b> 6.	Date of Survey		
<b>▲</b> 7.	Vicinity map locating streets, highways,	, section lines, railroad, school	ls, & parks within ½ mile
<b>8.</b>	Legal description of the property with e	exact boundary lines	
<b>▲</b> 9.	Acreage of property		•
<b>1</b> 0.	Number of Lots		
<b>▲</b> 11.	Lot area in square feet		
<b>▲</b> 12.	Lot lines with appropriate dimensions		
<b>13.</b>	Building setback lines		
<b>▲</b> 14.	Preliminary Engineering certificate seal	and signature on each page	
<b>15.</b>	Certificate of Engineering Accuracy		
I .	Certificate of Owner		
<b>▲</b> 17.	Certificate of Final Plat Approval		
1	Certificate of Recording		
<b>▲</b> 19.	Show scale (not less than 1" = 100')		
<b>2</b> 0.	North Arrow		
<b>▲</b> 21.	Show Title block		
1	Show adjoining property owners		
1	Layout of all proposed streets including	•	igns, speed limit, etc.)
	Layout of all subdivision entrance street	: upgrades	
1	Layout of all proposed alleys		
1	Layout of all proposed sidewalk systems		
<b>▲</b> 27.	Layout identifies any FEMA flood plain a		the 100-year flood elevation.
1 4 20	(Provide Corp of Engineers 404 Permit if Drainage easements for stormwater run		nsions locations and purpose
	Layout accommodates Master Street Pla		
•	Street layout ties to existing adjoining s	•	
<b>—</b> 30.	future adjoining subdivisions.	abdivision stab out streets and	a provides seab ode servers for
/ <b>▲</b> 31.	Street width and right-of-way properly s	shown for each functional class	sification
<b>Y</b>	Street centerlines showing angles of def	lection, intersection, radii, ler	
	degree of curvature with basis of curve	aata	
<b>V</b>	Typical cross section of streets		
<b>V</b>	Location and name of existing streets	o ovieting street	
<b>V</b>	New street names that are not similar to	existing street names	
<b>A</b> 36.	Show street lights		

▲ 37. Show Fire Hydrant placement

- ▲ 38. Show and label all permanent & proposed easements
- ▲ 39. Any proposed open space must be shown
  - ▲ 40. Show the direction and flow of all water courses entering the tract
- 41. Show the direction and flow of all water courses leaving the tract
  - ▲ 42. The drainage area of all water courses above the points of entry.
  - ▲ 43. The downstream drainage channel and drainage structures substantially impacted by the subdivision/project.
- ▲ 44. Show source of water supply

 $\sqrt{}$ 

- ▲ 45. Show location of waste water connection to municipal main & sanitary sewer layout
- ▲ 46. A phasing plan outlining the boundaries for each phase

#### II. ADDITIONAL INFORMATION NEEDED, BUT NOT NECESSARILY ON THE PLAT

- ▲ 47. Natural features within the proposed subdivision including drainage channels, bodies of water, wooded areas, and other significant features
- ▲ 48. Existing streets, buildings, water courses, railroads. Culverts, utilities and easement on and adjacent to the tract.
- ▲ 49. Where method of disposal of wastewater is other than connection to a public waste water system, detailed information shall accompany the plat.
- ▲ 50. Calculations and field notes, including drainage calculations along with support drawing
  - 51. Stormwater detention plan approval from City Engineer (attach copy of approval)
- ▲ 52. The Certificate of Preliminary Engineering Accuracy on each set of street and drainage plans.
  - ▲ 53. ADA Accessibility Standard Form completed (and attached)
  - ▲ 54. A Bill of Assurance has been prepared for this subdivision (and attached)
  - ▲ 55. All lots comply with minimum square footage area and minimum lot width at the front building line
  - ▲ 56. Street pavement design will be as specified by City or AHTD design procedures, approved by the City Engineer.
  - ▲ 57. Made the "One Call" prior to site clearance or other excavation activity

#### III. PRELIMINARY PLAT ATTACHMENTS

#### (APPLICATION WILL NOT BE ACCEPTED UNTIL ALL ATTACHMENT REQUIREMENTS ARE MET)

- ▲ 58. Letter to Planning Commission stating your request
- ▲ 59. Completed Checklist

 $\sqrt{}$ 

- ▲ 60. Completed agreement to provide performance assurance
- ▲ 61. Subdivider Performance Bond or Cashier's Check for infrastructure installation
- ▲ 62. Landscaping plan of any proposed common open space
- ▲ 63. **Draft of Bill of Assurance** proposed for the subdivision (if applicable)
- ▲ 64. **20 copies of Preliminary Plat Plan (folded)** that includes vicinity map (minimum size 17" X 34" paper)
- ▲ 65. Two (2) IBM compatible diskettes or CDR's with pertinent data and Plat in CAD compatible .DXF electronic file format
- ▲ 66. Copy of Stormwater Detention approval
- ▲ 67. 2 copies Plan and profile of all streets
- ▲ 68. Receipt for \$300.00 + \$3.00 per lot for preliminary Subdivision fee
- ▲ 69. Receipt for \$250.00 or \$25.00 per lot (whichever is greater) for Stormwater Detention and Drainage Plan review
  - ▲ 70. Copy of ADEQ Stormwater Pollution Prevention Plan for property parcel containing one acre or larger.

III. FINAL PLAT ATTACHMENTS

#### (APPLICATION WILL NOT BE ACCEPTED UNTIL ALL ATTACHMENT REQUIREMENTS ARE MET)

- ▲ 71. Letter to Planning Commission stating your request
- ▲ 72. Completed Checklist
- ▲ 73. 20 copies of Final Plat Plan (folded) that includes vicinity map (minimum size 17" X 34" paper)
- ▲ 74. Two (2) IBM compatible diskettes or CDR's with pertinent data and Plat in CAD compatible .DXF electronic file format
- ▲ 75. Bill of Assurance including provisions set out in Title 15 Subdivision Regulations 15.16.01
- ▲ 76. Copy of Water & Sewer Commission approval or....
- ▲ 77. State Health Department approval of any new water supply and/or sewage system.
- ▲ 78. Letter submitted by a Registered Professional Engineer, certifying that all infrastructure improvements and installations have been installed in accordance with the submitted construction plans and drawings and the standards established by the City of Bryant and are functioning properly.
- ▲ 79. Infrastructure Maintenance Bond or Cashier's check.
- ▲ 80. Check for \$25.00 + \$1.00 per lot for final Subdivision fee
- ▲ 81. Check for Water Sewer impact fees (\$100.00 Flushing Fee and \$100.00 impact fee per lot)

	Jonathan Hope
Name of Subdivision	Surveyor
I HAVE COMPLIED WITH THE REQUIREMEN CHECKLIST WHICH APPLY TO THIS PROJECT	ITS LISTED ABOVE AND HAVE CHECKED ALL OF THE BOXES ON THE CT SUBMITTAL.
	William McFadden
Owner Signature	Engineer Signature
	CITYLISE
	<u>CITY USE</u>
Preliminary Plat Approved	
Planning Commission Date	
Final Plat Approved	
Planning Commission Date	
Proof of Recording - County	
County Clerk	Date

# AGREEMENT BY SUBDIVISION DEVELOPER TO PROVIDE ASSURANCE TO THE CITY OF BRYANT ARKANSAS PER ORDINANCE #98-35

T	, developer for the
	subdivision located in
the City of Bryant city limits or plar	nning jurisdiction agree to provide a surety
bond or cashier's check in the amoun	at of 10% of the development cost estimated
to be \$ but not les	ss than \$10,000 or more than \$50,000 within
10 calendar days after preliminar	y plat approval by the Bryant Planning
Commission in accordance with the	terms of Ordinance Number 98-35.
Date	Developer Signature
Witness	Printed Name
	Address
	Phone Number

ORDINANCE NO. 98-35

# ASSURANCES FOR COMPLIANCE, INSTALLATION, ETC.

- a.) Upon preliminary approval of subdivision construction plans and specifications for improvements, the Developer shall enter into an agreement with the City of Bryant to install or ensure the completion of the improvements as designed and to (repair or replace), (pay the cost to the city of repairing or replacing) all city property damaged or destroyed in connection therewith. The city will accept the subdivision and issue the certificate of final plat approval subject to the assurance of performance of the obligations of the Developer under the agreement.
- b.) One of the following assurances assigned to the city shall be utilized by the Developer to assure performance of the Developer's obligations under the agreement:
  - 1. Surety Bond in the amount of ten percent (10%) of the estimated development cost and recorded at the Saline County Courthouse.
  - Cashier's check(s) in the amount of ten percent (10%) of the estimated development cost on which no interest will be paid by the city.

Any cashier's check or certificate of deposit allowed by this section shall be insured by a financial institution insured by the Federal Deposit Insurance Corporation and licensed to business in Arkansas. Further, each instrument of assurance shall be payable to the City of Bryant, and shall be in principal amount no less that \$10,000 or no greater than \$50,000. All instruments of assurance or the city's check in the amount equal to the principal amount of the instrument less any deductions for failure to perform by the Developer shall be returned to the Developer one-year after completion of the Developers performance under the agreement.

Forfeiture of the assurance for compliance does not relieve the Developer of his responsibility to complete the subdivisions improvements to the satisfaction of the City.

Developer's of large projects that could have an adverse impact on the City's infrastructure may be required to have an assurance for compliance if so directed by the Planning Commission.

All Ordinances and parts of Ordinances in conflict with this Ordinance are hereby repealed.

Should any portion of this ordinance be unconstitutional or invalid and so declared by a court of competent jurisdiction, then the remainder of this Ordinance, and any remaining applications of the Ordinance, shall not be affected by such partial unconstitutionality or invalidity.

This Ordinance shall be in full force and effect from and after its passage, approval, and publication.

Vanda Smith City Clerk

PASSED AND APPROVED THIS 28th DAY OF September , 1998.

No Emergency Clause

Page 6



May 25, 2022

Truett Smith City of Bryant 210 Southwest Third St., Bryant, AR 72022

RE: Midtown Phase 3 (Hope Job# 07-0032)

Dear Truett:

On behalf of the property owner, Hope Consulting is requesting the review of the next phase of Midtown. We would like to be placed June 2<sup>nd</sup>, 2022 DRC Agenda. It is our goal to be on the July 11<sup>th</sup> Planning Commission meeting.

The developer of this project is Graham Smith Construction, LLC

Contact information: Graham Smith Construction, LLC 15100 Pride Valley Road, Little Rock, Arkansas 72223 501-217-8400 graham@grahamsmithcompanies.com

Please feel free to contact me with any questions or concerns or if I can be of any further assistance.

Sincerely,

Jonathan Hope







# Temporary Business Application City of Bryant

Date:5/17/2022						
Name of Business: 5 Star Fireworks						
Federal Tax Employer Identification Number: 453 21 6207						
Arkansas State Sales Tax Number: <u>Tax officer picks up taxes every year</u>						
Type of Business: Fireworks						
Location of proposed Temporary Business: 23101 I30 South Bryant, AR 72022						
Parcel Number of Location of proposed Temporary Business:						
Owner Mailing Address: 17 Ashlee Blvd, Nash Texas						
Contact Person: Mark Bradford						
Daytime Phone Number: 903-826-4453 Evening Phone Number: 903-826-4453						
Please check the category you are applying for. Permits cannot exceed the following						
time limits:						
Carnivals 30 Days						
X Fireworks stands or tents 30 Days						
Christmas tree stands, tents or lots 60 Days						
General commercial sales stands, tents or lots 90 Days						
Concession/Refreshment stands/Food Service 180 Days						
Beginning Date Requested 6/18/2022 Ending Date Requested 07/05/2022						
I hereby certify the above to be true and correct, and state that I am operating a						
business in accordance with the city's zoning regulations and/or any other city, state, or						
federal laws which may be applicable. I understand violation of Temporary Business						
Ordinance 2007-43 is a misdemeanor punishable by a fine of up to \$500.00 per						
occurrence of violation. Each day's occurrence is a separate violation. No temporary						
business may operate for more than 180 days during any consecutive 12-month period.						
Owners Signature Mark Bredford						
$\nu$						

## CITY OF BRYANT – BRYANT, ARKANSAS 210 SW 3rd St, BRYANT, ARKANSAS 72022 PHONE: (501) 943-0943

# Privilege Fee Information PERMANENT BUSINESS LICENSE

# (WHEN FILLING IN THE BLANKS PLEASE PRINT OR TYPE IN INK)

Date:_	05/17/2022		-				
Curren	t Entity #	···	-				
Busine	ess Name:	5 Star i	Fireworks				
Locati	on of Busines	ss:2:	3101 I-30 South		Bryan	t, AR 72022	
Mailin	g Address: 17	Ashlee B	lvd				75569
City:_!	Nash			State:_	_TX_	Zip Code:	75569
	ess Telephon	വാ	000 4450	Cell F			eminining, and in the 1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-
E-mai	l Address:	imafreely	/76@gmail.com				
Туре	of Business (	Services	offered or product s	sold):F	reworks	<b>3</b>	
Conta	act Person's N	lame:	Mark Bradford		Phor	ne: 903-826-4453	
Numb	er of Employ	ees:					
Do yo			nse in another city			X	
Name	e of Owner(s)	: Mark	Bradford				
Owne	ers Home Add	dress:1	7 Ashlee Blvd				
City:_	Nash	<del></del>	002 026 4452	State:_	TX	Zip Code:_	75569
Home	e/Cell Teleph	one:	003-826-4453	-			
zoning be in applic	g regulations a violation of any cable City of Br	nd/or any / of the city yant Ordin	other city, state, or fe	deral laws w	hich ma	y be applicable. I und	cordance with the city lerstand that if I am found to t to fines as outlined in any
M	arK K	radf	nl				

Owner

City Clerk/Treasurer or Designated Representative

I am requesting a temporary business permit for retail sales of consumer fireworks.

The dates I am requesting are June 20, 2022 to July 5, 2022. I have been in the fireworks industry for the past 30 years. I am based in Hot Springs, AR and have numerous locations around the state of Arkansas. We operate a professional business and strive for customer satisfaction.

Please consider this request.

Mark Brodford

Thank you,

**Mark Bradford** 

**5 Star Fireworks** 

#### Attn: City of Bryant Arkansas

Danielle Johnson DBA KYDAuh Sales Mark Bradford, dba 5 Star Fireworks permission to retail consumer fireworks on my property at 23101 I-30 South, Bryant, AR 72022 for the dates of June 20, 2022 to July 5, 2022.

If you have any questions, you can contact me at 501-951-3143.

Thank you, Signed You T. M.

23101 I-30 SOUTH BRYANT, ARK

I-30 EAST

TENT 50 ENTRANCE CHRINLINK FENCE FRONTAGE PRIVE ELECTRI Pole ROAD ENTRANCE THE PROPERTY IS SURROUNDED PROPERTY WILL BE SECURED AT

NIGHT W/ OCKED GATES



## **BOND**

(License	or Per	mit - C	ontinuo	ous)
----------	--------	---------	---------	------

Bond No. <u>107637640</u>
KNOW ALL MEN BY THESE PRESENTS:
THAT WE MARK BRADFORD  Principal, and Travelers Casualty and Surety Company of America, a corporation duly incorporated under the laws of the State of Connecticut and authorized to do business in the State of ARKANSAS, as Surety, are held and firmly bound unto City of Bryant, as Obligee, in the penal sum of One Thousand (\$1,000.00) Dollars, for the payment of which we hereby bind ourselves, our heirs, executors and administrators, jointly and severally, firmly by these presents.
WHEREAS, the Principal has obtained or is about to obtain a license or permit for Retail Sales of Fireworks
NOW, THEREFORE, THE CONDITIONS OF THIS OBLIGATION ARE SUCH, that if the Principal shall faithfully comply with all applicable laws, statutes, ordinances, rules or regulations, pertaining to the license or permit issued, then this obligation shall be null and void; otherwise to remain in full force and effect.
This bond shall become effective on
PROVIDED, that regardless of the number of years this bond is in force, the Surety shall not be liable hereunder for a larger amount, in the aggregate, than the penal sum listed above.
PROVIDED FURTHER, that the Surety may terminate its liability hereunder as to future acts of the Principal at any time by giving thirty (30) days written notice of such termination to the Obligee.
SIGNED, SEALED AND DATED this
MARK BRADFORD
By: Mark Bredford Principal Travelers Casualty and Surety Company of America
By: Wilson-Murphy  S-2151A (6/10)  By: Kimberly N Wilson-Murphy  Attorney-in-fact



Travelers Casualty and Surety Company of America Travelers Casualty and Surety Company St. Paul Fire and Marine Insurance Company Farmington Casualty Company

#### **POWER OF ATTORNEY**

KNOW ALL MEN BY THESE PRESENTS: That Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, St. Paul Fire and Marine Insurance Company, and Farmington Casualty Company are corporations duly organized under the laws of the State of Connecticut (herein collectively called the "Companies"), and that the Companies do hereby make, constitute and appoint Kimberly N Wilson-Murphy, of TEXARKANA, TX, their true and lawful Attorney(s)-in-Fact, to sign, execute, seal and acknowledge the following bond:

Surety Bond No.: 107637640

Principal: MARK BRADFORD

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed and their corporate seals to be hereto affixed, this 21st day of April, 2021.









State of Connecticut

City of Hartford ss.

Robert L. Raney, Senior Vice President

On this the 21st day of April, 2021, before me personally appeared Robert L. Raney, who acknowledged himself to be the Senior Vice President of each of the Companies, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of said Companies by himself as a duly authorized officer.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My Commission expires the 30th day of June, 2026

NOTARY NOTARY PUBLIC ADDR P. Maril Notar

Anna P. Nowik, Notary Public

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of each of the Companies, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is

**FURTHER RESOLVED**, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Assistant Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, Kevin E. Hughes, the undersigned, Assistant Secretary of each of the Companies, do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which remains in full force and effect.

Dated this 17 day of May, 2022.









Wes & Husten

Kevin E. Hughes, Assistant Secretary



#### IMPORTANT NOTICE REGARDING COMPENSATION DISCLOSURE

For information about how Travelers compensates independent agents, brokers, or other insurance producers, please visit this website: www.travelers.com/w3c/legal/Producer\_Compensation\_Disclosure.html

If you prefer, you can call the following toll-free number: 1-866-904-8348. Or you can write to us at Travelers, Enterprise Development, One Tower Square, Hartford, CT 06183.



#### Variance Application

2 messages

Ronny Skipper <ronny@seizsigns.com>
To: Colton Leonard <cleonard@cityofbryant.com>

Tue, May 24, 2022 at 1:05 PM

Good Afternoon, Colton:

Buffalo Wild Wings is wanting to seek a variance for their pole sign. Code indicates 25' maximum height so they want to apply for a variance for the 50' sign shown on the attached design. The hardship is based on the requirement to install the sign so far into the property due to all the utilities that converge at the corner of their property making it impossible to install a "normal" street sign near the street.

Attached are the drawings for the proposed pole sign requiring the variance as well as the rest of the project for reference.

Regards,

#### **Ronny Skipper**

General Manager Seiz Sign Company

1231 Central Ave Hot Springs, AR 71901

501-282-4126 PHONE 501-623-4594 FAX

2 attachments



BWW (BRYANT, AR) 23-70338-10 R2.pdf 1749K



**2016 BWW (BRYANT, AR) 23-35611-10 R2.pdf** 7526K

**Colton Leonard** <cleonard@cityofbryant.com>
To: Ronny Skipper <ronny@seizsigns.com>

Wed, May 25, 2022 at 11:28 AM

Ronny,

Thanks for submitting this application, we will have you at the next DRC meeting Friday, June 3rd at 9AM for the recommendation of the variance to the Planning Commission. The next upcoming Planning Commission will be held on June 8th.

Best,

Colton

[Quoted text hidden]


\_\_

#### Colton Leonard

City Planner

210 SW 3rd Street City of Bryant, Arkansas (501) 943-0301 (501)943-0992 (Fax) cleonard@cityofbryant.com

Web: www.CityofBryant.com





PROPOSED PYLON SIGN (NONE EXISTING

## **IGNAGE SCHEDULE**

(1) INTERNALLY ILLUMINATED PYLON SIGN | QTY: ONE (1)



1128 Beville Road, Suite E Daytona Beach, FL 32114 (386) 255-1901 Fax (386) 258-0211

Manufacturing Facilities: Delaware, OH - Euless, TX - Jacksonville, TX Oceanside, CA - Racine, WI - Rochester Hills, MI

Atlanta, GA - Brandon, FL - Indianapolis, IN Tunica, MS - Daytona Beach, FL - Delaware, OH - Euless, TX Grafton, Wi - Houston, TX - Idaho Falls, ID - Jacksonville, TX Knoxville, TN - Las Vegas, NV - Louisville, KY Dceanside, CA - Racine, WI - Rochester Hills, MI - San Antonio, Tampa, FL - Willowbrook, IL - Orlando, FL

R1 BW 5.9.22 Revise size & add option. R2 BW 5.12.22 Re-design Main ID cabinet & delete option 2. Colors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc Client Approval/Date: Building Quality Signage Since 1901 Landlord Approval/Date:


RANDY CEARLOCK | Project / Location: Account Rep: JIM HARVEY Project Manager JOE KNESTRICK Underwriters
Laboratories Inc.

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.

STORE # 7206 ALCOA ROAD BRYANT, AR 72022

23-70338-10 February 08, 2022 Design Number:

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign 23-70338-10 R2 Company, LEC 3. .... authorized agent. ©FHSC



## CUSTOM D/F INTERNALLY ILLUMINATED PYLON SIGN W/ READER BOARD | 200.0 SQ.FT.

SCALE: 3/16" = 1'-0"

#### NAIN ID CABINET

CE: WHITE FLEXIBLE FACE MATERIAL W/ 1ST SURFACE VINYL GRAI

PY: (300) 8" BLACK COMMERCIAL FONT ZIP CHANG

STORAGE CARINET & CHANGER ARM

STANDARD INSTALL IS TO BE DIRECT PIPE EMBEDMENT INTO CONCRETE FOOTING PER FH ENGINEERING SPECS.


MANUFACTURING WILL PROVIDE A STUB PIPE WITH SIGN CABINETS ONLY IF O.A.H. (CABINET + STUB PIPE) DOES NOT EXCEED 9'-7" MAXIMUM SHIPPING HEIGHT RESTRICTIONS.

ALL SUPPORTING STEEL, INCLUDING STUB PIPE, IF NOT INCLUDED WITH CABINET, TO BE SHIPPED TO INSTALLATION SITE BY AN OUTSIDE SUPPLIER OR BY THE INSTALLATION CONTRACTOR, AS DETERMINED BY PROJECT MANAGEMENT.

NOTE: UPON CUSTOMER ACCEPTANCE, FEDERAL HEATH ENGINEERING DEPARTMENT WILL PROVIDE FABRICATION DRAWINGS & ENGINEERED SEAL DRAWINGS IF REQUIRED THIS DRAWING IS FOR PRESENTATION ONLY

INSTALLATION OF THIS SIGN SHALL CONFORM TO ARTICLE 600 OF THE NEC, UL48, AND OR OTHER APPLICABLE LOCAL CODES, INCLUDING PROPER GROUNDING AND BONDING OF SIGN.

LOCATION OF DISCONNECT SWITCH AFTER INSTALLATION SHALL COMPLY WITH ARTICLE 600.6(A) OF THE NEC.



#### Color Breakdown | Logo

PMS 7548c 2500-125

PMS 440c 2500-69

100 % White 3



# **ENGINEERING REQUIRED**

# **FEDERAL**

1128 Beville Road, Suite E Daytona Beach, FL 32114 (386) 255-1901 Fax (386) 258-0211

Manufacturing Facilities: Delaware, OH - Euless, TX - Jacksonville, TX Oceanside, CA - Racine, WI - Rochester Hills, MI Office Locations:

Atlanta, GA - Brandon, FL - Indianapolis, IN Grafton, WI - Houston, TX - Idaho Falls, ID - Jacksonville, TX Knoxville, TN - Las Vegas, NV - Louisville, KY ceanside, CA - Racine, WI - Rochester Hills, MI - San Antonio Tampa, FL - Willowbrook, IL - Orlando, FL

R1 BW 5.9.22 Revise size & add option. R2 BW 5.12.22 Re-design Main ID cabinet & delete option 2. Tunica, MS - Davtona Beach, FL - Delaware, OH - Euless, TX Colors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc Client Approval/Date: Building Quality Signage Since 1901 Landlord Approval/Date:

RANDY CEARLOCK | Project / Location: Account Rep: JIM HARVEY Project Manager JOE KNESTRICK

Underwriters net components and shall meet All N.E.C. STANDARDS

ALL ELECTRICAL SIGNS ARE TO COMPONENTS AND SHALL MEET ALL N.E.C. STANDARDS

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.

STORE # 7206 ALCOA ROAD BRYANT, AR 72022

23-70338-10 Job Number: February 08, 2022 Of Sheet Number Design Number:

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced permission of Federal Heath Sign 23-70338-10 R2 Company, LLC Company, authorized agent. ©FHSC



nside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, TX Grafton, WI - Willowbrook, IL - Tunica, MS

Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:

R2 4.21.16 BW Remove sign D from rear elevation olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc

R1 4.13.16 GB Revise Title Block Address (City)

RANDY CEARLOCK Account Rep:

Underwriters
Laboratories Inc.

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 F THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.

Project / Location:



Ε

G


Ε


D

7206 ALCOA ROAD **BRYANT, AR 72015** 

23-35611-10 MARCH 21, 2016 Of **11** 

This original drawing s provided as part of a olanned project Company, LLC or its Design Number: 23-35611-10 R2 Company, LLC of its authorized agent. ©FHSC





RIGHT SIDE (WEST) SCALE: 1/8" = 1'-0'

Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Revisions:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, TX Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:

R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation. Colors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc

JODY GRAHAM Underwriters Laboratories Inc.

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.

Account Rep:

Project Manager

RANDY CEARLOCK

JIM HARVEY

Project / Location:

7206 ALCOA ROAD


**BRYANT, AR 72015** 

MARCH 21, 2016 Of **11** 


Job Number:

23-35611-10

This original drawing is provided as part of a planned project copied or reproduced Federal Heath Sign Company, LLC or its Design Number: 23-35611-10 R2 Company, LLC of its authorized agent. ©FHSC



REAR (SOUTH) SCALE: 1/8" = 1'-0"



# LEFT SIDE (EAST) SCALE: 1/8" = 1'-0"



Manufacturing Facilities: Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Revisions:

Client Approval/Date:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, TX Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation.

Underwriters
Laboratories Inc.

LELECTRICAL TO USE UL. LISTED
COMPONENTS AND SHALL MEET
ALL N.E.C. STANDARDS

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND
ARTICLE 500 OF THE N.E.C. STANDARDS, INCLUDING
THE PROPER GROUNDING AND BONDING OP ALL SIGNS. Colors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc


RANDY CEARLOCK Account Rep: JIM HARVEY Project Manager Drawn By JODY GRAHAM

Project / Location: 7206 ALCOA ROAD

**BRYANT, AR 72015** 

23-35611-10 Job Number: MARCH 21, 2016 Of **11** 

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign Design Number: 23-35611-10 R2 Company, LLC or its authorized agent. ©FHSC



SIGN TYPE	A	В	C BLACK BORDER	WHITE (ILLUM) BORDER	(RETAINER)	SQ.FT.	SQ.FT.
W-EM84	7'-0"	7'-0"	3 1/2"	7/8"	2"	49.0	<b>38.4</b>

#### LOGO CHANNEL:

RETURNS OF CABINET PAINTED BRUSHED ALUMINUM. NOTE: METAL RETAINER TWO TONE. RETURN OF RETAINER PAINTED BRUSHED ALUMINUM, FACE OF RETAINER PAINTED WHITE.

NOTE: IF CUSTOM LOGO SIZE OF 36" or LESS IS REQUIRED, RETAINER WILL BE TRIM-CAP PAINTED BRUSHED ALUMINUM.

CIRCULAR FACE: WHITE POLYCARBONATE w/ FIRST SURFACE

TRANSLUCENT VINYL DECORATION.

**ILLUMINATION:** VIA SLOAN VL PLUS-2 WHITE LEDS






ΜΑΧΙΜΙΙΜ (ΜΑΧ)

MINIMUM (MIN)

Total: **T.B.D.** Amps

#### # of 120V, 20A Circuits Reg'd T.B.D.

ALL BRANCH CIRCUITS SHALL BE DEDICATED TO SIGNS (INCLUDING GROUND AND NEUTRAL) AND SHALL NOT BE SHARED WITH OTHER LOADS.



#525 ARLON | BRIGHT YELLOW VINYL (Translucent)

#22 ARLON | BLACK VINYL




#51 ARLON SILVER GRAY VINYL (Translucent)


2a - BACKGROUND ELEMENT (By Others)



WHITE

#171S BRUSHED ALUMINUM PAINT (Spraylat)





#### **CUSTOMER TO PROVIDE:**

(For New / Remodel Construction) ADEQUATE BEHIND THE WALL BACKING AND ACCESS AS REQUIRED TO INSTALL SIGNAGE, CUSTOMER TO FORWARD COPY OF FINAL APPROVED SIGNAGE DRAWINGS TO BUILDING SITE CONTACT SO THAT THESE PROVISIONS CAN BE MADE DURING CONSTRUCTION AND PRIOR TO SIGN INSTALLATION.

ALL BRANCH (PRIMARY ELECTRICAL SERVICE) CIRCSI'S FINAL CONNECTION TO EACH SIGNWITHIN 5 FT. JTO BE BY CERTIFIED ELECTRICIAN:

- A. All branch circuits for signs must be totally dedicated to signs (including dedicated ground and dedicated neutral per circuit).

  B. Sign circuits must not be shared with other loads such as lighting, air conditioning, and other equipment.
- C. Properly sized ground wire that can be traced back to the breaker panel must be provided.

  D. Number and size of circuits for each sign to meet Federal Heath Sign's requirement.

Any deviation from the above recommendations may result in:

- Damage to or improper operation of the sign(s).
- 2. Delays and additional costs.
- □ Certain electrical components of signs will fail prematurely if signs are not shut-off for a period of time, once, each day. For best performance, we recommend signs to be connected to an automatic controlling device such as an Energy Management System, Time Clock or Photo Cell that will automatically shut-off the sign for a period of time, each day. Failure to do so will cause damage to the electrical components of the sign and
  - □ Some dimming devices will also adversely affect sign electrical components, causing failure. Any dimming of the sign without consultation with Federal Heath Sign Co. will void the warranty.

#### **INSTALLER IS RESPONSIBLE FOR:**

PROVIDING AND INSTALLING ALL COMPONENTS REQUIRED TO RUN SECONDARY WIRING (CONNECTORS, GTO CONDUIT, ETC.) TO BE DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

#### ELECTRICAL NOTES:

1. INSTALLATION OF THESE (ELECTRICAL) SIGNS SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE 600 OF THE N.E.C., U.L. 48 AND / OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN

PROVIDING ALL NEEDED INSTALLATION HARDWARE AS DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

SEALING BUILDING PENETRATIONS WITH SILICONE TO PREVENT MOISTURE PENETRATION @ EXTERIOR LOCATIONS.



Manufacturing Facilities Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, T Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:

Revisions R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc Client Approval/Date:

Account Rep: RANDY CEARLOCK Project Manager JODY GRAHAM

Underwriters Laboratories Inc.

Underwriters Laboratories Inc. ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS. Project / Location:




7206 ALCOA ROAD **BRYANT. AR 72015** 

23-35611-10 Job Number MARCH 21, 2016 Of **11** 

is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign Company, LLC or its Design Number: 23-35611-10 R2 authorized agent. ©FHSC

This original drawing



# INDIVIDUAL INTERNALLY ILLUMINATED CHANNEL LETTER LAYOUT



**CHANNEL LETTERS "BWW":** 

RETURNS: 5" DEEP, PRE-FINISHED BLACK ALUMINUM LETTERS PAINTED BLACK ON ALL EXTERIOR SURFACES

FACES: #7328 WHITE ACRYLIC BANDED W/A 1" BLACK TRIM CAP.

**ILLUMINATION:** VIA SLOAN VL PLUS-2 WHITE LEDS

WHITE

#7328 | WHITE ACRYLIC (Translucent)


BLACK

RETURNS | TRIM-CAP

Total: **T.B.D.** Amps

# of 120V, 20A Circuits Reg'd T.B.D.

ALL BRANCH CIRCUITS SHALL BE DEDICATED TO SIGNS (INCLUDING GROUND AND NEUTRAL) AND SHALL NOT BE SHARED WITH OTHER LOADS.



#### **CUSTOMER TO PROVIDE:**

(For New / Remodel Construction) ADEQUATE BEHIND THE WALL BACKING AND ACCESS AS REQUIRED TO INSTALL SIGNAGE. CUSTOMER TO FORWARD COPY OF FINAL APPROVED SIGNAGE DRAWINGS TO BUILDING SITE CONTACT SO THAT THESE PROVISIONS CAN BE MADE DURING CONSTRUCTION AND PRIOR TO SIGN INSTALLATION.

ALL BRANCH (PRIMARY ELECTRICAL SERVICE) CIRCUITS FINAL CONNECTION TO EACH SIGNWITHIN 5 FT. TO BE BY CERTIFIED ELECTRICIAN:
A. All branch circuits for signs must be totally dedicated to signs (including dedicated ground and dedicated neutral per circuit).

- Sign circuits must not be shared with other loads such as lighting, air conditioning, and other equipment.
- Properly sized ground wire that can be traced back to the breaker panel must be provided
- D. Number and size of circuits for each sign to meet Federal Heath Sign's requirement.

Any deviation from the above recommendations may result in:

- . Damage to or improper operation of the sign(s). . Delays and additional costs.

Certain electrical components of signs will fail prematurely if signs are not shut-off for a period of time, once, each day. For best performance, we recommend signs to be connected to an automatic controlling device such as an Energy Management System, Time Clock or Photo Cell that will automatically shut-off the sign for a period of time, each day. Failure to do so will cause damage to the electrical components of the sign and will void the warranty

Some dimming devices will also adversely affect sign electrical components, causing failure. Any dimming of the sign without consultation with Federal Heath Sign Co. will void the warranty.

#### INSTALLER IS RESPONSIBLE FOR:

PROVIDING AND INSTALLING ALL COMPONENTS REQUIRED TO RUN SECONDARY WIRING (CONNECTORS, GTO CONDUIT, ETC.) TO BE DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

. INSTALLATION OF THESE (ELECTRICAL) SIGNS SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE 600 OF THE N.E.C., U.L. 48 AND / OR OTHER APPLICABLE LOCAL CODES.

PROVIDING ALL NEEDED INSTALLATION HARDWARE AS DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

SEALING BUILDING PENETRATIONS WITH SILICONE TO PREVENT MOISTURE PENETRATION @ EXTERIOR LOCATIONS.



Manufacturing Facilities

Revisions

Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, T Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Mat Client Approval/Date: Building Quality Signage Since 1901 Landlord Approval/Date:

Account Rep: RANDY CEARLOCK Project Manager JIM HARVEY

JODY GRAHAM Underwriters Laboratories Inc.

Underwriters Laboratories Inc.


DELECTRICAL TO USE U.L. LISTED COMPONENTS AND SHALL MEET ALL N.E.C. STANDARDS ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS. Project / Location:



7206 ALCOA ROAD **BRYANT. AR 72015** 

23-35611-10 Job Number MARCH 21, 2016 Sheet Number Of

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign Design Number: 23-35611-10 R2 authorized agent. ©FHSC Company, LLC or its





#### INDIVIDUAL INTERNALLY ILLUMINATED CHANNEL LETTER LAYOUT



**CHANNEL LETTERS "BWW":** 

RETURNS: 5" DEEP, PRE-FINISHED BLACK ALUMINUM LETTERS PAINTED BLACK ON ALL EXTERIOR SURFACES

FACES: #7328 WHITE ACRYLIC BANDED W/A 1" BLACK TRIM CAP.

**ILLUMINATION:** VIA SLOAN VL PLUS-2 WHITE LEDS

WHITE

#7328 | WHITE ACRYLIC (Translucent)


BLACK

RETURNS | TRIM-CAP

Total: **T.B.D.** Amps

# of 120V, 20A Circuits Reg'd T.B.D.

ALL BRANCH CIRCUITS SHALL BE DEDICATED TO SIGNS (INCLUDING GROUND AND NEUTRAL) AND SHALL NOT BE SHARED WITH OTHER LOADS.



#### **CUSTOMER TO PROVIDE:**

(For New / Remodel Construction) ADEQUATE BEHIND THE WALL BACKING AND ACCESS AS REQUIRED TO INSTALL SIGNAGE. CUSTOMER TO FORWARD COPY OF FINAL APPROVED SIGNAGE DRAWINGS TO BUILDING SITE CONTACT SO THAT THESE PROVISIONS CAN BE MADE DURING CONSTRUCTION AND PRIOR TO SIGN INSTALLATION.

ALL BRANCH (PRIMARY ELECTRICAL SERVICE) CIRCUITS FINAL CONNECTION TO EACH SIGNITHIN 5 FT. TO BE BY CERTIFIED ELECTRICIAN:
A. All branch circuits for signs must be totally dedicated to signs (including dedicated ground and dedicated neutral per circuit).

- Sign circuits must not be shared with other loads such as lighting, air conditioning, and other equipment.
- Properly sized ground wire that can be traced back to the breaker panel must be provided
- D. Number and size of circuits for each sign to meet Federal Heath Sign's requirement.

Any deviation from the above recommendations may result in:

- . Damage to or improper operation of the sign(s). . Delays and additional costs.

Certain electrical components of signs will fail prematurely if signs are not shut-off for a period of time, once, each day. For best performance, we recommend signs to be connected to an automatic controlling device such as an Energy Management System, Time Clock or Photo Cell that will automatically shut-off the sign for a period of time, each day. Failure to do so will cause damage to the electrical components of the sign and will void the warranty

Some dimming devices will also adversely affect sign electrical components, causing failure. Any dimming of the sign without consultation with Federal Heath Sign Co. will void the warranty.

#### INSTALLER IS RESPONSIBLE FOR:

PROVIDING AND INSTALLING ALL COMPONENTS REQUIRED TO RUN SECONDARY WIRING (CONNECTORS, GTO CONDUIT, ETC.) TO BE DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

. INSTALLATION OF THESE (ELECTRICAL) SIGNS SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE 600 OF THE N.E.C., U.L. 48 AND / OR OTHER APPLICABLE LOCAL CODES.

PROVIDING ALL NEEDED INSTALLATION HARDWARE AS DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

SEALING BUILDING PENETRATIONS WITH SILICONE TO PREVENT MOISTURE PENETRATION @ EXTERIOR LOCATIONS.



Revisions

R1 4.13.16 GB Revise Title Block Address (City)

Manufacturing Facilities Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, T Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS

Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

R2 4.21.16 BW Remove sign D from rear elevation olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Mat Client Approval/Date: Building Quality Signage Since 1901 Landlord Approval/Date:

Account Rep: RANDY CEARLOCK Project Manager JIM HARVEY


JODY GRAHAM Underwriters nec Components and Shall MEET ALL N.E.C. STANDARDS ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.


Project / Location:


7206 ALCOA ROAD **BRYANT. AR 72015** 

23-35611-10 Job Number MARCH 21, 2016 6 Sheet Number Of

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign Design Number: 23-35611-10 R2 authorized agent. ©FHSC Company, LLC or its









#### **WALL SIGN LAYOUT**

Scale: 3/8"=1'-0"

SIGN TYPE	Α	В	C	D	E	F	G	Н	BLACK BORDER	WHITE (ILLUM) BORDER	K RETAINER	SQ.FT. (GRAPHICS ONLY) (MAX)	QTY.
W-NM72H3	6'-0"	6'-0"	11'-11"	5'-5"	4'-1"	11 1/4"	1'-7 1/2"	1'-3 1/2"	3"	3/4"	1 3/4"	71.46	1

#### **LOGO CHANNEL:**

RETURNS OF CABINET PAINTED BRUSHED ALUMINUM. NOTE: METAL RETAINER TWO TONE. RETURN OF RETAINER PAINTED BRUSHED ALUMINUM, FACE OF RETAINER PAINTED WHITE.

NOTE: IF CUSTOM LOGO SIZE OF 36" or LESS IS REQUIRED, RETAINER WILL BE TRIM-CAP PAINTED BRUSHED ALUMINUM.

CIRCULAR FACE: WHITE POLYCARBONATE w/ FIRST SURFACE TRANSLUCENT VINYL DECORATION.

**ILLUMINATION: VIA SLOAN VL PLUS-2 WHITE LEDS** 

RETURNS OF LETTERS PAINTED BLACK ON ALL EXTERIOR SURFACES FACES: #7328 WHITE ACRYLIC BANDED W/A 1" BLACK TRIM CAP.

**ILLUMINATION: VIA SLOAN VL PLUS-2 WHITE LEDS** 

NOTE: BACKGROUND PANEL BY OTHERS.

#### FACE TREATMENT NOTE: WHITE TRANSLUCENT BORDER (ON FACE OF LOGO) WILL BLEED OUT UNDERNEATH RETAINER.



2a - BACKGROUND ELEMENT (By Others)

#22 ARLON | BLACK VINYL



#51 ARLON SILVER GRAY VINYL (Translucent)



#171S BRUSHED ALUMINUM PAINT (Spraylat)



#7328 | WHITE POLYCARBONATE (Translucent) 5a - FACE OF RETAINER PAINTED WHITE





Total: **T.B.D.** Amps

#### # of 120V, 20A Circuits Req'd T.B.D.

ALL BRANCH CIRCUITS SHALL BE DEDICATED TO SIGNS (INCLUDING GROUND AND NEUTRAL) AND SHALL NOT BE SHARED WITH OTHER LOADS.

#### **CUSTOMER TO PROVIDE:**

(For New / Remodel Construction) ADEQUATE BEHIND THE WALL BACKING AND ACCESS AS REQUIRED TO INSTALL SIGNAGE. CUSTOMER TO FORWARD COPY OF FINAL APPROVED SIGNAGE DRAWINGS TO BUILDING SITE CONTACT SO THAT THESE PROVISIONS CAN BE MADE DURING CONSTRUCTION AND PRIOR TO SIGN INSTALLATION.

ALL BRANCH (PRIMARY ELECTRICAL SERVICE) CIRCUITS FINAL CONNECTION TO EACH SIGNWITHIN 5 FT. JTO BE BY CERTIFIED ELECTRICIAN:

A. All branch circuits for signs must be totally dedicated to signs (including dedicated ground and dedicated neutral per circuit).

B. Sign circuits must not be shared with other loads such as lighting, air conditioning, and other equipment.

C. Properly sized ground wire that can be traced back to the breaker panel must be provided.

D. Number and size of circuits for each sign to meet Federal Heath Sign's requirement.

Any deviation from the above recommendations may result in:

. Damage to or improper operation of the sign(s).

2 Delays and additional costs

Notes: 🗆 Certain electrical components of signs will fail prematurely if signs are not shut-off for a period of time, once, each day. For best performance, we recommend signs to be connected to an automatic controlling device such as an Energy Management System, Time Clock or Photo Cell that will automatically shut-off the sign for a period of time, each day. Failure to do so will cause damage to the electrical components of the sign and

□ Some dimming devices will also adversely affect sign electrical components, causing failure. Any dimming of the sign without consultation with Federal Heath Sign Co. will void the warranty.

#### **INSTALLER IS RESPONSIBLE FOR:**

PROVIDING AND INSTALLING ALL COMPONENTS REQUIRED TO RUN SECONDARY WIRING (CONNECTORS, GTO CONDUIT, ETC.) TO BE DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

#### **ELECTRICAL NOTES:**

INSTALLATION OF THESE (ELECTRICAL) SIGNS SHALL CONFORM TO THE REQUIREMENTS OF ARTICLE 600 OF THE N.E.C., U.L. 48 AND / OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN

PROVIDING ALL NEEDED INSTALLATION HARDWARE AS DETERMINED BY LOCAL CODE AND SITE CONDITIONS.

SEALING BUILDING PENETRATIONS WITH SILICONE TO PREVENT MOISTURE PENETRATION @ EXTERIOR LOCATIONS.



DuraColor - Racine, WI

Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, T Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:

Revisions R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation. olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc Client Approval/Date:

Account Rep: RANDY CEARLOCK Project Manager

JODY GRAHAM Underwriters Laboratories Inc.

Underwriters Laboratories Inc.


DELECTRICAL TO USE U.L. LISTED COMPONENTS AND SHALL MEET ALL N.E.C. STANDARDS ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS. Project / Location:



7206 ALCOA ROAD **BRYANT. AR 72015** 

23-35611-10 Job Number MARCH 21, 2016 Of

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced without the written permission of Federal Heath Sign Company, LLC or its Design Number: 23-35611-10 R2 authorized agent. ©FHSC





### **V-ME12**

VINYL DOOR GRAPHICS | first surface | QTY: SIX (6) REQUIRED

FIRST SURFACE APPLIED DIGITAL PRINT @ 360 DPI NOTE: TWO(2) DIGITAL PRINT LOGOS REQUIRED FOR EACH DOOR. DIGITAL PRINTS TO BE SINGLE SIDED APPLIED BACK TO BACK ON EACH DOOR.

NOTE: (1ST SURFACE APPLIED TO INSIDE & OUTSIDE SURFACE OF GLASS) TOTAL DOORS (3) | TOTAL UNITS REQUIRED (6)





### V-T020

TAKE OUT DOOR GRAPHICS | first surface

scale 1"=1'-0"

FIRST SURFACE APPLIED DIGITAL PRINT @ 360 DPI






Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations: Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID

uless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, TX Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:



RANDY CEARLOCK Account Rep: Project Manager


JODY GRAHAM Underwriters Laboratories Inc.

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS. Project / Location:


7206 ALCOA ROAD **BRYANT, AR 72015** 

23-35611-10 Job Number: MARCH 21, 2016 Of **11** Design Number: 23-35611-10 R2 Company, LLC of its authorized agent. ©FHSC

This original drawing is provided as part of a planned project copied or reproduced Federal Heath Sign Company, LLC or its



#### **FACE TREATMENT** NOTE: WHITE TRANSLUCENT BORDER (ON FACE OF LOGO) WILL BLEED OUT UNDERNEATH TRIM-CAP





Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, TX Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Revisions: R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation. olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc Building Quality Signage Since 1901 Landlord Approval/Date:

RANDY CEARLOCK Account Rep: Project Manager JODY GRAHAM

UL Underwriters Laboratories Inc.

ALL ELECTRICAL SIGNS ARE TO COMPLY WITH U.L. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS.




**BRYANT, AR 72015** 

MARCH 21, 2016 Of **11** 

Job Number:

23-35611-10

This original drawing is provided as part of a planned project and is not to be exhibited, copied or reproduced permission of Federal Heath Sign Design Number: 23-35611-10 R2 Company, LLC of its authorized agent. ©FHSC Company, LLC or its



SINGLE FACED INTERNALLY ILLUMINATED ACRYLIC FACED DISPLAY


CABINET: ALUMINUM LETTER CONSTRUCTION W/ PRE-FINISHED BLACK RETURNS. FACES: #7328 WHITE ACRYLIC W/ FIRST SURFACE APPLIED VINYL GRAPHICS. FACES ATTACHED W/ 1" BLACK TRIM CAP. COLORS AS PER PALETTE. ILLUMINATION: SLOAN VL PLUS WHITE LED

TYPE	Α	В	SQ.FT.
F-RR18	18"	18"	2.3

### **ELECTRICAL REQUIREMENTS** Total: **T.B.D.** Amps

# of 120V, 20A Circuits Reg'd T.B.D.

ALL BRANCH CIRCUITS SHALL BE DEDICATED TO SIGNS (INCLUDING GROUND AND NEUTRAL) AND SHALL NOT BE SHARED WITH OTHER LOADS.



#### **UL APPROVED INSTALLATION DETAIL CHANNEL LETTER WITH LED & POWER SUPPLY**





Oceanside, CA - Euless, TX - Jacksonville, TX - Delaware, OH DuraColor - Racine, WI Office Locations:

Oceanside, Ca - Las Vegas, NV - Laughlin, AZ - Idaho Falls, ID Euless, TX - Jacksonville, TX - San Antonio, TX - Corpus Christi, T Indianapolis, IN - Delaware, OH - Knoxville TN - Louisville, KY Grafton, WI - Willowbrook, IL - Tunica, MS Atlanta, GA - Tampa, FL - Daytona Beach, FL - Orlando, FL

Building Quality Signage Since 1901 Landlord Approval/Date:

Revisions: R1 4.13.16 GB Revise Title Block Address (City) R2 4.21.16 BW Remove sign D from rear elevation. olors Depicted In This Rendering May Not Match Actual Finished Materials. Refer To Product Samples For Exact Color Matc


RANDY CEARLOCK Account Rep: Project Manager JODY GRAHAM

Underwriters Laboratories Inc. ALL ELECTRICAL SIGNS ARE TO COMPLY WITH LL. 48 AND ARTICLE 600 OF THE N.E.C. STANDARDS, INCLUDING THE PROPER GROUNDING AND BONDING OF ALL SIGNS. Project / Location:


7206 ALCOA ROAD **BRYANT, AR 72015** 

23-35611-10 Job Number: MARCH 21, 2016 **10** Of **11** Design Number: 23-35611-10 R2 Comparity, LLC OF ILS authorized agent. ©FHSC

This original drawing is provided as part of a planned project copied or reproduced permission of Federal Heath Sign Company, LLC or its



**NOTE: TO BE USED ONLY WHEN** THE SIGN IS PLACED ON A SIDEWALK OR SIMILAR CONCRETE SURFACE.




PARKING LOT STENCIL | ONE (1) REQ'D. scale 3/4"=1'-0" 9.0 SQ.FT

MANUFACTURE ONE (1) PARKING LOT STENCIL AS SHOWN AND NOTED. STENCIL FABRICATED OUT OF .125 PVC BOARD (SENTRA OR EQUIV). GRAPHICS ROUTED-OUT OF PVC BOARD. HANDLES GLUED ONTO STENCIL BOARD FOR STENCIL REMOVAL.

NOTE: FEDERAL HEATH TO FABRICATE PARKING LOT STENCIL ONLY AND HAND OFF TO GC. PAINTING IMAGE ONTO PARKING LOT SPACES BY GC.







**BRYANT. AR 72015** 

23-35611-10 Job Number: MARCH 21, 2016 **11** Of **11** Design Number: 23-35611-10 R2 Company, LLC OF ILS authorized agent. ©FHSC

This original drawing s provided as part of a olanned project copied or reproduced permission of Federal Heath Sign Company, LLC or its

# STORMWATER POLLUTION PREVENTION PLAN (SWPPP) CONSTRUCTION ACTIVITY for


Splash Car Wash 2116 N Reynolds Road Bryant, Arkansas 72022

## National Pollutant Discharge Elimination (NPDES) General Permit #ARR150000

Prepared for:
Splash Car Wash
Attn: Paul Stagg
2116 N Reynolds Rd
Bryant, Arkansas 72022

**Date: May 2022** 

Prepared by:
Phillip Lewis Engineering, Inc.
23620 Interstate 30
Bryant, Arkansas 72022



Project Name and Location: Splash Car Wash, 2116 N Reynolds Rd Bryant, Arkansas 72022

County Parcel ID: 805-14205-00 | Saline County, Arkansas

Operator Name and Address: Splash Car Wash, 2116 N Reynolds Rd, Bryant, Arkansas 72022

#### A. Site Description

#### a. Project description, intended use after NOI is filed

An Overall Layout Map is included showing total project area of 1.091 with 0.83 Acres disturbed. that provides for buffer zones, construction of utilities, building remodel, new canopies, parking lot addition and resurfacing and landscaping improvements. All areas will be covered with vegetation or paving. Details on the Sediment and Erosion Control Plan shows drainage patterns, surface waters, storm water discharge locations and receiving streams. The Site Map included at the end of this SWPPP shows the buffer zones, approximate slopes after grading activities, area of soil disturbance, areas that will not be disturbed, location of controls and stabilization areas. A concrete washout is shown on the Site Map.

#### b. Sequence of major activities which disturb soils:

- 1. Construct stabilized construction entrance. This will be the first construction work on the project.
- 2. Construct the silt fences and BMP controls on the site.
- 3. Perform site demolition.
- 4. Clear and grub the site.
- 5. Begin grading the site.
- 6. Start construction of building pad and structures.
- 7. Temporarily seed denuded areas.
- 8. Install underground utilities and curbs and gutters Sediment barriers shall be utilized as required to bound the down slope side of utility construction.
- 9. Prepare site for paving.
- 10. Pave site.
- 11. Complete Grading and install permanent sodding and landscaping.
- 12. Remove all temporary erosion and sediment control devices (only if site stabilized).

The actual schedule for implementing pollutant control measures will be determined by project construction progress. Down slope protective measures must always be in place before soil is disturbed.

c. Total Area: 1.091 Acres Disturbed Area: 0.83 Acres

#### **B.** Responsible Parties

Be sure to assign all SWPPP related activities to an individual or position; even if the specific individual is not yet known (i.e. contractor has not been chosen).

Individual/Company	Phone Number	Service Provided for SWPPP (i.e., Inspector, SWPPP revision, Stabilization Activities, BMP Maintenance, etc.)
		Inspection of Controls
		Stabilization, BMP Maintenance, Construction Oversite, Stormwater Inspection

#### C. Receiving Waters

#### a. The following waterbodies receive stormwater from the project property:

There is an unnamed waterbody which receives stormwater from the site that eventually turn into crooked creek.

#### b. Is the project located within the jurisdiction of an MS4? Yes

If yes, Name of MS4: City of Bryant

c. Ultimate Receiving Water: Ouachita River

#### D. Site Map Requirements, shown on Site Map and to be Revised for Construction:

- a. Pre-construction topographic view
- b. Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
- c. Delineate on the site map areas of soil disturbance and areas that will not be disturbed under the coverage of this permit;
- d. Location of major structural and nonstructural controls identified in the plan;
- e. Location of main construction entrance and exit;
- f. Location where stabilization practices are expected to occur;
- g. Locations of off-site materials, waste, borrow area, or equipment storage area;
- h. Location of areas used for concrete wash-out;
- i. Location of all surface water bodies (including wetlands);
- j. Locations where stormwater is discharged to a surface water and/or municipal separate

- storm sewer system if applicable,
- k. Locations where stormwater is discharged off-site (should be continuously updated);
- I. Areas where final stabilization has been accomplished and no further construction phase permit requirements apply.
- m. A legend that identifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
- n. Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

#### E. Other Potential Pollution Sources:

- i. Concrete Source: Foundation and Curb and Gutter
- ii. Curing Compound Source: Concrete Finishing
- iii. Waste Concrete Truck Washout
- iv. Sediment Disturbed Soil Area
- v. Paints and Solvent Painting Operations
- vi. Petroleum Based Product Equipment and Vehicles
- vii. Emulsified Asphalt Paving Operations
- viii. Trash/Litter/Debris General Construction Activities
- ix. Sanitary Waste Portable Toilets
- x. Potentially Hazardous Materials General Construction Activities

The concrete washout will be located at the construction entrance/exit while the other sources of potential pollution will be located on the temporary parking/storage areas of the site.

#### F. Stormwater Controls

#### a. Initial Site stabilization, Erosion and Sediment Controls, and Best Management Practices:

- i. Initial Site Stabilization: Construct sediment fence if needed and entrance/exit pad if tracking onto roads occurs
- ii. Erosion and Sediment Controls: Sediment fence, straw waddles, waddles or bales for stormwater inlet protection on and in the vicinity of the project.
- iii. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the operator will replace or modify the control for site situations: Yes
- iv. Off-site accumulations of sediment will be removed at a frequency sufficient to minimize off-site impacts: Yes
- v. Sediment will be removed from sediment traps or sedimentation ponds when design capacity has been reduced by 50%: Yes
- vi. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges: Yes

vii. Off-site material storage areas used solely by the permitted project <u>are not being</u> used for this project

#### **b. Stabilization Practices**

- i. Description and Schedule: <u>Disturbed areas will be vegetated once work is ceased in a particular area.</u> Driveway and parking areas will be paved immediately after subgrade is developed.
- ii. Are buffer areas required? No, but buffer areas are provided and consists of undisturbed areas.
- iii. A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be done with the project.
- iv. **Deadlines for Stabilization**: Stabilization procedures
  - 1. Stabilization procedures will be initiated 14 days after construction activity temporarily ceases on a portion of the site.
  - 2. Temporary Seeding or Stabilization: Must initiate stabilization measures immediately, but not more than 14 days after construction activity ceases on any particular area, all disturbed ground where there will be no construction for longer than 14 days must be seeded with fast-germinating temporary seed and protected with mulch. Stockpiles and diversion ditches/berms must be stabilized to prevent erosion and dust issues. Where temporary stabilization measure are not appropriate, adequate erosion and sediment controls and appropriate maintenance must be implemented. Temporary stabilization may be used whenever construction activities are expected to resume in the area to be stabilized or when weather or other conditions are not appropriate for initiation of permanent stabilization.
  - 3. Permanent Seeding: All areas at final grade must be seeded or sodded immediately, but not more than 14 days after completion of the major construction activity. Except for small level spots, seeded areas should generally be protected with mulch. See immediately after final grade is achieved and soils are prepared to take advantage of soil moisture and see germination. At the completion of ground-disturbing activities the entire site must have permanent vegetative cover, meeting vegetative density requirements, or mulch per landscape plan, in all areas not covered by hardscape (pavement, building, etc.) To minimize the potential for erosion and maximize seed germination & growth, the General Contractor must evaluate the short and long-term local forecast prior to applying permanent seed or sod.

#### c. Structural Practices

i. Describe any structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site: sediment fences and rock check dams will be used to prevent scouring in ditches or from sheet flow. ii. Sediment Basins:

Are 10 or more acres draining to a common point? No Is a sediment basin included in the project? No

iii. Describe Velocity Dissipation Devices: N/A

#### **G. Other Controls**

- a. Solid materials, including building materials, shall be prevented from being discharged to Waters of the State: Yes
- b. Off-site vehicle tracking of sediments and the generation of dush shall be minimized through the use of: A stabilized construction entrance and exit pad if tracking occurs
- c. Temporary Sanitary Facilities: These will be provided by; \_\_\_\_\_\_

All personnel involved with construction activities must comply with state and local sanitary or septic system regulations. Temporary sanitary facilities will be provided at the site throughout the construction phase. They must be utilized by all construction personnel and will be serviced by a commercial operator. Portable toilets must be securely anchored and are not allowed with 30' of inlets or permitted limit of disturbance or with 50' of a water of the State.

- d. Concrete Waste Area Provided: Yes
- e. Fuel Storage Areas, Hazardous Waste Storage, and Truck Wash Areas: <u>Are not used</u> for this project
- f. Dust Control: Construction must enter and exit the site at the stabilized construction exit. The purpose is to trap dust and mud that would otherwise be carried off-site by construction traffic. Large areas of soil that are denuded of vegetation and have no protection or from particles being picked up and carried by wind should be protected with a temporary cover or kept under control with water or other soil adhering product to limit wind transported particles existing the site perimeter. Water trucks or other dust controls agents will used as needed during construction minimize dust generated from the site.

#### H. Non-Stormwater Discharges

a. The following allowable non-stormwater discharges comingled with stormwater are present or anticipated at the site:

<u>Potable water sources including uncontaminated waterline flushings;</u> <u>Landscape Irrigation;</u>

Routine external building wash down which does not detergents or other chemicals; Uncontaminated are conditioning, compressor condensate (See Part I.B.12.C of the Permit;

<u>Uncontaminated springs, excavation dewatering and groundwater (See Part I.B.12.C of the permit);</u>

- b. Describe any controls associated with non-stormwater discharges present at the site:

  None
- **I. Applicable State or Local Programs:** The SWPPP will be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site.

#### J. Hazardous Material Management and Spill Reporting Plan

Any hazardous or potentially hazardous material that is brought onto the construction site will be handled properly in order to reduce the potential for storm water pollution. All materials used on this construction site will be properly stored, handled, dispensed, and disposed of following all applicable label directions.

Material Safety Data Sheets (MSDS information will be kept on site for any and all applicable materials.)

In the event of an accidental spill, immediate action will be undertaken by the General Contractor to contain and remove the spilled materials All hazardous materials will be disposed of by the Contractor in the manner specified by federal, state and local regulations and by the manufacturer of such products. As soon as possible, the spill will be reported to the appropriate agencies. As required under the provisions of the Clean Water Act, any spill or discharge entering waters of the United States will be properly reported. The General Contractor will prepare a written record of any spill and associated clean-up activities of petroleum products or hazardous materials in excess of 1 gallon or reportable quantities, whichever is less. It is recommended that the contractor take photos to document spill clean-up measures and attach the photos to the Spill Report Form. All spill information must be transferred to the next inspection report and resolved as appropriate.

If the spill greater than the applicable reportable quantity, the contractor must follow the information below:

- a. The permittee is required to notify the National Response Center (NRC) (800-424-8802) as soon as permittee has knowledge of the discharge;
- b. Permittee shall prepare, within 14 days of knowledge of the release, a written description of: the release (including the type and estimate of the amount of material released), the date that such release occurred, the circumstances leading to the release, what actions were taken to mitigate effects of the release, and steps to be taken to minimize the chance of future occurrences and retain with the SWPPP.
- c. The SWPPP must be updated within 14 days of knowledge of the release to provide a description of the release, the circumstances lading to the release, and the date of the

release. This can be accomplished by including a cop of the written description of the release as described above in Item B.

In order to minimize the potential for a spill of petroleum product or hazardous materials to come in contact with storm water, the following steps will be implemented:

- a. All material with hazardous properties (such as pesticides, petroleum products, fertilizers, detergents, construction chemicals, acids, paints, paint solvents, additives for soil stabilization, concrete, curing compounds and additives, etc.) will be stored in a secure location, under cover, when not in use.
- b. The minimum practical quantity of all such materials will be kept on the job site and scheduled for delivery as close to time of use as practical.
- c. A spill control and containment kit (containing for example, absorbent materials such as kitty litter or sawdust, acid neutralizing agent, brooms, dust pans, mops, rags, glove, goggles, plastic and metal trash containers, etc. shall be provided.
- d. All of the product in a container will be used before the container with original product label.
- e. All products will be stored in and used from the original container with original product label.
- f. All products will be used in strict compliance with instructions on the product label.
- g. The disposal of excess or used products will be in strict compliance with instruction on the products label.

#### **K.** Inspections

- a. Inspection frequency: Every 14 calendar days and within 24 hours of a storm event of 0.25 inches or greater (a rain gauge must be maintained on site)
- b. Inspections: <u>Completed inspection forms will be kept with the SWPPP and ADEQ's</u> form will be used (See Appendix B)
- c. Inspection records will <u>be retained as part of the SWPPP for at least 3 years from the</u> date of termination.
- d. It is understood that the following sections describe waivers of site inspection requirements. All applicable documentation requirements will be followed in accordance with the referenced sections.
  - i. Winter Conditions (Part II.A.4.L.3)
  - ii. Adverse Weather Conditions (Part II.A.4.L.4)

#### L. Maintenance:

The following procedures to maintain vegetation, erosion and sediment control

measures and other protective measures in good, effective operating condition will be followed:

- a. A rain gauge must be maintained on site.
- b. The following are maintenance practices that will be used to maintain erosion and sediment controls.
- c. All measures will be maintained in good working order; and if a repair is necessary, it will be initiated within three (3) business days of discovery, or as otherwise directed by state or local officials.
- d. Accumulated sediment will be removed from the silt fence, straw bales and sediment basins when it has reached one-fourth the height of the fence, bale or depth of the basin.
- e. Sediment fence, rock or sand bag check dams and sediment basins will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the posts or anchored by stakes, and to see that the posts or stakes are firmly in the ground.
- f. Small diversion sediment basins and rock or sand bag check dams will be cleaned as necessary to prevent overflow or bypassing.
- g. Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and health growth and repaired as necessary.

Any necessary repairs will be completed, when practicable, before the next storm event, but not to exceed a period of 3 business days of discovery, or as otherwise directed by state or local officials.

#### M. Employee Training:

Employee training must be provided annually, as new employees are hired, or as necessary to ensure personnel are informed of their responsibility in implementing the practices and controls included in the SWPPP and to ensure compliance with the SWPPP and general permit. A stormwater Pollution Prevention Training Log should be kept on site in order to log dates, hours, topics, objectives, attendee roster, etc., of any employee training that takes place.

Training topics that should be addressed, at minimum, include Erosion Control BMPs, Sediment Control BMPs, Non-Stormwater BMPs, Emergency Procedures, and Good Housekeeping BMPs.

#### Certification

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official:	
Title:	Date:

### **LIST OF APPENDICES**

- APPENDIX "A" CONTACT LIST
- APPENDIX "B" CONTRACTOR/SUB-CONTRACTOR LIST
- APPENDIX "C" VICINITY MAP & USGS MAP
- APPENDIX "D" INSPECTION REPORT & GENERAL CONTRACTOR'S DELEGATED INSPECTOR FORM
- APPENDIX "E" RECORD OF STABILIZATION AND CONSTRUCTION ACTIVITIES DATES
- APPENDIX "F" SOIL REPORT AND MAP
- APPENDIX "G" SPILL REPORT FORM
- APPENDIX "H" ADDITIONAL SITE INSPECTOR LOG
- APPENDIX "I" WEEKLY STORMWATER MEETING LOG
- APPENDIX "J" CORRECTIVE ACTION LOG
- APPENDIX "K" SWPPP AMENDMENT LOG
- APPENDIX "L" RAIN GAUGE LOG
- APPENDIX "M" SWPPP TRAINING LOG
- APPENDIX "N" EROSION CONTROL PLAN & DETAILS
- APPENDIX "O" ADEQ PERMIT ARR150000
- APPENDIX "P" ARR150000 SMALL SITE NOTICE OF COVERAGE (NOC)

## **APPENDIX "A"**

**CONTACT LIST** 

### **CONTACT LIST**

Contacts for: Camping World, Alvarado, TX	Date:
Responsible for conducting monthly inspections, conducting overseeing compliance with all applicable permits, the Clea	g the final site inspection after verifying final stabilization and an Water Act, and the site SWPPP.
Responsible Contractor's Compliance Officer:	Name:
	Company:
	Phone:
	on at a site and able to adequately identify and implement storm ctively instruct employees and contractors in the implementation
Project Superintendent:	Name:
	Company:
	Phone (office):
	Phone (mobile):
	4-hours a day and can easily visit the site when needed in case of storm water sediment and erosion control practices and effectively such practices.  Name:
	Company:
	Phone (office):
	Phone (mobile):
Responsible for overseeing activities and work at a site; ha actions to comply with all applicable permits, the Clean Wa	as the authority to direct employees and contractors to undertake ter Act, and the site's SWPPP.
Construction Manger:	Name:
	Company:
	Phone (office):
	Phone (mobile):

**Note to General Contractors:** Date this form each time contact information is added or updated. Do not erase information from this form. If information is incorrect or outdated, line through incorrect / outdated information and write in correct / new information. If contact information changes more than once, create a new update Contact List, date, and place on top of old Contact List in the SWPPP Binder.


### **APPENDIX "B"**

Contractor/Sub-Contractor List

Company/Firm	Name	Address	Phone Number	Responsibility/Trade
		<u></u>		
		:		and the second control of the second control

## **APPENDIX "C"**

VICINITY MAP & USGSMAP



## **APPENDIX "D"**

INSPECTION REPORT & GENERAL CONTRACTOR'S DELEGATED INSPECTOR FORM

### General Contractor's Inspector Delegation of Authority

I,(name), nereby designar	te the person or specifically described postion
below to be a duly auhorized representative for the pur	rpose of overseeing compliance with
environmental requirement, including the Construction	
, ,	· · · · · · · · · · · · · · · · · · ·
construction site. The designee is authorized to sign an	
plans and all other documents required by the permit.	
	(name of person or position)
	(company)
<del></del>	(
· · · · · · · · · · · · · · · · · · ·	(phone)
By signing this authorization, I confirm that I meet the	e requirements to make such designation as set
forth in the Wyoming Large Construction General Per	mit for Storm Water, and that the designee
above meets the definition of a "duly authorized repres	=
Construction General Permit for Stom Water.	satisfied as set forth in the <u>vvyorning Large</u>
Construction General Fermit for Storn Water.	
I certify under penalty of law that this document and a	all attachment were prepared under my direction
or supervision in accordance with a system designed to	
gathered and evaluated the information submitted. Bat	
manage the system, or those persons directly responsib	ole for gathering the information, the
information submitted is, to the best of my knowledge	and belief, true, accurate, and complete. I am
aware that there are significant penalties for submitting	
find and imprisonment for knowing violations.	g rates in the management of the processing the
mid and imprisonment for knowing violations.	
Name:	
Name.	
Company	
Company:	
Titlo:	
Title:	
Signature:	
Date.	

### STORM WATER POLLUTION PREVENTION PLAN INSPECTION REPORT

				Completion Date:
Contractor:		Inspector	:	Inspection Date:
Inspector's Qu	alifications*	•		Inspection Time:
mopeotor 5 Qu	difficultions .			Reason for Inspection:
SITE COND	ITIONS.			
POLLUTANT CO		IN CONFORMANCE	EFFECTIVE	LOCATION OF NON-CONFORMANCE
Construction Entra		YES NO NA	YES NO NA	ECCATION OF NON-CONFORMATIVE
Sediment Barriers,		YES NO NA	YES NO NA	
Storage/Disposal A	reas	YES NO NA	YES NO NA	
Sediment Pond		YES NO NA	YES NO NA	
Outfall Locations		YES NO NA	YES NO NA	
र हात्।		YES NO NA	YES NO NA	
REMEDIAL COMMENTS	<u>ACTIONS TO</u>	BE TAKEN:		
report shall be k from the date of Based or	ept on file by the C completion and su	General Contractor as paul lbmission of the Notice of pection, the site is in comp	rt of the Storm V of Termination.	Il be implemented within 7 calendar days. This Water Pollution Prevention Plan for at least 5 years  SWPPP and the generalpermit. No corrective measures
accordance with submitted. Base gathering the int I am aware that	penalty of law that a system designed of on my inquiry of formation, the info there are significant or knowing violation	I to assure that qualified f the person or persons v rmation submitted is, to nt penalties for submittin	personnel prope who manage the the best of my k g false informat	prepared under my direction or supervision in erly gathered and evaluated the information system, or those persons directly responsible for mowledge and belief, true, accurate, and complete.
Phone:				
				Date:
	(Authorized Sign	nature*)		

<sup>\*</sup>It is the General Contractor's responsibility to insure that the inspector has been properly authorized under the applicable General Permit Regulations to sign these inspection forms.

### **APPENDIX "E"**

RECORD OF STABILIZATION

### SITE STABILIZATION and CONSTRUCTION ACTIVITY DATES

A record of dates when stabilization measures are initiated, when major grading activities occur, and when construction activities temporarily or permanently cease on a portion of the site shall be maintained until final site stabilization is achieved and the Notice of Termination is filed.

#### MAJOR STABILIZATION AND GRADING ACTIVITIES

Description of Activity:			
Site Contractor:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	PCONDUCTOR OF THE POSITION OF
Description of Activity:Site Contractor:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	
Description of Activity: Site Contractor: Location:	Begin (date):	End(date):	E0.45042127 of 5-1-10, state -
Description of Activity: Site Contractor: Location:		End(date):	ala Suur ookur oo ka sir sir s

### **APPENDIX "F"**

SOIL REPORT & MAP

## **APPENDIX "G"**

SPILL REPORT FORM

### Spill Report Form

Spill Reported by:	
Date/Time Spill:	
	ing to spill:
Material spilled:	
Source of spill:	
Amount spilled:	Amount spilled to waterway:
Containment or clean up action:	
List Injuries or Personal Contamination	on:
Action to be taken to prevent future sp	pills:
Modification to SWPPP, including rec	quired sampling, necessary due to this spill:
accordance with a system designed to assur Based on my inquiry of the person or person information, the information submitted is,	cument and allattachments were prepared under my direction or supervision in the that qualified personnel properly gather and evaluate the information submitted. Ins who manage the system, or those persons directly responsible for gathering the to the bestof my knowledge and belief, true, accurate, and complete. I am aware nitting false information, including the possiblility of fine and imprisonment for
Contractor / Superintendent	

### **APPENDIX "H"**

ADDITIONAL SITE INSPECTOR LOG

# Federal, State, or Local Storm Water or other Environmental Inspector Site Visit Log

inspectors wame:	Agency:			
Contractors Representative Present:				
Others Present:				
Comments:				
Time and Date:	Report Prepared:	Yes	No	
Inspectors Name:	Agency:			
Contractors Representative Present:				
Others Present:				
Comments:				
Time and Date:	Report Prepared:	Yes	No	
Inspectors Name:	Agency:			
Contractors Representative Present:				
Others Present:				
Comments:				
Time and Date:	Report Prepared:	Yes	No	
Inspectors Name:	Agency:			
Contractors Representative Present:				
Others Present:				
Comments:				
Time and Date:	Report Prepared:	Yes	No	

### **APPENDIX "I"**

WEEKLY STORMWATER MEETING LOG

### Weekly Storm Water Meeting Review and Comment Form

Project Site Superintendent:	Date and Time:		
Others Present: NAME	TITLE	COMPANY	
Installation/Removal of BMPs (include subcontractors performing the activities):			
BMP Maintenance and Repair (include subcontractors performing the activities):			
Non-effective BMPs:			
Efforts to mitigate or correct non-effective BM Ps:			
Status of staging areas, storage, borrow, fill, concrete wash-out, and exits:			
Upcoming Activities:			
Modifications or additions to SWPPP or project phasing:			
Finding, Conclusions & Additional Information:			

## APPENDIX "J"

CORRECTIVE ACTION LOG

Inspection Date:	Inspector Name(s):	Description of BMP Deficiency	Corrective Action Needed (including planned date/responsible person)	Date Action Taken/Responsible person

## **APPENDIX "K"**

SWPPP AMENDMENT LOG

Amendment No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

## **APPENDIX "L"**

RAIN GAUGE LOG

Date of Reading	Reading (In)	Date of Reading	Reading (In)

## **APPENDIX "M"**

SWPPP TRAINING LOG


## **Stormwater Pollution Prevention Training Log**

Project Name: Camping World					
Proj	Project Location:				
Inst	Instructor's Name(s):				
Inst	Instructor's Title(s):				
	Course Location: Date:				
Cour	se Length (hours):				
Storn	nwater Training Topic: (check as	аррі	ropriate)		
	Erosion Control BMPs		Emergency Procedures		
	Sediment Control BMPs		Good Housekeeping BMPs		
	Non-Stormwater BMPs				
Spec	ific Training Objective:		·		
Atter	Attendee Roster: (attach additional pages as necessary)				


No.	Name of Attendee	Company	1
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

## **APPENDIX "N"**

**EROSION CONTROL PLAN & DETAILS** 



#### Exhibit 1100-5



**Exhibit 1100-6** 

(Source: Arkansas Highway and Transportation Department Drainage Manual)




Exhibit 1100-7

(Source: Virginia Erosion and Sediment Control Handbook)






Exhibit 1100-8




### Exhibit 1100-9

(Source: Arkansas Highway and Transportation Department Drainage Manual)



#### Exhibit 1100-10

(Source: Arkansas Highway and Transportation Department Drainage Manual)







Exhibit 1100-11

(Source: Virginia Erosion and Sediment Control Handbook)






Exhibit 1100-12 (Source: Virginia Erosion and Sediment Control Handbook)

# STORM WATER PREVENTION PLAN

SCALE 1" = 20'

G = GUTTER ELEVATION TC = TOP OF CURB ELEVATION

### **GENERAL CONSTRUCTION NOTES**

- A. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGES OCCURRING TO ANY PROPERTY DURING THE CONSTRUCTION OF THIS PROJECT. SAID CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT PROPERTY DAMAGE.
- B. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL SOLELY AND COMPLETELY BE RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE LIMITED TO NORMAL WORKING

THE DUTY OF BRYANT TO CONDUCT CONSTRUCTION INSPECTION REVIEWS OF THE CONTRACTOR'S PERFORMANCE IS NOT AN INSPECTION OR REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE.

- C. ALL WATER AND SEWER IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION TO THE CITY OF BRYANT'S WATER AND WASTEWATER (SANITARY SEWER) STANDARD SPECIFICATIONS.
- D. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF ALL UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS SHOWN ON THE PLAN.
- CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH, AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.
- PRIOR TO INSTALLATION OF ANY UTILITIES. THE CONTRACTOR IS TO EXCAVATE, VERIFY AND CALCULATE ALL CROSSINGS AND INFORM ANY AND ALL UTILITIES OF ANY CONFLICTS PRIOR TO CONSTRUCTION.
- G. CONSTRUCTION SHALL NOT START ON ANY WATER UTILITY TIE-INS UNTIL APPROVAL IS GIVEN BY BRYANT WATER. SAID CONTRACTOR SHALL NOT OPERATE ANY VALVE, HYDRANT, OR WATER UTILITY APPURTENANCE NOR SHALL HE ATTACH TO OR TAP ANY WATER UTILITY MAIN WITHOUT APPROVAL. THE CONTRACTOR SHALL BEAR THE COST AND CONSEQUENCE OF ANY DISRUPTION OF UTILITY OPERATION CAUSED BY CONSTRUCTION.
- H. FIBER OPTIC CABLE ON AND/OR ADJACENT TO THIS SITE WERE NOT LOCATED BY THE SURVEY AND ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ANY FIBER OPTIC CABLES ASSOCIATED WITH THIS SITE AND TAKE ALL NECESSARY AND REQUIRED PRECAUTIONS TO PROTECT ANY EXISTING FIBER OPTIC CABLES. CONTRACTORS SHALL COORDINATE ALL EFFORTS WITH OWNER OF FIBER OPTIC CABLES OR THEIR DESIGNATED REPRESENTATIVE.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING "ONECALL" SERVICE TO MARK ALL UTILITIES PRIOR TO ANY DEMOLITION, EARTHWORK, OR UTILITY WORK ON THIS SITE.

ENGINEERING,

PHILLIP

REVISION:

ARV

SP

PROJECT NUMBER:

5/11/2022

STORM WATER POLLUTION PREVENTION

PLAN SHEET NUMBER: C-1.7

## **APPENDIX "O"**

ADEQ PERMIT ARR150000

05/04/2021

### AUTHORIZATION TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM AND THE ARKANSAS WATER AND AIR POLLUTION CONTROL ACT

In accordance with the provisions of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.), and the Clean Water Act (33 U.S.C. 1251 et seq.), an

#### Operator of Facilities with Stormwater Discharges Associated with Construction Activity

is authorized to discharge to all receiving waters except as stated in Part I.B.11 (Exclusions).

For large construction sites that are eligible for coverage under this General Permit (GP), the Arkansas Department of Energy and Environment - Division of Environmental Quality (DEQ), Office of Water Quality will provide a Notice of Coverage (NOC) with tracking permit number which starts with ARR15 and a copy of the permit to the facility. The cover letter includes the DEQ's determination that a facility is covered under the GP and may specify alternate requirements outlined in the permit.

Small construction sites that are eligible for coverage under this GP will be considered to have automatic coverage under this GP and must follow the permit requirements outlined in Condition 6 of Part I.

Effective Date: November 1, 2021

Expiration Date: October 31, 2026

Digitally signed by Alan J. York DN: cn=Alan J. York, o, ou, email=alan.york@adeq.state.ar.us,

c=US Date: 2021.05.04 09:13:53 -05'00'

Issue Date

Associate Director, Office of Water Quality

Division of Environmental Quality

Alan J. York

### PART I PERMIT REQUIREMENTS

Information in **Part I** is organized as follows:

**Section A:** Definitions with Included Commentary

**Section B:** Coverage Under this Permit:

- 1. Permitted Area
- 2. Eligibility
- 3. Responsibilities of the Operator
- 4. Where to Submit
- 5. Requirements for Qualifying Local Program (QLP)
- 6. Requirements for Coverage
- 7. Notice of Intent (NOI) Requirements
- 8. Posting Notice of Coverage (NOC)
- 9. Applicable Federal, State or Local Requirements
- 10. Allowable Non-Stormwater Discharges
- 11. Limitations on Coverage (Exclusions)
- 12. Short Term Activity Authorization (STAA)
- 13. Effluent Limitation Guidelines (ELG)
- 14. Natural Buffer Zones
- 15. Waivers from Permit Coverage
- 16. Notice of Termination (NOT)
- 17. Responsibilities of the Operator of a Larger Common Plan of Development for a Subdivision
- 18. Change in Operator
- 19. Late Notifications
- 20. Failure to Notify
- 21. Maintenance
- 22. Releases in Excess of Reportable Quantities
- 23. Attainment of Water Quality Standards
- 24. Requiring an Individual Permit

#### SECTION A: DEFINITIONS WITH INCLUDED COMMENTARY

- 1. "Arkansas Pollution Control and Ecology Commission" shall be referred to as APC&EC throughout this permit.
- 2. "Automatic Coverage" is a term used to define the method of coverage for a small construction site.
- **3.** "Best Management Practices (BMPs)" schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to waters of the State. BMPs also include treatment requirements, operating procedures, and practices to control construction site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage. According to the EPA BMP manual, the use of hay-bales in concentrated flow areas is not recommended as a BMP.
- **4.** "Cognizant Official" is a duly authorized representative, as defined in Part II.B.9.B.
- **5.** "Commencement of Construction" is the initial disturbance of soils (or breaking ground) associated with clearing, grading, or excavating activities or other construction-related activities (e.g., stockpiling of fill material; placement of raw materials at the site).
- **6.** "Contaminated" is a substance the entry of which into the MS4, waters of the State, or Waters of the United States may cause or contribute to a violation of Arkansas water quality standards.
- 7. "Control Measure" as used in this permit, refers to any Best Management Practice or other method used to prevent or reduce the discharge of pollutants to waters of the State.
- **8.** "Construction Activity" earth-disturbing activities, such as the clearing, grading, and excavation of land, and other construction—related activities (e.g., stockpiling of fill material; placement of raw materials at the site) that could lead to the generation of pollutants.
- **9.** "Construction Site" is an area upon which one or more land disturbing construction activities occur that in total will disturb one acre or more of land, including areas that are part of a larger common plan of development or sale that may be less than one acre where multiple separate and distinct land disturbing construction activities may be taking place at different times on different schedules but under one plan such that the total disturbed area is one acre or more.
- 10. "Construction Support Activity" a construction-related activity that specifically supports the construction activity and involves earth disturbance of pollutant-generating activities of its own, and can include, but not limited to, activities associated with concrete or asphalt batch plants, equipment staging yards, materials storage areas, excavated material disposal areas, and burrow areas.
- 11. "CWA" is the Clean Water Act or the Federal Water Pollution Control Act.
- 12. "Department" is referencing the Department of Energy and Environment.
- **13.** "<u>DEQ</u>" or "<u>Division</u>" is referencing the Division of Environmental Quality. The Division is the governing authority for the National Pollutant Discharge Elimination System program in the state of Arkansas.

- 14. "<u>Detention Basin</u>" is an area where excess stormwater is stored or held temporarily and then slowly drains when water levels in the receiving channel recede. In essence, the water in a detention basin is temporarily detained until additional room becomes available in the receiving channel.
- 15. "Director" is the Director of the Division of Environmental Quality, or a designated representative.
- **16.** "Discharge" is when used without qualification means the "discharge of a pollutant".
- 17. "<u>Disturbed area</u>" is the total area of the site where any construction activity is expected to disturb the ground surface. This includes any activity that could increase the rate of erosion, including, but not limited to, clearing, grubbing, grading, excavation, demolition activities, haul roads, and areas used for staging. Also included are stockpiles of topsoil, fill material and any other stockpiles with a potential to create additional runoff.
- **18.** <u>"Drainageway"</u> is an open linear depression, whether constructed or natural, that functions for the collection and drainage of surface water.
- **19.** <u>"Duly Authorized Representative"</u> is a representative of the Responsible Official meeting the requirements specified in Part II.B.9.B.
- 20. "Eligible" refers to being qualified for authorization to discharge stormwater under this general permit.
- 21. "Erosion" is the process by which the land's surface is worn away by the action of wind, water, ice or gravity.
- **22.** "ERW" Extraordinary Resource Water, in accordance with Rule 2.
- 23. "ESW" Ecologically Sensitive Waterbodies, in accordance with Rule 2.
- **24.** "<u>Facility</u>" or "<u>Activity</u>" is any NPDES "point source" or any other facility or activity (including land or appurtenances thereto) that is subject to regulation under the NPDES program.

#### 25. "Final Stabilization":

- A. All soil disturbing activities at the site have been completed and either of the two following criteria are met:
  - 1) A uniform (e.g., evenly distributed, without large bare areas) perennial vegetative cover with a density of 80% or more of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or
  - 2) Equivalent permanent stabilization measures (such as the use of riprap, gabions, or geotextiles) have been employed.
- B. When background native vegetation will cover less than 100% of the ground (e.g., arid areas, beaches), the 80% coverage criteria is adjusted as follows: if the native vegetation covers 50% of the ground, 80% of 50% (0.80 x 0.50 = 0.40) would require 40% total cover for final stabilization. On a beach with no natural vegetation, no stabilization is required.
- C. For individual lots in residential construction, final stabilization means that either:
  - 1) The homebuilder has completed final stabilization as specified above, or

- 2) The homebuilder has established temporary stabilization including perimeter controls for an individual lot prior to occupation of the home by the homeowner and informing the homeowner of the need for, and benefits of, final stabilization.
- D. For construction projects on land used for agricultural purposes (e.g., pipelines across crop or range land, staging areas for highway construction, etc.), final stabilization may be accomplished by returning the disturbed land to its preconstruction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to "waters of the State", and areas which are not being returned to their pre-construction agricultural use shall meet the final stabilization criteria in A, B, or C above.
- **26.** "Grading Activities" as used in this permit are those actions that disturb the surface layer of the ground to change the contouring, surface drainage pattern, or any other slope characteristics of the land without significantly adding or removing onsite rock, soil, and other materials. This can include demolition, excavation, and filling.
- 27. "Impaired Water" is a waterbody listed in the current, approved Arkansas 303(d) list.
- **28.** "Infrastructure" refers to streets, drainage, curbs, utilities, etc.
- **29.** "Landscaping" is improving the natural beauty of a piece of land (i.e. entrance of subdivision) through plantings or altering the contours of the ground.
- **30.** "Large Construction Site" is a construction site in which construction activity including clearing, grading and excavation. Construction activity also includes the disturbance of less than five acres of total land area that is a part of a larger common plan of development or sale if the larger common plan will ultimately disturb five acres or greater. (Please see Part I.B.15 for partial waivers.)
- 31. "Larger Common Plan of Development or Sale" is a contiguous (sharing a boundary or edge; adjacent; touching) area where multiple and distinct construction activities may be taking place at different times on different schedules under one plan. Such a plan might consist of many small projects (e.g. a common plan of development for a residential subdivision might lay out the streets, house lots, and areas for parks, schools and commercial development that the developer plans to build or sell to others for development). All these areas would remain part of the common plan of development or sale. The following items can be used as guidance for deciding what might or might not be considered a "Common Plan of Development or Sale." The "plan" in a common plan of development or sale is broadly defined as any announcement or piece of documentation (including a sign, public notice or hearing, sales pitch, advertisement, drawing, permit application, zoning request, computer design, etc.) or physical demarcation (including boundary signs, lot stakes, surveyor markings, etc.) indicating construction activities may occur on a specific plot. The applicant shall still meet the definition of operator in order to be required to get permit coverage, regardless of the acreage that is personally disturbed.

If a smaller project (i.e., less than 1 acre) is part of a larger common plan of development or sale (e.g., you are building a residential home on a ½ acre lot in a 40 acre subdivision or are putting in a fast food restaurant on a ¾ acre pad that is part of a 20 acre retail center), permit coverage is required.

- **32.** "Losing Stream Segment" a stream segment which, beginning at the point of existing or proposed discharge and extending two (2) miles downstream, contribute thirty percent (30%) or more of its flow at a 7Q10 flow or one (1) cfs, whichever is greater, through natural processes such as permeable subsoil or cavernous bedrock into an aquifer.
- **33.** <u>"Natural Buffer"</u> for purposes of this permit, an area of undisturbed natural cover surrounding waters of the State. Natural cover includes vegetation, exposed rock, or barren ground that exists prior to commencement of construction activities

at the site.

- **34.** "NOC" Notice of Coverage.
- **35.** "NOI" Notice of Intent to be covered by this permit.
- **36.** "NOT" Notice of Termination.
- 37. "NSW" Natural and Scenic Waterways, in accordance with Rule 2.
- **38.** "Operator"/"Permittee" for the purpose of this permit and in the context of stormwater associated with construction activity, means any person(s), an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has financial and operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; additionally, the Division may require any person(s), an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions can be named as a co-permittee.

In addition, for purposes of this permit and determining who is an operator, "owner" refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline or a landowner who allows a mining company to remove dirt, shale, clay, sand, gravel, etc. from a portion of his property). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g., having a house built by a residential homebuilder).

- **39.** "Outfall" a point source where stormwater leaves the construction site.
- **40.** "Owner" refers to the owner or operator of any "facility or activity" subject to regulation under the NPDES program. In addition, for purposes of this permit and determining who is an operator, "owner" refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g. having a house built by a residential homebuilder).
- **41.** "Physically Interconnected" means that one municipal separate storm sewer system is connected to a second municipal separate storm sewer system in such a way that it allows for direct discharges into the second system.
- **42.** "Point Source" is any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural stormwater runoff.
- **43.** "Qualified Local Program" is a municipal program for stormwater discharges associated with construction sites that has been formally approved by DEQ.
- **44.** "Qualified personnel" a person knowledgeable in the principles and practice of erosion and sediment controls who possesses the skills to assess conditions at the construction site that could impact stormwater quality and to assess the effectiveness of any sediment and erosion control measures selected to control the quality of stormwater discharges from the

construction activity.

- **45.** "<u>Regulated Small Municipal Separate Storm Sewer System</u>" are all municipal separate storm sewer systems that are either:
  - A. Located within the boundaries of an "urbanized area" with a population of 50,000 or more as determined by the latest Decennial Census by the Bureau of Census; or
  - B. Owned or operated by a municipality other than those described in paragraph A and that serve a jurisdiction with a population of at least 10,000 and a population density of at least 1,000 people per square mile; or
  - C. Owned or operated by a municipality other than those described in paragraphs A and B and that contributes substantially to the pollutant loadings of a "physically interconnected" municipal separate storm sewer system.
- **46.** "Responsible Official" is the authorized representative, as defined in Part II.B.9.A.
- **47.** "Retention Basin" a basin that is designed to hold the stormwater from a rain event and allow the water to infiltrate through the bottom of the basin. A retention basin also stores stormwater, but the storage of the stormwater would be on a more permanent basis. In fact, water often remains in a retention basin indefinitely, with the exception of the volume lost to evaporation and the volume absorbed into the soils. This differs greatly from a detention basin, which typically drains after the peak of the storm flow has passed, sometimes while it is still raining.
- **48.** "Runoff Coefficient" is the fraction of total rainfall that will appear at the conveyance as runoff.
- **49.** "**Sediment**" is material that settles to the bottom of a liquid.
- **50.** "Sediment Basin" is a basin that is designed to maintain a 10 year-24 hour storm event for a minimum of 24-hours in order to allow sediment to settle out of the water.
- 51. "Small Construction Site" is a construction site in which construction activities including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre and less than five acres. Small construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one and less than five acres. Small construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility.
- **52.** "Stormwater" is stormwater runoff from rainfall, snow melt runoff, and surface runoff and drainage.
- **53.** "Stormwater Discharge Associated with Construction Activity" refers to the discharge of runoff from any conveyance which is used for collecting and conveying stormwater and which is directly related to construction activity.
- **54.** "Stormwater Pollution Prevention Plan (SWPPP or SWP3)" is a plan that includes site map(s), an identification of construction/contractor, activities that could cause pollutants in the stormwater, and a description of measures or practices to control these pollutants.
- **55.** "<u>Temporary Sediment Controls</u>" are controls that are installed to control sediment runoff from the site during construction activity. These could be silt fencing, rock check dams, etc.
- **56.** "<u>Total Maximum Daily Load</u>" or "<u>TMDL</u>" is the sum of the individual wasteload allocations (WLAs) for point sources and load allocations (LAs) for non-point sources and natural background. If the receiving water has only one point

source discharger, the TMDL is the sum of that point source WLA plus the LAs for any non-point sources of pollution and natural background sources, tributaries, or adjacent segments. TMDLs can be expressed in terms of mass per time, toxicity, or other appropriate measure.

- **57.** "<u>Uncontaminated</u>" means that the water will not exceed the water quality standards as set forth in APC&EC Rule 2; also not containing a harmful quantity of any substance.
- **58.** "<u>Urbanized Area</u>" means the areas of urban population density delineated by the Bureau of the Census for statistical purposes and generally consisting of the land area comprising one or more central place(s) and the adjacent densely settled surrounding area that together have a residential population of at least 50,000 and an overall population density of at least 1,000 people per square mile as determined by the latest Decennial Census by the Bureau of Census.
- **59.** "Waters of the State" waters of the State means all streams, lakes, marshes, ponds, watercourses, waterways, wells, springs, irrigation systems, drainage systems, and all other bodies or accumulations of water, surface and underground, natural or artificial, public or private, which are contained within, flow through, or border upon this state or any portion of the state.

#### SECTION B: COVERAGE UNDER THIS PERMIT

#### Introduction

This Construction General Permit (CGP) authorizes stormwater discharges from large and small construction activities that result in a total land disturbance of equal to or greater than one acre or less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one acre. This permit also authorizes stormwater discharges from any other construction activity designated by DEQ where DEQ makes that designation based on the potential for contribution to an excursion of a water quality standard or for significant contribution of pollutants to waters of the State. This permit replaces the permit issued in 2016. The goal of this permit is to minimize the discharge of stormwater pollutants from construction activity into waters of the State. The operator shall read and understand conditions of the permit. A copy of the CGP is available on the DEO web https://www.adeq.state.ar.us/water/permits/npdes/stormwater/. A hard copy may be obtained by contacting the DEO's General Permits Section at (501) 682-0623.

- 1. <u>Permitted Area</u>. If a large or small construction activity is located within the State of Arkansas, the operator may be eligible to obtain coverage under this permit.
- **2.** Eligibility. Permit eligibility is limited to discharges from "large" and "small" construction activity, or as otherwise designated by DEQ. This general permit contains eligibility restrictions, as well as permit conditions and requirements. Operators shall meet the requirements of Part I.B.6.A or Part I.B.6.B to be eligible for coverage under this permit. In such cases, operators shall continue to satisfy those eligibility provisions to maintain permit authorization. If operators do not meet the requirements that are a pre-condition to eligibility, then resulting discharges constitute unpermitted discharges. By contrast, if operators are eligible for coverage under this permit and do not comply with the requirements of the general permit, they may be in violation of the general permit for otherwise eligible discharges.
  - A. This general permit authorizes discharges from construction activities as defined in 40 C.F.R. §122.26(a), 40 C.F.R. §122.26(b)(14)(x), 40 C.F.R. §122.26(b)(15)(i)-(ii) and 40 C.F.R. §450.
  - B. This permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, concrete truck washout, fueling, equipment staging yards, materials storage areas, excavated material disposal areas, stockpiles of top soil, borrow areas) provided:
    - 1) The support activity is directly related to a specific construction site that is required to have NPDES permit coverage for discharges of stormwater associated with the construction activity;
    - 2) The support activity is not a commercial operation, nor does it serve multiple unrelated construction projects; and does not continue to operate beyond the completion of the construction activity at the project it supports;
    - 3) Pollutant discharges from support activity areas are minimized in compliance with conditions of this permit; and
    - 4) Discharges from the support activity areas shall be identified in a Stormwater Pollution Prevention Plan (SWPPP) stating appropriate controls and measures for the areas off the construction site.
  - C. Other activities may be considered for this permit at the discretion of the Director as defined in 40 C.F.R. §122.26(b)(15)(ii).

- 3. Responsibilities of the Operator. Permittees with operational control are responsible for compliance with all applicable terms and conditions of this permit as it relates to their activities on the construction site including construction support activities off site, including protection of endangered species and implementation of BMPs and other controls required by the SWPPP. Receipt of this general permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance or regulation.
- **4.** Where to Submit. The operator shall submit a complete and signed Notice of Intent (NOI) and SWPPP to DEQ through ePortal, unless the operator receives a waiver from DEQ, which can be found on the following website:

https://eportal.adeq.state.ar.us/

A. The operator shall submit the application fee to DEQ through ePortal (when available), submit an email requesting an invoice to be created to pay online, or mail in invoice from ePortal with a check (listing the invoice number on the check) to the follow address:

Division of Environmental Quality ATTN: Fiscal 5301 Northshore Drive North Little Rock, AR 72118-5317

NOTE: Notice of Coverage (NOC) will **NOT** be issued until payment has been received by DEQ.

- B. Waivers from electronic reporting may be granted based on one of the following conditions:
  - 1) If the operational headquarters is physically located in a geographic area (i.e. Zip code or census tract) that is identified as under-served for broadcast internet access in the most recent report from the Federal Communications Commission:
  - 2) If available computer access or computer capability is limited; or
  - 3) If the operator is a religious community that choose not to use certain modern technologies pursuant to 40 C.F.R. §127.15(c)(1).
- C. In order to apply for a waiver from the electronic reporting, the operator must submit the required information outlined in 40 C.F.R. §127.15(b)(2).
- D. If DEQ grants a waiver approval to use a paper NOI, and operator elects to use it, the operator **must** use the approved form developed by DEQ.
- 5. Requirements for Qualifying Local Program (QLP). DEQ reviews and approves the QLPs to ensure that they meet or supersede both state and federal requirements outlined in this permit and 40 C.F.R. §122.44(s). DEQ will review the QLP at least every 5 years for recertification. If DEQ approves a QLP, then the QLP requirements shall at the minimum meet the DEQ's requirements. This includes all templates and forms. This permit may be modified to add new QLPs or modify existing QLPs at DEQ's discretion. All public notice and other applicable costs incurred by the modification of the permit for the addition or modification of a QLP will be paid by the QLP.

If a small construction site is within the jurisdiction of a QLP, the operator of the small construction site is authorized to discharge stormwater associated with construction activity under QLP permit requirements only.

At the time of issuance of this permit, only the City of Hot Springs is meeting the DEQ minimum requirements.

#### 6. Requirements for Coverage.

- A. <u>Small Construction Sites</u>. An operator of a small construction site will be considered to have automatic coverage under this general permit and may discharge without submitting a NOI, SWPPP or fee if the following conditions are met:
  - 1) A completed Notice of Coverage (NOC) must be posted at the site prior to commencing construction and remain posted until final stabilization is completed;
  - 2) A Stormwater Pollution Prevention Plan must be prepared in accordance with good engineering practice as described in Rule 6.203(B), completed prior to posting the NOC, implemented upon commencement of construction activities, and the latest copy must be maintained at the construction site;
  - 3) All permit conditions set forth in this general permit must be followed; and
  - 4) The operator is responsible for ensuring that the site is in compliance with any changes or updates of this general permit, by either contacting DEQ or reviewing the DEQ website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

- B. <u>Large Construction Sites</u>. An operator of a large construction site discharging under this general permit shall submit the following items at least ten (10) business days prior to the commencement of construction activities:
  - 1) A complete NOI in accordance with the requirements of Part I.B.7 of this permit.
  - 2) A complete SWPPP in accordance with the requirements of Part II.A of this permit.
  - 3) An initial permit fee shall accompany the NOI under the provisions of APC&EC Rule 9. Subsequent annual fees will be billed by DEQ until the operator has requested a termination of coverage by submitting a Notice of Termination (NOT). Failure to remit the required initial permit fee shall be grounds for the Director to deny coverage under this general permit. Failure to remit the required annual fees shall be grounds for the Director to revoke coverage under this permit.
- C. <u>Modification of Permit Coverage to Include Additional Acreage</u>. Any request to increase the <u>total</u> acreage of a construction site shall be accompanied by a \$200 permit modification fee and an updated SWPP. Any request to only increase the <u>disturbed</u> acreage without changing the total acreage shall be accompanied by an updated SWPP. A \$200 permit modification fee is not required with an increase in disturbed acreage. The operator shall submit a complete and signed Additional Acreage Request Form to DEQ through ePortal, which can be found on the following website:

https://eportal.adeq.state.ar.us/

#### 7. Notice of Intent (NOI) Requirements.

A. <u>NOI Form</u>. Large construction site operators who intend to seek coverage for a stormwater discharge under this general permit shall submit a complete and accurate DEQ NOI form through the ePortal system (at <a href="https://eportal.adeq.state.ar.us/">https://eportal.adeq.state.ar.us/</a>) at least ten (10) business days prior to the date coverage under this permit is desired, unless granted a waiver in accordance with Part I.B.4.D. The NOI form completed **must** be the current version obtained from ePortal.

If the NOI is deemed incomplete, DEQ will notify the applicant with regard to the deficiencies by a letter, email, or phone within ten (10) business days of the receipt of the NOI. If the operator does not receive a notification of deficiencies from DEQ's receipt of the NOI, the NOI is deemed complete. If the applicant does not provide DEQ with the requested deficiencies within the deadline set by DEQ, then DEQ will return the NOI, fee and SWPPP back to the

applicant.

- B. Contents of the NOI. The NOI form contains, at a minimum, the following information:
  - 1) Operator (Permittee) information (name, mailing address, telephone, and E-mail address)
  - 2) Whether the operator is a federal, state, private, public, corporation, or other entity
  - 3) Invoice mailing information (name, address, and telephone and fax numbers)
  - 4) Project Construction site information (name, county, address, contact person, directions to the site, latitude and longitude for the entrance of the site or the endpoints for linear project (in degrees, minutes, and seconds), estimated construction start date and completion date through site final stabilization, the total project acreage and the acreage to be disturbed by the operator submitting the NOI, type of the project (subdivision, school, etc), whether the project is part of a larger common plan of development or sale.)
  - 5) Discharge information (name of the receiving stream, ultimate receiving stream, name of municipal storm sewer system)
  - 6) List of current permits
  - 7) The Certification statement and signature of a qualified signatory person in accordance with 40 CFR 122.22, as adopted by reference in APC&EC Rule 6
  - 8) The certification of the facility corporation
  - 9) Other information (location of the SWPPP)
  - 10) And the SIC Code.
- C. <u>Notice of Coverage (NOC)</u>. Unless notified by the Director to the contrary, operators who submit a complete NOI and SWPPP in accordance with the requirements of this permit are authorized to discharge stormwater from the construction sites under the terms and conditions of this permit ten (10) business days after the date the NOI is deemed complete (which may not be the original submission date if revisions or additions were necessary) by DEQ. If the NOC has not been received by the permittee ten (10) business days after the date the NOI is deemed complete by DEQ, the NOI may be posted until the NOC is received. Upon review of the NOI and other available information, the Director may deny coverage under this permit and require submittal of an application for an individual NPDES permit.

#### 8. Posting Notice of Coverage (NOC).

A. <u>Automatic Coverage Sites</u>. The NOC for small sites, as defined in Part I.A.51, shall be obtained from the DEQ's Stormwater website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/.

The NOC must be posted at the site prior to commencing construction. In addition, a copy of the latest signed and certified SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

- B. <u>Large Sites: NOC Posting for Large Construction Sites</u>. The posting for large construction sites shall be obtained from DEQ only after the permittee has submitted the required NOI, permit fee and complete SWPPP to DEQ for the coverage.
- C. <u>Linear Projects</u>. If the construction project is a linear construction project (e.g., pipeline, highway, etc.), the notice shall be placed in a publicly accessible location near where construction is actively underway and moved as necessary.

Please note, this permit does not provide the public with any right to trespass on a construction site for any reason, including inspection of a site; nor does this permit require that the permittee allow members of the public access to a construction site.

**9.** Applicable Federal, State or Local Requirements. The operator shall ensure that the stormwater controls implemented at the site are consistent with all applicable federal, state, or local requirements. Additionally, an operator who is operating under approved local erosion and sediment plans, grading plans, local stormwater permits, or stormwater management plans shall submit signed copies of the NOI to the local agency (or authority) upon the local agency's request.

#### 10. Allowable Non-Stormwater Discharges.

- A. The following non-stormwater discharges as part of the construction activity may be authorized by this permit through appropriate controls. Non-stormwater discharges shall be addressed in the stormwater pollution prevention plan and measures to minimize or eliminate non-stormwater discharge should be taken if reasonably possible.
  - 1) Fire-fighting activities;
  - 2) Fire hydrant flushings;
  - 3) Water used to wash vehicles and equipment (where detergents, soaps, solvents or other chemicals are not used) or to control dust in accordance with Part II.A.4.J.2;
  - 4) Potable water sources including uncontaminated waterline flushings;
  - 5) Uncontaminated landscape irrigation;
  - 6) Uncontaminated routine external building wash down which does not use detergents, soaps, solvents or other chemicals;
  - 7) Uncontaminated pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents, soaps. solvents or other chemicals are not used);
  - 8) Uncontaminated air conditioning compressor condensate (See Part I.B.13.C of this permit);
  - 9) Uncontaminated springs, excavation dewatering and uncontaminated groundwater (See Part I.B.13.C of this permit);
  - 10) Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated groundwater (See Part I.B.13.C of this permit).
- 11. <u>Limitations on Coverage (Exclusions)</u>. The following stormwater discharges associated with construction activity are <u>not</u> covered by this permit:
  - A. <u>Post Construction Discharge</u>. Stormwater discharges associated with construction activities that originate from the site, as well as construction support activities located off site, after construction activities have been completed, the site has undergone final stabilization, and the permit has been terminated.
  - B. <u>Discharges Mixed with Non-Stormwater</u>. Stormwater discharges that are mixed with sources of non-stormwater other than those identified in Part I.B.10.
  - C. <u>Discharges Covered by another Permit</u>. Stormwater discharges associated with construction activity that are covered under an individual or an alternative general permit may be authorized by this permit after an existing permit expires, provided the expired permit did not establish numeric effluent limitations for such discharges.
  - D. <u>Discharges into Receiving Waters with an Approved TMDL</u>. Discharges from a site into receiving waters for which there is an established total maximum daily load (TMDL) allocation (<a href="https://www.adeq.state.ar.us/water/planning/integrated/tmdl/">https://www.adeq.state.ar.us/water/planning/integrated/tmdl/</a>) are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that is consistent with the assumptions and requirements in the EPA approved TMDL. To be eligible for coverage under this general permit, operators shall incorporate into their SWPPP all conditions applicable to their discharges necessary for consistency with the assumptions and requirements of the TMDL within the timeframes established in the TMDL. If a specific numeric allocation has been established that

applies to the project's discharges, the operator shall incorporate that allocation into its SWPPP and implement necessary steps to meet that allocation. If a numeric limit has been assigned to the facility, quarterly monitoring shall be submitted to DEQ demonstrating compliance with the assigned Waste Load Allocation established in the TMDL. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge into a receiving stream with a TMDL, then DEQ may require additional BMPs.

- E. <u>Discharges into Impaired Receiving Waters (303(d) List)</u>. If stormwater discharges from a construction site enters the receiving water listed as impaired under Section 303(d) of the Clean Water Act (<a href="https://www.adeq.state.ar.us/water/planning/integrated/">https://www.adeq.state.ar.us/water/planning/integrated/</a>), the permittee shall incorporate into the SWPPP the additional BMPs needed to sufficiently protect water quality. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge to an impaired water body, then DEQ may require additional BMPs.
- F. Discharges into an Extraordinary Resource Water (ERW), Natural and Scenic Waterway (NSW), or Ecologically Sensitive Waterbody (ESW). Discharges from a construction site located within the watershed of any water body or waterway designated as an Outstanding Resource Water as defined in the APC&EC Rule 2.203, including ERWs, NSWs, or ESWs are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. For the purposes of this permit, the watershed of an Outstanding Resource Water will be identified by the United States Geological Survey's twelve (12) digit Hydrological Unit Code (HUC). Please note that DEQ will be reviewing this information. If the site will discharge to an ERW, NSW, or ESW, then DEQ may determine that additional requirements are necessary.
- G. <u>Discharges into an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas.</u> Discharges from a construction site located within the watershed of any potential losing stream and/or sensitive aquatic species native to the area are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. In accordance with Part I.B.3, it is the responsibility of the permittee to prevent activity which may take or otherwise risk harm to endangered species. Please note that DEQ will be reviewing this information. If the site will discharge to an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas, then DEQ may determine that additional requirements are necessary.
- 12. Short Term Activity Authorization (STAA). Any work being conducted in waters of the State will require a STAA from DEQ in accordance with Rule 2.305. An STAA is necessary for any in-stream activity that has the potential to exceed the water quality standards, including, but not limited to: gravel removal, bridge or crossing repair/maintenance, bank stabilization, debris removal, culvert replacement, flood control projects, and stream relocation. Any work being conducted in Waters of the United States may require a Section 404 permit from the U.S. Army Corps of Engineers. This permit does not authorize any activity under an STAA, Individual 401 Certification, or Section 404 permit. The necessary forms to apply for coverage under an STAA or Individual 401 Certification can be found on the following website:

https://www.adeq.state.ar.us/water/planning/instream/

The SWPPP shall be updated to include a copy of the STAA letter (and Individual 401 Certification if needed) upon receipt. Re-submittal of the SWPPP is not required unless specifically requested by DEQ.

- 13. Effluent Limitation Guidelines (ELG). All permittees shall comply with the following effluent limits:
  - A. <u>Erosion and Sediment Controls</u>. Design, install, and maintain effective erosion controls and sediment controls to minimize the discharge of pollutants. At a minimum, such controls shall be designed, installed and maintained to:

- 1) Control stormwater volume and velocity to minimize soil erosion in order to minimize pollutant discharges;
- 2) Control stormwater discharges, including both peak flowrates and total stormwater volume, to minimize channel and streambank erosion and scour in the immediate vicinity of discharge points;
- 3) Minimize the amount of soil exposed during construction activity;
- 4) Minimize the disturbance of steep slopes;
- 5) Minimize sediment discharges from the site. The design, installation and maintenance of erosion and sediment controls shall address factors such as the amount, frequency, intensity and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site:
- 6) Provide and maintain natural buffers around waters of the State, direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible;
- 7) Minimize soil compaction. Minimizing soil compaction is not required where the intended function of a specific area of the site dictates that it be compacted; and
- 8) Unless infeasible, preserve topsoil. Preserving topsoil is not required where the intended function of a specific area of the site dictates that the topsoil be disturbed or removed.
- B. <u>Soil Stabilization</u>. Stabilization of disturbed areas must, at a minimum, be initiated immediately (unless weather conditions do not allow immediate initiation) whenever any clearing, grading, excavating or other earth disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and will not resume for a period exceeding fourteen (14) calendar days. In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures must be employed as specified by the permitting authority. Stabilization must be completed within fourteen (14) calendar days. In limited circumstances, stabilization may not be required if the intended function of a specific area of the site necessitates that it remain disturbed.
- C. <u>Dewatering</u>. Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, are prohibited unless managed by appropriate controls. There shall be no turbid discharges to waters of the State resulting from dewatering activities. If trench or ground waters contain sediment, it shall pass through a sediment settling pond or other equally effective sediment control device, prior to being discharged from the construction site. Alternatively, sediment may be removed by settling in place or by dewatering into a sump pit, filter bag, or comparable practice. Ground water dewatering which does not contain sediment or other pollutants is not required to be treated prior to discharge. However, care shall be taken when discharging ground water to ensure that it does not become pollutant-laden by traversing over disturbed soils or other pollutant sources.
- D. <u>Pollution Prevention Measures</u>. Design, install, implement, and maintain effective pollution prevention measures to minimize the discharge of pollutants. At a minimum, such measures shall be designed, installed, implemented and maintained to:
  - 1) Minimize the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other wash waters. Wash waters shall be treated in a sediment basin or BMP control that provides equivalent or better treatment prior to discharge;
  - 2) Minimize the exposure of building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site to precipitation and to stormwater. Minimization of exposure is not required in cases where the exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use); and
  - 3) Minimize the discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures.

- E. <u>Prohibited discharges</u>. The following discharges are prohibited:
  - 1) Wastewater from washout of concrete, unless managed by an appropriate control;
  - 2) Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds and other construction materials:
  - 3) Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance; and
  - 4) Soaps, solvents, or detergents used in vehicle, equipment washing, or external building washdown.
  - 5) Toxic or hazardous substances from a spill or release.
- F. <u>Surface Outlets</u>. When discharging from basins and impoundments, utilize outlet structures that withdraw water from the surface, unless infeasible.
- 14. Natural Buffer Zones. A natural buffer zone as stated below shall be maintained at all times and direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law.
  - A. For construction projects where construction activities or construction support activities occur, the SWPPP shall provide at least twenty-five (25) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from any waters of the State.
  - B. DEQ will require at least fifty (50) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from established TMDL water bodies, streams listed on the 303(d) list, an Extraordinary Resource Water (ERW), Ecologically Sensitive Waterbody (ESW), Natural and Scenic Waterway (NSW), or any other uses at the discretion of the Director.
  - C. Linear projects will be evaluated individually by DEQ to determine natural buffer zone setbacks.
- **15.** Waivers from Permit Coverage. The Director may waive the otherwise applicable requirements of this general permit for stormwater discharges from construction activities under the terms and conditions described in this section.
  - A. <u>Waiver Applicability and Coverage</u>. Based upon 40 C.F.R. §122.26.b.15.i.A, operators of small construction activities may apply for and receive a waiver from the requirements to obtain this permit.
  - B. <u>No Stormwater Leaving the Site</u>. If all of the stormwater from the construction activity is captured on-site under any size storm event and allowed to evaporate, soak into the ground on-site, or is used for irrigation, a permit is not needed.
  - C. <u>TMDL Waivers</u>. This waiver is available for sites with automatic coverage if the DEQ has established or approved a TMDL that addresses the pollutant(s) of concern and has determined that controls on stormwater discharges from small construction activity are not needed to protect water quality. The pollutant(s) of concern include sediment (such as total suspended solids, turbidity or siltation) and any other pollutant that has been identified as a cause of impairment of any water body that will receive a discharge from the construction activity. The operator must certify to the Director that construction activity will take place, and storm water discharges will occur within the drainage area addressed by the TMDL or equivalent analysis. Information on approved TMDLs is available on DEQ's website:

https://www.adeq.state.ar.us/water/planning/integrated/tmdl/.

16. Notice of Termination (NOT). When all construction activities that disturbed soil are complete, the site has reached final stabilization (100% stabilization with 80% density or greater, or as defined in Part I.A.25.B for sites where background native vegetation will cover less than 100% of the ground), all stormwater discharges from construction activities authorized by this permit are eliminated and all temporary sediment controls are removed and properly disposed, the operator of the facility may submit a complete Notice of Termination (NOT) to the Director. Along with the NOT, pictures that represent the entire site shall be submitted for review. Final stabilization is not required if the land is returned to its pre-construction agriculture use. Operators of small construction sites are not required to submit NOTs for their construction sites. However, final stabilization is required on all sites. If a NOT is not submitted when the project is completed, the operator will be responsible for annual fees.

### 17. Responsibilities of the Operator of a Larger Common Plan of Development or Sale.

- A. The operator is ultimately responsible for the runoff from the perimeter of the entire development. Regardless of the reason for the runoff, the operator is responsible for ensuring sufficient overall controls of the development.
- B. The operator shall not terminate the permit coverage until the following conditions have been met:
  - 1) After all construction activities including landscaping and lot development has been completed; and
  - 2) All lots are sold and developed.

The following exceptions to this requirement may apply:

- a. Less than 100% sold and developed at the discretion of the Director, or
- b. Separation of the larger common plan if twenty-four (24) months have passed with no construction activity, or
- c. All lots are developed and there are no temporary common controls for subdivision outfalls, i.e. sediment basins, large sediment traps, check dams, etc.
- 3) If lots are sold and then re-sold to a third party, permit coverage shall be obtained by each of the operators while they have ownership of the lots. The second owner is responsible for obtaining the same certification from the third owner (i.e. the certification shall pass from owner to owner).

C.	The operator shall not terminate permit coverage until the operators of all of the individual lots within the larger
	common plan of development or sale are notified of their permitting requirements under this general permit. In this
	case, the signed certification statements from each operator of individual lots shall be maintained in the stormwater
	pollution prevention plan for the larger common plan of development or sale. A copy of the signed certifications shall
	be submitted to DEQ with the NOT. The certification shall be as follows:
	"I,, operator of an individual lot #, block # of
	subdivision, certify under penalty of law that I was notified by the operator of the larger common
	plan of the stormwater permitting requirements for my construction site(s). I understand prior to commencement of any
	construction activity I have to prepare and comply with a SWPPP and post the Construction Site Notice. I understand
	that prior to the sale of this lot to another party; I must notify the new owner of DEQ requirements and obtain this
	certification from the new owner."
	Signature
	·

D. The following examples are provided as clarification:

- 1) If a small portion of the original common plan of development remains undeveloped and there has been a period of time (i.e., more than 24 months) where there are no ongoing construction activities (i.e., all areas are either undisturbed or have been finally stabilized), operators may re-evaluate the original project based on the acreage remaining from the original "larger common plan of development or sale." If less than five (5) but more than one (1) acre remains to build out the original "common plan", coverage under the large permit may not be required. However, operators will need to comply with the terms and conditions for Small Construction Sites in the Construction General Permit. If less than one acre remains of the original common plan, the individual project may be treated as a part of a less than one acre development and no permit would be required.
- 2) If operators have a long-range master plan of development or sale where some portions of the master plan are conceptual rather than a specific plan of future development and the future construction activities would, if they occur at all, happen over an extended period of time (i.e., more than 24 months), operators may consider the "conceptual" phases of development to be separate "common plans" provided the periods of construction for the physically interconnected phases will not overlap.
- 3) Where discrete construction projects within a larger common plan of development or sale are located ¼ mile or more apart and the area between the projects is not being disturbed, each individual project can be treated as a separate plan of development or sale provided any interconnecting road, pipeline or utility project that is part of the same "common plan" is not concurrently being disturbed. For example, if an interconnecting access road or pipeline were under construction at the same time, they would generally be considered as a part of a single "common plan" for permitting purposes.
- 4) If the operator sells all the lots in the subdivision to one or more multi-lot homebuilder(s), provisions shall be made to obtain stormwater permit coverage by one of the following options:
  - a. The permit may be transferred from the first "operator" to the new/second "operator".
  - A new, separate permit coverage may be obtained by the second "operator".
     NOTE: If a new permit coverage is to be obtained, then it shall be obtained before the first/original permit is terminated.
- 5) If the operator retains ownership of any lots in the subdivision, the operator shall maintain permit coverage for those lots under the original permit coverage. The operator shall modify the SWPPP by stating which lots are owned and marking the lots on the site map. If there are one (1) or two (2) lots remaining and the total acreage is less than five (5) acres, the original permit coverage could be terminated and those lots could be covered as a small site.
- **18.** Change in Operator. For stormwater discharges from large construction sites where the operator changes, including instances where an operator is added after the initial NOI has been submitted, the new operator shall ensure that a permit transfer form is received by DEQ at least two (2) weeks prior to the new operator beginning work at the site.
- 19. <u>Late Notifications</u>. A discharger is not precluded from submitting an NOI in accordance with the requirements of this part after the dates provided in Part I.B.7 of this permit. In such instances, the Director may bring an enforcement action for failure to submit an NOI in a timely manner or for any unauthorized discharges of stormwater associated with construction activity that have occurred on or after the dates specified in this permit.
- **20.** <u>Failure to Notify.</u> The operator of a construction site who fails to notify the Director of their intent to be covered under this permit, and who potentially discharges pollutants (sediment, debris, etc.) to waters of the State without an NPDES permit, is in violation of the Arkansas Water and Air Pollution Control Act.
- 21. <u>Maintenance</u>. Determination of the acreage of disturbance does not typically include disturbance for routine maintenance activities on existing roads where the original line and grade, hydraulic capacity, or original purpose of the road is not being altered, nor does it include the paving of existing roads. Maintenance activities (returning to original conditions) are not

regulated under this permit unless one or more acres of underlying or surrounding soil are cleared, graded, or excavated as part of the operation.

#### 22. Releases in Excess of Reportable Quantities.

- A. The discharge of hazardous substances or oil in the stormwater discharge(s) from a facility shall be prevented or minimized in accordance with the applicable stormwater pollution prevention plan for the facility. This permit does not relieve the operator of the reporting requirements of 40 C.F.R. §110, §117 and §302. Where a release containing a hazardous substance or oil in an amount equal to or in excess of a reporting quantity established under either 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302, occurs during a twenty-four (24) hour period, the following action shall be taken:
  - 1) Any person in charge of the facility is required to notify the National Response Center (NRC) (800-424-8802) in accordance with the requirements of 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302 as soon as he/she has knowledge of the discharge;
  - 2) The operator shall submit within five (5) calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, and the circumstances leading to the release, and steps to be taken in accordance with Part II.B.17 of this permit to the DEO.
  - 3) The SWPPP described in Part II.A of this permit shall be modified within fourteen (14) calendar days of knowledge of the release to:
    - a. Provide a description of the release and the circumstances leading to the release; and
    - b. The date of the release;
  - 4) Additionally, the SWPPP shall be reviewed to identify measures to prevent the reoccurrence of such releases and to respond to such releases, and the plan shall be modified where appropriate.
- B. Spills. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.

#### 23. Attainment of Water Quality Standards.

The operator shall select, install, implement, and maintain control measures at the construction site and construction support activities off site that minimize the discharge of pollutants for which a stream is impaired at the discretion of the Director as necessary to protect water quality. In general, except in situations explained below, the stormwater controls developed, implemented, and updated to be considered stringent enough to ensure that discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.

At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:

- A. Develop a supplemental BMP action plan describing SWPPP modifications to address adequately the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or
- B. Cease discharges of pollutants from construction activity and submit an individual permit application.

All written responses required under this part shall include a signed certification consistent with Part II.B.9.

#### 24. Requiring an Individual Permit

The Director may require any person eligible for coverage under the general permit to apply for and obtain an individual permit. In addition, any interested person(s) may submit an application for an individual permit. The Director may consider the issuance of individual permits according to the criteria in 40 C.F.R. §122.28(b)(3).

Coverage of the facility under this general permit is may be terminated by DEQ if the operator fails to submit or respond to the permitting process or requests for information in a timely manner.

Any operator covered under this general permit may request to be excluded from the coverage of this permit by applying for an APC&EC Rule 6 individual permit. The operator shall submit an application for an individual permit with the reasons supporting the application to DEQ. If a final, individual NPDES permit is issued to an operator otherwise subject to this general permit, the operator is required to submit a NOT. Coverage under this general permit will then be terminated no earlier than the effective date of the individual NPDES permit. Otherwise, the applicability of this general permit to the facility remains in full force and effect.

#### PART II STANDARD CONDITIONS

#### Information in **Part II** is organized as follows:

#### **Section A:** Stormwater Pollution Prevention Plans (SWPPP):

- 1. Deadlines for Plan Preparation and Compliance
- 2. Signature, SWPPP, Inspection Reports, and Notice of Coverage (NOC)
- 3. Keeping SWPPP Current
- 4. Contents of the Stormwater Pollution Prevention Plan
- 5. Plan Certification

#### **Section B:** Standard Permit Conditions:

- 1. Retention of Records
- 2. Duty to Comply
- 3. Penalties for Violations of Permit Conditions
- 4. Continuance of the General Permit
- 5. Need to Halt or Reduce Activity Not a Defense
- 6. Duty to Mitigate
- 7. Duty to Provide Information
- 8. Other Information
- 9. Signatory Requirements
- 10. Certification
- 11. Penalties for Falsification of Reports
- 12. Penalties for Tampering
- 13. Oil and Hazardous Substance Liability
- 14. Property Rights
- 15. Severability
- 16. Transfers
- 17. Proper Operation and Maintenance
- 18. Inspection and Entry
- 19. Permit Actions
- 20. Re-Opener Clause
- 21. Local Requirements
- 22. Applicable Federal, State Requirements

#### SECTION A: STORMWATER POLLUTION PREVENTION PLANS (SWPPP)

The operator shall prepare a SWPPP <u>before</u> permit coverage. The SWPPP shall follow the order outlined in Part II.A.4 & 5 below. This basic DEQ format is available through DEQ's website <a href="https://www.adeq.state.ar.us/water/permits/npdes/stormwater/">https://www.adeq.state.ar.us/water/permits/npdes/stormwater/</a>. Other formats may be used at the discretion of the Director if the format has been approved by DEQ prior to use. The operator shall implement the SWPPP as written from initial commencement of construction activity until final stabilization is complete, with changes being made as deemed necessary by the permittee, local, state or federal officials. The plan shall be prepared in accordance with good engineering practices, by qualified personnel and shall:

- Identify potential sources of pollution which may reasonably be expected to affect the quality of stormwater discharges from the construction site and construction support activities off site;
- Identify, describe and ensure the implementation of BMPs, with emphasis on initial site stabilization, which are to be used to reduce pollutants in stormwater discharges from the construction site and construction support activities off site:
- Be site specific to what is taking place on a particular construction site;
- Ensure compliance with the terms and conditions of this permit; and
- Identify the responsible party for on-site SWPPP implementation.

#### 1. Deadlines for Plan Preparation and Compliance.

#### A. Automatic Coverage Sites.

The plan shall be completed prior to obtaining permit coverage and commencement of construction activities and updated as appropriate. Submittal of the NOI, permit fee and SWPPP is not required. All conditions set forth in Part II.A must be followed, and the NOC must be posted at the site prior to commencing construction activities. In addition, a copy of the SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

#### B. Large Construction Sites.

The plan shall be completed and submitted for review, along with an NOI and initial permit fee ten (10) business days prior to the commencement of construction activities. Submittals of updates to the plan during the construction process are required in accordance with Part I.B.6.C or if requested by the Director.

#### C. Existing Permittees.

Existing permittees that were permitted prior to the issuance of this renewal permit are required to update their plan as appropriate to come into compliance with the requirements contained in Part II.A.4 by the effective date of this permit.

#### 2. Signature, SWPPP, Inspection Reports and Notice of Coverage (NOC).

- A. The SWPPP and inspection reports shall be signed by the operator (or cognizant official) in accordance with Part II.B.9 and be retained at the construction site during normal business hours (8:00 A.M. 5:00 P.M.). The inspections frequency shall be conducted in accordance with Part II.A.4.N.1.
- B. The operator shall make SWPPP and inspection reports available, upon request, to the Director, the EPA, or a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or, in the case of a stormwater discharge associated with construction activity which discharges through a municipal separate storm sewer system with an NPDES permit, to the municipal operator of the system.

- C. The Director, or authorized representative, may notify the operator at any time that the plan does not meet one or more of the minimum requirements of this Part. Within seven (7) business days of such notification from the Director (or as otherwise provided by the Director) or authorized representative, the operator shall make the required changes to the plan and submit to the Director a written certification that the requested changes have been made. DEQ may request resubmittal of the SWPPP to confirm that all deficiencies have been adequately addressed. DEQ may also take appropriate enforcement action for the period of time the operator was operating under SWPPP that did not meet the minimum requirements of this permit.
- D. The operator shall post the NOC near the main entrance of the construction site and visible to the public. The NOC shall indicate the location of the SWPPP. If the SWPPP location is changed from the initial location, the NOC shall be updated to reflect the correct location of the SWPPP.
- 3. <u>Keeping SWPPP Current.</u> The operator shall amend the SWPPP within seven (7) business days or whenever there is a change in design, construction, operation, or maintenance at the construction site which has or could have a significant effect on the potential for the discharge of pollutants to the waters of the State that has not been previously addressed in the SWPPP. The SWPPP shall also be modified if a determination has been made through inspections, monitoring (if required), *or* investigation by the operator, local, state, or federal officials that the discharges are causing or contributing to water quality violation or the plan proves to be ineffective in eliminating or significantly minimizing pollutants from sources identified in stormwater discharges from the construction site.
- **4. Contents of the SWPPP.** The SWPPP shall include the following items:
  - A. Site Description. SWPPP shall provide a description of the following:
    - 1) A description of the nature of the construction activity and its intended use after the NOI is filed (i.e., residential subdivision, shopping mall, etc.);
    - 2) A description of the intended sequence of major activities which disturb soils for major portions of the site (e.g. grubbing, excavation, grading, infrastructure installation, etc.);
    - 3) Estimates of the total area of the site including off-site borrow and fill areas and the total area of the site that is expected to be disturbed by excavation, grading or other activities; and
    - 4) An estimate of the runoff coefficient of the site for pre- and post-construction activities and existing data describing the soil or the quality of any discharge from the site.
  - B. <u>Responsible Parties</u>. The SWPPP shall identify (as soon as this information is known) all parties (i.e., General Contractors, Landscapers, Project Designers, and Inspectors) responsible for particular construction activities and services they provide to the operator to comply with the requirements of the SWPPP for the project site and construction support activities off site, and areas over which each party has control. If these parties change over the life of the permit, or new parties are added, the SWPPP shall be updated to reflect these changes.
  - C. <u>Receiving Waters</u>. The SWPPP shall include a clear description of the nearest receiving water(s), or if the discharge is to a MS4, the name of the operator of the municipal system, and the ultimate receiving water(s).
  - D. <u>Documentation of Permit Eligibility Related to the 303(d) list and Total Maximum Daily Loads (TMDL)</u>. The SWPPP shall include information on whether or not the stormwater discharges from the site enter a waterbody that is on the most recent 303(d) list or with an approved TMDL. If the stormwater discharge does enter a waterbody that is on the most recent 303(d) list or with an approved TMDL, then the SWPPP shall address the following items:
    - 1) Identification of the pollutants that the 303(d) list or TMDL addresses, specifically whether the 303(d) list or TMDL addresses sediment or a parameter that addresses sediment (such as total suspended solids, turbidity, or siltation);
    - 2) Identification of whether the operator's discharge is identified, either specifically or generally, on the 303(d) list or

- any associated assumptions and allocations identified in the TMDL for the discharge; and
- 3) Measures taken by the operator to ensure that its discharge of pollutants from the site is consistent with the assumptions and allocations of the TMDL.

If DEQ determines during the review process that the proposed project will be discharging to a receiving water that is on the most recent 303(d) list or with an approved TMDL, then DEQ may notify the applicant to include additional Best Management Practices in the SWPPP.

- E. <u>Documentation of Permit Eligibility Related to Discharges into an ERW, NSW, or ESW</u>. The SWPPP shall include information whether or not the construction site located within a watershed of an ERW, ESW, or NSW. If the construction site is located within a watershed of an ERW, ESW, or NSW, then the SWPPP should consider using additional BMPs for these areas. The practices shall be considered during the progression of site activities and updates to the construction site SWPPP for continued protection of underground water resources.
- F. <u>Documentation of Permit Eligibility related to potential losing stream and/or sensitive aquatic species native to these areas.</u> The SWPPP shall include information whether or not the construction site located within a watershed of a potential losing stream, and/or sensitive aquatic species native to these areas. If the construction site is located within a watershed of a potential losing stream and/or sensitive aquatic species native to these areas, then the SWPPP shall consider using BMPs for losing stream areas. The practices should be considered during the progression of site activities and updates to the facility SWPPP for continued protection of underground water resources.
- G. Attainment of Water Quality Standards After Authorization.
  - 1) The permittee shall select, install, implement, and maintain BMPs at the construction support activities off site that minimize pollutants in the discharge as necessary to meet applicable water quality standards. In general, except in situations explained below, the SWPPP shall be developed, implemented, and updated to be considered as stringent as necessary to ensure that the discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.
  - 2) At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:
    - a. Develop a supplemental BMP action plan describing SWPPP modifications to adequately address the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or
    - b. Cease discharges of pollutants from construction activity and submit an individual permit application.
  - 3) All written responses required under this part shall include a signed certification (Part II.B.9).
- H. <u>Site Map</u>. The SWPPP shall contain a legible site map (or multiple maps, if necessary) complete to scale, showing the entire site, that identifies, at a minimum, the following:
  - 1) Pre-construction topographic view;
  - 2) Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
  - 3) Delineate on the site map areas of soil disturbance and areas that will not be disturbed with regards to the construction activities and construction support activities off site under the coverage of this permit;
  - 4) Location of major structural and nonstructural controls identified in the plan;
  - 5) Location of main construction entrance and exit;

- 6) Location where stabilization practices are expected to occur;
- 7) Locations of all construction support activities off-site (i.e. materials, waste, borrow area, or equipment storage areas);
- 8) Location of areas used for concrete wash-out;
- 9) Location of all waters of the State with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
- 10) Locations where stormwater is discharged to waters of the State or a municipal separate storm sewer system if applicable,
- 11) Locations where stormwater is discharged off-site (shall be continuously updated);
- 12) Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
- 13) A legend that clearly specifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
- 14) Locations of any storm drain inlets on the site and in the immediate vicinity of the site.
- I. <u>Stormwater Controls</u>. Each plan shall include a description of appropriate controls and measures that will be installed and implemented at the construction site. The plan shall clearly describe each construction activity identified in the project description control measures associated with the construction activity and the schedule during the construction process that the measures will be implemented. Perimeter controls for the site shall be installed after the clearing and grubbing necessary for installation of the measure, but before the clearing and grubbing for the remaining portions of the site. Perimeter controls shall be actively maintained until final stabilization of those portions of the site upward of the perimeter control. Temporary controls shall be removed and properly disposed of after final stabilization. The description and implementation of controls shall address the following minimum components:
  - 1) <u>Initial Site Stabilization</u>, <u>Erosion</u>, and <u>Sediment Controls and Best Management Practices</u>. Design, install, implement, and maintain effective erosion and sediment controls to minimize the discharge of pollutants. At a minimum the following controls and BMPs shall be designed, installed, implemented, and maintained. Therefore, the SWPPP shall address, at a minimum, the following:
    - a. For larger common plans of development or sale, only streets, drainage, utility areas, areas needed for initial construction of streets (e.g., borrow pits, parking areas, etc.) and areas needed for stormwater structures may be disturbed initially. Upon stabilization of the initial areas, additional areas may be disturbed.
    - b. The construction-phase erosion (such as site stabilization) and sediment controls (such as check dams) shall be designed to retain sediment on-site to the extent practicable.
    - c. All control measures shall be properly selected, installed, and maintained in accordance with the manufacturer's specifications, good engineering, and construction practices. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the permittee shall replace or modify the control for site situations.
    - d. If sediment escapes the construction site, off site accumulations of sediment shall be removed before the next business day to minimize off-site impacts (e.g., to prevent fugitive sediment in a street could be washed into storm sewers by the next rain or pose a safety hazard to users of public streets). This permit does not give the authority to trespass onto other property; therefore this condition should be carried out along with the permission of neighboring land owners to remove sediment.
    - e. Sediment shall be removed from sediment traps (if used, please specify what type) or sedimentation ponds when design capacity has been reduced by 50%.
    - f. Litter, construction debris, and construction chemicals exposed to precipitation and to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls picked up daily).
    - g. Construction support activities off site (i.e. material storage areas, overburden and stockpiles of dirt, borrow areas, etc.) used solely by the permitted project are considered a part of the project and shall be addressed in the SWPPP.

- 2) Stabilization practices. The SWPPP shall include, at a minimum, the following information:
  - a. Description and Schedule: A description of initial, interim, and permanent stabilization practices, including site-specific scheduling of the implementation of the practices. Site plans shall ensure that existing vegetation is preserved where attainable and that disturbed areas are stabilized. Stabilization practices may include, but not limited to: mulching, temporary seeding, permanent seeding, geotextiles, sod stabilization, natural buffer strips, protection of trees, and preservation of mature vegetation and other appropriate measures.
  - b. Description of natural buffer areas: DEQ requires that a natural buffer zone be established between the top of stream bank and the disturbed area. The SWPPP shall contain a description of how the site will maintain natural buffer zones. For construction projects where clearing and grading activities will occur, SWPPP shall provide at least twenty-five (25) feet of natural buffer zone from any named or unnamed streams, creeks, rivers, lakes or other water bodies. The plan shall also provide at least fifty (50) feet of natural buffer zone from established TMDL waterbodies, waterbodies listed on the 303(d) list, an ERW, ESW, NSW, or other uses at the discretion of the Director. If the site will be disturbed within the recommended buffer zone, then the buffer zone area shall be stabilized as soon as possible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law. Please note that above-grade clearing that does not disturb the soil in the buffer zone area does not have to comply with buffer zone requirements.
  - c. Records of Stabilization: A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included in the plan.
  - d. Deadlines for Stabilization After Construction Activity Temporarily Ceases: Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily ceased, but in no case more than fourteen (14) calendar days after the construction activity in that portion of the site has temporarily ceased, except:
    - (1) Where the initiation of stabilization measures by the fourteenth (14<sup>th</sup>) calendar day after construction activity temporarily ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.
    - (2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.
  - e. Deadline for Stabilization After Construction Activity Permanently Ceases: Stabilization measures shall be initiated immediately in portions of the site where construction activities have permanently ceased, except:
    - (1) Where the initiation of stabilization measures immediately after construction activity permanently ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.
    - (2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.
- 3) <u>Structural Practices</u>. A description of structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site to the degree attainable. Structural practices should be placed on upland soils to the degree attainable. The installation of these devices may

be subject to Section 404 of the Clean Water Act. Such practices may include but are not limited to:

- silt fences (installed and maintained);
- earthen dikes to prevent run-on;
- drainage swales to prevent run-on;
- check dams;
- subsurface drains;
- pipe slope drains;
- storm drain inlet protection;
- rock outlet protection;
- sediment traps;
- reinforced soil retaining systems;
- gabions;
- temporary or permanent sediment basins.

A combination of erosion and sediment control measures is encouraged to achieve maximum pollutant removal. Adequate spillway cross-sectional area and re-enforcement shall be provided for check dams, sediment traps, and sediment basins.

#### a. Sediment Basins:

- (1) For common drainage locations that serve an area with ten (10) or more acres (including run-on from other areas) draining to a common point, a temporary or permanent sediment basin that provides storage based on either the smaller of 3600 cubic feet per acre, or a size based on the runoff volume of a 10 year, 24 hour storm, shall be provided where attainable (so as not to adversely impact water quality) until final stabilization of the site. In determining whether installing a sediment basin is attainable, the operator may consider factors such as site soils, slope, available area on site, etc. Proper hydraulic design of the outlet is critical to achieving the desired performance of the basin. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. If "non-attainability" is claimed, then an explanation of nonattainability shall be included in the SWPPP. Where a sediment basin is not attainable, smaller sediment basins or sediment traps shall be used. Where a sediment basin is un-attainable, natural buffer strips or other suitable controls which are effective are required for all side slopes and down slope boundaries of the construction area. The plans for removal or final usage of the sediment basin shall be included with the description of the basin in the SWPPP.
- (2) For drainage locations serving an area less than ten (10) acres, sediment traps, silt fences, or equivalent sediment controls are required for all side slope and down slope boundaries of the construction area unless a sediment basin providing storage based on either the smaller of 3600 cubic feet per acre, or a size based on the run off volume of a 10 year, 24 hour storm is provided. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. However, in order to protect the waters of the State, the Director, at their discretion, may require a sediment basin for any drainage areas draining to a common point.

#### b. Velocity Dissipation Devices:

Velocity dissipation devices shall be placed at discharge locations, within concentrated flow areas serving two

or more acres, and along the length of any outfall channel to provide a non-erosive flow velocity from the structure to a water course so that the natural physical and biological characteristics and functions are maintained and protected (i.e., no significant changes in the hydrological regime of the receiving water). Please note that the use of hay-bales is not recommended in areas of concentrated flow.

#### J. Other Controls.

- 1) No solid materials identified in Part I.B.13.D shall be discharged to waters of the State or offsite.
- 2) Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of a stabilized construction entrance and exit or vehicle tire washing.
- 3) For lots that are less than one (1) acre in size an alternative method may be used in addition to a stabilized construction entrance. An example of an alternative method could be daily street sweeping. This could allow for the shortening of the construction entrance.
- 4) The plan shall ensure and demonstrate compliance with applicable State or local waste disposal, temporary and permanent sanitary sewer or septic system regulations.
- 5) No liquid concrete waste shall be discharged to waters of the State. Appropriate controls to prevent the discharge of concrete washout waters shall be implemented if concrete washout will occur on-site.
- 6) No contaminants from fuel storage areas, hazardous waste storage and truck wash areas shall be discharged to waters of the State or offsite. Methods for protecting these areas shall be identified and implemented. These areas shall not be located near a waterbody, if there is a water body on or near the project.
- K. <u>Non-stormwater discharges</u>. Sources of non-stormwater listed in Part I.B.10 of this permit that are combined with stormwater discharges associated with construction activity shall be identified in the plan. This list shall be site specific non-stormwater discharges.
- L. <u>Post-Construction Stormwater Management</u>. The operator is required to provide a description of measures that will be installed during the construction process to control pollutants in stormwater discharges that will occur after construction operations have been completed. Structural measures shall be placed on upland soils to the degree attainable. The installation of these devices may be subject to Section 404 (Corps of Engineers) of the Clean Water Act. This permit only addresses the installation of stormwater management measures, and not the ultimate operation and maintenance of such structures after the construction activities have been completed and the site has undergone final stabilization. However, post-construction stormwater BMPs that discharge pollutants from a point source once construction is completed may need authorization under a separate DEQ NPDES permit. Such practices may include but are not limited to:
  - infiltration of runoff onsite;
  - flow attenuation by use of open vegetated swales and natural depressions;
  - stormwater retention structures;
  - stormwater detention structures (including wet ponds);
  - sequential systems, which combine several practices.

A goal of at least eighty percent 80 % removal of total suspended solids from these flows which exceed predevelopment levels should be used in designing and installing stormwater management controls (where practicable). Where this goal is not met, the operator shall provide justification for rejecting each practice listed above based on site conditions.

- M. <u>Applicable State or Local Programs</u>. The SWPPP shall be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site.
- N. <u>Inspections</u>. Inspections shall be conducted by qualified personnel (provided by the operator). Inspections shall include all areas of the site disturbed by construction activity and construction support activities located off site that are exposed to precipitation and to stormwater. Inspectors shall look for evidence of, or the potential for, pollutants entering

the stormwater conveyance system. All stormwater control measures shall be observed to ensure proper installation, operation, and maintenance. Discharge locations shall be inspected to determine whether all stormwater control measures are effective in preventing significant impacts to waters of the State or offsite, where accessible. Where discharge locations are inaccessible, nearby downstream locations shall be inspected to the extent that such inspections are practicable. Locations where vehicles enter or exit the site shall be inspected for evidence of off-site sediment tracking. Inspections may not be required if the remaining lot(s) within a larger common plan of development or sale disturb less than one acre of land. In addition, inspections may not be required on a completed section of a linear project if final stabilization has been completed for that section. Stabilized areas of the project shall be indicated in the SWPPP and site map and show what date they were stabilized. The operator shall ensure that no sediment will leave the lot(s) that are stabilized. These lots shall be identified within the SWPPP and show what date they were stabilized. If the operator is unable to ensure this, then inspections shall continue.

- 1) <u>Inspection Frequency</u>. Inspections shall be conducted in accordance with one of the following schedules listed below. The schedule **must be specified** in the SWPPP.
  - a. At least once every seven (7) calendar days, or
  - b. At least once every fourteen (14) calendar days and within twenty-four (24) hours of the end of a storm event of 0.25 inches or greater (a rain gauge must be maintained on-site).
- 2) <u>Inspection Form</u>. The DEQ inspection form should be used for all inspections. The inspection form shall include all stormwater controls that are being used on site as well as at construction support activities off site. The form is available on DEQ's website <u>www.adeq.state.ar.us</u>. If a different form is used, it shall at a minimum contain the following information:
  - a. Inspector name and title;
  - b. Date of Inspection;
  - c. Amount of rainfall and days since last rain event (only applicable to Part II.A.4.N.1.b);
  - d. Approximate beginning and duration of the storm event;
  - e. Description of any discharges during inspection;
  - f. Locations of discharges of sediment/other pollutants;
  - g. Locations of BMPs in need of maintenance or where maintenance was performed;
  - h. If the BMPs are in working order and if maintenance is required (including when scheduled and completed);
  - i. Locations that are in need of additional controls;
  - j. Location and dates when major construction activities begin, occur or cease;
  - k. Signature of qualified signatory official, in accordance with Part II.B.9.

Additional information may be added to the inspection report at the permittee's discretion.

- 3) <u>Inspection Records</u>. Each report shall be retained as part of the SWPPP for at least three (3) years from the date the site is finally stabilized. Each report shall be signed and have a certification statement in accordance with Parts II.B.9 and 10 of this permit.
- 4) <u>Winter Conditions</u>. Inspections will not be required at construction sites nor the construction support activities located off site where snow cover exists over the entire site for an extended period, and melting conditions do not exist. If there is any runoff from the site at any time during snow cover, melting conditions are considered to be existent at the site and this inspection waiver does not apply. Regular inspections, as required by this permit, are required at all other times as specified in this permit. If winter conditions prevent compliance with the permit, documentation of the beginning and ending date of winter conditions shall be included in the SWPPP.
- 5) <u>Adverse Weather Conditions</u>. Adverse conditions are those that are dangerous or create inaccessibility for personnel, such as local flooding, high winds, or electrical storms, or situations that otherwise make inspections

impractical, such as extended frozen conditions. When adverse weather conditions prevent the inspection of the site, an inspection shall be completed as soon as is safe and feasible. If adverse weather conditions prevent compliance with the permit, documentation of the beginning and ending date of adverse weather conditions shall be included in the SWPPP.

- O. <u>Maintenance</u>. A description of procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition shall be outlined in the plan. Any repairs that are needed based on an inspection shall be completed, when practicable, before the next storm event, but not to exceed a period of three (3) business days of discovery, or as otherwise directed by state or local officials. However, if conditions do not permit large equipment to be used, a longer time frame is allowed if the condition is thoroughly documented on the inspection form. Maintenance for manufactured controls shall be done at a minimum of the manufacturer's specifications. Maintenance for non-manufactured controls, i.e. check dams and sediment traps, shall be done when 50% of treatment capacity remains.
- P. <u>Employee Training</u>. The permittee/operator is responsible for training personnel, who are responsible for implementing activities identified in the SWPPP, on the components and requirements of the SWPPP and the requirements of the general permit. This includes contractors and subcontractors. Training shall be given by a knowledgeable and qualified trainer. The SWPPP shall identify periodic dates for such training for all personnel and records of training shall be maintained with the SWPPP. Training records that are maintained electronically (i.e. database, etc.) do not need to be maintained with the SWPPP, but shall be accessible upon request. Formal training classes given by Universities or other third-party organizations are not required but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.
- **5.** Plan Certification. The SWPPP Certification shall be signed by either the operator or the cognizant official identified on the NOI. All documents required by the permit and other information requested by the Director shall be signed by operator or by a <u>duly authorized</u> representative of the operator (Please see Part II.B.10 below for certification).

#### **SECTION B: STANDARD PERMIT CONDITIONS**

#### 1. Retention of Records.

- A. The operator shall retain records of all Stormwater Pollution Prevention Plans, all inspection reports required by this permit, and records of all data used to complete the NOI to be covered by this permit for a period of at least three (3) years from the date the NOT letter is signed by DEQ. This period may be extended by request of the Director at any time.
- B. The operator shall retain a signed copy of the SWPPP and inspection reports required by this permit at the construction site from the date of project initiation to the date of final stabilization.
- 2. <u>Duty to Comply.</u> The operator shall comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the federal Clean Water Act and the Arkansas Water and Air Pollution Control Act and is grounds for: enforcement action; permit termination, revocation and re-issuance, or modification; or denial of a permit renewal application.
- 3. Penalties for Violations of Permit Conditions. The Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.) provides that any person who violates any provisions of a permit issued under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year, or a criminal penalty of not more than twenty five thousand dollars (\$25,000) or by both such fine and imprisonment for each day of such violation. Any person who violates any provision of a permit issued under the Act may also be subject to civil penalty in such amount as the court shall find appropriate, not to exceed ten thousand dollars (\$10,000) for each day of such violation. The fact that any such violation may constitute a misdemeanor shall not be a bar to the maintenance of such civil action. Any person that purposely, knowingly, or recklessly causes pollution of the water of the state in a manner not otherwise permitted by law and thereby places another person in imminent danger of death or serious bodily injury shall be guilty of a felony and shall be subject to imprisonment, a fine not more than two hundred fifty thousand dollars (\$250,000), or both such fine and imprisonment.
- **4.** Continuance of the General Permit. Permittees wishing to continue coverage under this general permit shall submit a Renewal NOI (see Part I.B.4 for where to submit documentation) up to 180 days prior to the expiration date, but no later than thirty (30) days prior to the expiration date. No additional fee is required to be submitted along with the Renewal NOI.

An expired general permit continues in force and effect until a new general permit is issued. If this permit is not re-issued or replaced prior to the expiration date, it will be administratively continued in accordance with Ark. Code Ann. § 8-4-203(m) and remain in force and effect. If a permittee was granted permit coverage prior to the expiration date, the permittee will remain covered by the continued permit until the earliest of:

- A. The effective date of the re-issuance or replacement of this permit and a timely submittal of a renewal NOI by the operator; or
- B. The operator's submittal and DEQ approval of a NOT; or
- C. Issuance and effectiveness of an individual permit for the project's discharges and completion of item B of this section (see Part I.B.24); or
- D. A formal permit decision by DEQ to not re-issue this general permit, at which time operators must seek coverage under an alternative permit (see Part I.B.24).

Small site operators are responsible for ensuring that the site is in compliance with any changes or updates of this general permit by reviewing DEQ's website at:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

- 5. <u>Need to Halt or Reduce Activity Not a Defense</u>. It shall not be a defense for an operator in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.
- **6. <u>Duty to Mitigate.</u>** The operator shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has reasonable likelihood of adversely affecting human health or the environment.
- 7. <u>Duty to Provide Information</u>. The operator shall furnish to the Director, an authorized representative of the Director, the EPA, a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or in the case of a stormwater discharge associated with industrial activity which discharges through a MS4 with an NPDES permit, to the municipal operator of the system, within a reasonable time, any information which is requested to determine compliance with this permit.
- **8.** Other Information. When the operator becomes aware that he or she failed to submit any relevant facts or submitted incorrect information in the NOI or in any other report to the Director, he or she shall promptly submit such facts or information.
- 9. <u>Signatory Requirements</u>. All NOIs, reports, or information submitted to the Director shall be signed and certified by the operator.
  - A. All NOI shall be signed as follows:
    - 1) <u>For a corporation</u>: by a responsible corporate officer. For purposes of this section, a responsible corporate officer means:
      - a. A president, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or
      - b. The manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to ensure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
    - 2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;
    - 3) <u>For a municipality, State, Federal or other public agency</u>: by either a principal executive or ranking elected official. For purposes of this section, a principal executive officer of a Federal agency includes:
      - a. The chief executive officer of the agency; or
      - b. A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.
  - B. All reports required by the permit and other information requested by the Director shall be signed by a person described

above or by a <u>duly authorized</u> representative of that person. A person is a duly authorized representative only if:

- 1) The authorization is made in writing by a person described above and submitted to the Director;
- 2) The authorization specifies either an individual or a person having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility, or position of equivalent responsibility for environmental matters for the company (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and
- 3) <u>Changes to authorization</u>. If an authorization under this Part is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the above requirements shall be submitted to the Director prior to or together with any reports, information, or applications to be signed by an authorized representative.
- 10. <u>Certification</u>. Any person signing a document under this section shall make the following certification:

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Note: For this permit only, "this document" refers to the Stormwater Pollution Prevention Plan, "attachments" refers to the site map and inspection forms, and "system" is referencing the project site.

- 11. Penalties for Falsification of Reports. The Arkansas Water and Air Pollution Control Act provides that any person who knowingly makes any false statement, representation, or certification in any application, record, report, plan or other document filed or required to be maintained under this permit shall be subject to civil penalties specified in Part II.B.3 of this permit and/or criminal penalties under the authority of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.).
- 12. <u>Penalties for Tampering</u>. The Arkansas Water and Air Pollution Control act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year or a fine of not more than twenty five thousand dollars (\$25,000) or by both such fine and imprisonment.
- 13. Oil and Hazardous Substance Liability. Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the operator from any responsibilities, liabilities, or penalties to which the operator is or may be subject under Section 311 of the Clean Water Act or Section 106 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).
- 14. <u>Property Rights.</u> The issuance of this permit does not convey any property rights of any sort or any exclusive privileges, nor does it authorize any injury to private property, any invasion of personal rights, or any infringement of Federal, State, or local laws or regulations.
- **15.** <u>Severability.</u> The provisions of this permit are severable. If any provisions of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provisions to other circumstances and the remainder of this permit shall not be affected thereby.

- **16.** <u>Transfers.</u> This permit is not transferable to any person except after notice to the Director. A transfer form shall be submitted to DEQ as required by this permit.
- 17. Proper Operation and Maintenance. The operator shall at all times:
  - A. Properly operate and maintain all systems of treatment and control (and related appurtenances) which are installed or used by the operator to achieve compliance with the conditions of this permit. This provision requires the operation of backup or auxiliary facilities or similar systems which are installed by an operator only when the operation is necessary to achieve compliance with the conditions of the permit.
  - B. Provide an adequate operating staff which is duly qualified to carry out operation, inspection, maintenance, and testing functions required to ensure compliance with the conditions of this permit.
- **18.** <u>Inspection and Entry.</u> The operator shall allow the Director, the EPA, or an authorized representative, or, in the case of a construction site which discharges to a municipal separate storm sewer, an authorized representative of the municipal operator of the separate sewer system receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:
  - A. Enter upon the operator's premises where a regulated facility or activity is located or conducted, or where records shall be kept under the conditions of this permit;
  - B. Have access to and copy, at reasonable times, any records that shall be kept under the conditions of this permit;
  - C. Inspect at reasonable times any facilities or equipment, including monitoring and control equipment and practices or operations regulated or required by the permit;
  - D. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the CWA, any substances or parameters at any location on the permitted property.
- **19. Permit Actions.** This permit may be modified, revoked and reissued, or terminated for any cause including, but not limited to, the following;
  - A. Violation of any terms or conditions of this permit;
  - B. Obtaining this permit by misrepresentation or failure to fully disclose all relevant facts;
  - C. A change in any conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge;
  - D. A determination that the permitted activity endangers human health or the environment and can only be regulated to acceptable levels by permit modification or termination; or
  - E. Failure of the operator to comply with the provisions of DEQ Rule 9 (Fee Rule). Failure to promptly remit all required fees shall be grounds for the Director to initiate action to terminate this permit under the provisions of 40 C.F.R. §122.64 and §124.5(d), as adopted by reference in DEQ Rule 6, and the provisions of DEQ Rule 8.

#### 20. Re-Opener Clause.

- A. If there is evidence indicating potential or realized impacts on water quality due to any stormwater discharge associated with industrial activity covered by this permit, the operator of such discharge may be required to obtain an individual permit or an alternative general permit in accordance with Part I.B.24 of this permit, or the permit may be modified to include different limitations and/or requirements.
- B. Permit modification or revocation will be conducted in accordance with the provisions of 40 C.F.R. §122.62, §122.63, §122.64 and §124.5, as adopted by reference in DEQ Rule 6.
- 21. <u>Local Requirements</u>. All dischargers shall comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding any discharges of stormwater to storm drain systems or other water sources under their jurisdiction, including applicable requirements in municipal stormwater management programs developed to

comply with the DEQ permits. Dischargers shall comply with local stormwater management requirements, policies, or guidelines including erosion and sediment control.

**22.** Applicable Federal, State, or local Requirements. Permittees are responsible for compliance with all applicable terms and conditions of this permit. Receipt of this permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance policy, or regulation. Nothing in this permit shall be construed to preclude the institution of any legal action or enforcement actions or relieve the permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable local state, or federal law or regulation.

## **APPENDIX "P"**

ARR150000 SMALL SITE NOC

## SITE WITH AUTOMATIC COVERAGE (LESS THAN 5 ACRES) CONSTRUCTION SITE NOTICE

FOR THE

Division of Environmental Quality (DEQ) Stormwater Program

#### NPDES GENERAL PERMIT NO. ARR150000


The following information is posted in compliance with **Part I.B.8.a** of the DEQ General Permit Number **ARR150000** for discharges of stormwater runoff from sites with automatic coverage. Additional information regarding the DEQ stormwater program may be found on the internet at:

www.adeq.state.ar.us/water/branch\_npdes/stormwater

Permit Number	ARR150000					
Contact Name: Phone Number:						
Project Description (Name, Location, etc.): Start Date: End Date: Total Acres:						
Location of Stormwater Pollution Prevention Plan:						
Does this construction activity take place, and does the stormwater discharge occur within the drainage area addressed by a TMDL? YESNO						
For Construction Sites Authorized under <b>Part I.B.6.a</b> (Accompleted:	Automatic Coverage) the following certification must be					
claiming an authorization under Part I.B.2. of the DE pollution prevention plan has been developed and imple	(Typed or Printed Name of Person Completing this e read and understand the eligibility requirements for Q General Permit Number ARR150000. A stormwater emented according to the requirements contained in Part difficant penalties for providing false information or for bility of fine and imprisonment for knowing violations.					
Signature and Title	Date					

# SPLASH CARWASH

## BRYANT, ARKANSAS REYNOLDS ROAD MAY, 2022



**VICINITY MAP** 

SHEET INDEX					
SH. NO.	SHEET TITLE				
00	COVER SHEET				
G-1	EXISTING SITE SURVEY				
C-1.0	SITE PLAN				
C-1.1	UTILITY PLAN				
C-1.3	GRADING PLAN				
C-1.4	SITE DETAILS				
C1.5	WATER & SEWER DETAILS				
C-1.6	LANDSCAPE PLAN				
C-1.7	STORM WATER POLLUTION PREVENTION PLAN				
C-1.8	EROSION CONTROL DETAILS I				
C-1.9	EROSION CONTROL DETAILS II				

## PROPERTY SPECIFICATIONS

OWNER: COLLIERS INTERNATIONAL ATTN: BRADFORD GAINES 1 ALLIED DRIVE, STE 1500 LITTLE ROCK, AR 72202

(501)-372-6161

DEVELOPER/SUBDIVIDER: COLLIERS INTERNATIONAL ATTN: BRADFORD GAINES 1 ALLIED DRIVE, STE 1500 LITTLE ROCK, AR 72202

ENGINEERS: PHILLIP LEWIS ENGINEERING, INC. 23620 INTERSTATE-30 BRYANT, ARKANSAS 72022

(501)-350-9840 ZONING CLASSIFICATION: C-2

## DEVELOPMENT SPECIFICATIONS

BUILDING = 4,996 SQ. FT. (10.5% OF TOTAL PROPERTY AREA) PAVING = 22,400 SQ. FT. (47.1% OF TOTAL PROPERTY AREA) LANDSCAPE = 9,891 SQ. FT. (20.8% OF DEVELOPED AREA)

## FLOOD ZONE INFORMATION


FIRM PANEL NO: 05125 C 0380E

EFFECTIVE DATE: 6/05/2020.
THE PROPERTY IS NOT LOCATED WITHIN THE 100 YEAR FLOOD PLAIN NO BASE FLOOD ELEVATION IS DETERMINED FOR ZONE X OR ZONE A


## SITE NOTES


- 1. THE INFORMATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THIS SURVEY IS BASED ON RECORDS OF EXISTING UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS WERE TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS IN ADVANCE BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES.
- 2. BASIS OF BEARINGS: ARKANSAS STATE PLANE, NORTH ZONE .











#### LEGEND

Right of Way Monument

MAP

△ Control Points Set Iron Pin

• Found Monument © Gas Regulator

🖺 Gas Meter © Clean Out

Sanitary Sewer Manhole Telephone Pedestal

© Electric Meter  $\blacksquare$  Electric Box  $\neg \bigcirc \neg Power Pole$ 

--- Guy Wire Anchor ♣ Light Pole © Center Line

© Flag Pole

→ Fire Hydrant

 Water Hydrant Down Spout

W Water Meter  $\bowtie$  Water Valve

■ Metal Drainage Grate @ Gate Post *⊚* Ground Light

lacksquare Sign• Junction Box

 $\, \stackrel{\iota}{\leftarrow} \, Handicap \, Parking \,$ Manhole Bollard

MB MailboxRPZ RPZ Valve0 Tree

(VLT) Vault AC Air Conditioner

- Flow Direction [ Flared End Section

-S --- Sanitary Sewer Main — Electric Line ----- Underground Gas 


——— F ——— Fiber Optic 

Concrete

This property lies within Zone X according to Federal Flood Insurance Rate Map Community Panel No. 05125C0380E, effective

All utilities shown per visible field evidence, lines marked on the ground, or verbal communication from onsite utility personnel. Surveyor is not responsible for existing underground utilities that are incorrectly located, omitted from or added to this plat.

500-01S-14W-0-22-30-62-1348



## GENERAL CONSTRUCTION NOTES

- A. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGES OCCURRING TO ANY PROPERTY DURING THE CONSTRUCTION OF THIS PROJECT. SAID CONTRACTOR SHALL TAKE ALL NECESSARY
- THE CONTRACTOR WILL SOLELY AND COMPLETELY BE RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE LIMITED TO NORMAL WORKING
- INSPECTION REVIEWS OF THE CONTRACTOR'S PERFORMANCE IS NOT AN INSPECTION OR REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE.
- C. ALL WATER AND SEWER IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION TO THE CITY OF BRYANT'S WATER AND WASTEWATER (SANITARY SEWER) STANDARD SPECIFICATIONS.
- D. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF ALL UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS
- OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.
- PRIOR TO INSTALLATION OF ANY UTILITIES, THE CONTRACTOR IS TO EXCAVATE, VERIFY AND CALCULATE ALL CROSSINGS AND INFORM ANY AND
- APPROVAL IS GIVEN BY BRYANT WATER. SAID CONTRACTOR SHALL NOT OPERATE ANY VALVE, HYDRANT, OR WATER UTILITY APPURTENANCE NOR SHALL HE ATTACH TO OR TAP ANY WATER UTILITY MAIN WITHOUT APPROVAL. THE CONTRACTOR SHALL BEAR THE COST AND CONSEQUENCE OF ANY DISRUPTION OF UTILITY OPERATION CAUSED BY CONSTRUCTION.
- BY THE SURVEY AND ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ANY FIBER OPTIC CABLES ASSOCIATED WITH THIS SITE AND TAKE ALL NECESSARY AND REQUIRED PRECAUTIONS TO PROTECT ANY EXISTING FIBER OPTIC CABLES. CONTRACTORS SHALL COORDINATE ALL EFFORTS WITH OWNER OF FIBER OPTIC CABLES OR THEIR DESIGNATED
- TO MARK ALL UTILITIES PRIOR TO ANY DEMOLITION, EARTHWORK, OR UTILITY
- 1. EVANS LOOP IS CURRENTLY IMPROVED TO THE EAST 28' BC-BC WITH 60' R/W. EXISTING PAVING ALONG PROPERTY LINE IS 11' CL TO EDGE OF PAVING.
- 3. CONTRACTOR SHALL INSTALL CURB AND GUTTER TO THE DIMENSION OF 14' FROM
- 4. EXISTING LANE SLOPE SHALL BE TAKEN FROM CL EXISTING ROAD THROUGH A
- POINT 8' NORTH OF EXISTING CL TO DETERMINE EXISTING CROSS SLOPE TO MATCH 5. ASPHALT PAVEMENT AND GUTTER SHALL MATCH EXISTING ROAD CROSS SLOPE


REVISION:

ROJECT NUMBER:

5/25/2022

SITE PLAN

SHEET NUMBER:



ENGINEERING,

PHILLIP

REVISION:


り

ROJECT NUMBER:

SHEET ISSUE DATE: 5/25/2022

UTILITY PLAN

SHEET NUMBER:



ENGINEERING,

PHILLIP

REVISION:

ARV


SH SP

PROJECT NUMBER:

SHEET ISSUE DATE: 5/25/2022


GRADING PLAN

SHEET NUMBER:




NOT TO SCALE


NOT TO SCALE



HMAC ASPHALT SURFACE COURSE




CONCRETE APRON SECTION























NOT TO SCALE HANDICAP SIGN DETAIL NOTE: HANDICAP SIGNAGE SHALL BE IN STRICT COMPLIANCE WITH CURRENT FEDERAL AND LOCAL LAW REQUIREMENTS






**BOLLARD DETAIL** NOT TO SCALE

BASEPLATE DETAIL





PROJECT NUMBER:

ENGINEERING,

LEWIS

PHILLIP

REVISION:

S

ARV

SH


SP

SHEET ISSUE DATE: 5/25/2022


SITE DETAILS

SHEET NUMBER: C-1.4






SEWER SERVICE SADDLE



CONNECTION TO EXISTING SERVICE



1" CORPORATION STOP 1" SDR 9 HDPE TUBING WITH

A.Y.McDONALD 74701-22 STAINLESS STEEL INSERTS

USE GENTLE BENDS.

INSTALL 0-10° HORIZONTAL FOR END CONNECTIONS.

SINGLE METER SETTING

BOTTOM VIEW
WATER METER LID

2"x2" NOTCH OVER INLET AND OUTLET

METERS (TO BE

24" HIGH 24" DIA. SDR51 PVC METER BOX WITH 26.75"

POLYMER COVER FOR 1" METER SET

WITH DUCT TAPE.

2" x 2" NOTCH OVER

─ #67 CRUSHED STONE

6" THICK & 6" OUTSIDE BOX

INLET AND OUTLET

2 INCHES ABOVE DIRT GRADE

8 OZ. NON-WOVEN FILTER FABRIC

12" OUTSIDE BOX. TAPE TO BOX

OR 1/2 INCH ABOVE SOD

SET METER BOX

PROVIDED BY CITY)

IRRIGATION

REFER TO SPECIFICATIONS

METER SETTING

2" MIN. CLEAR (EACH SIDE)

∽BRACE EYE w/ 16"

OF 1/2" SCH 40 PVC

FOR MATERIALS FOR DOUBLE

SPLICE TRACER WIRE WITH

-1" CORPORATION STOP

U-BRANCH (7.5" WIDTH)

CONTINUOUS TRACER WIRE
12 GAUGE SOLID COATED COPPER

(BLUE JACKET) 6" ABOVE PIPE

DOUBLE METER SETTING

3M WATERPROOF

1" BRASS

ONLY FOR 1 LOT

METER (TO BE PROVIDED

24" HIGH 18" DIA. SDR51 PVC METER BOX WITH

BOX SHALL BE SUPPORTED BY CRUSHED STONE

COIL ENOUGH TRACER WIRE -

TO EXTEND 12" ABOVE BOX.

A.Y. McDONALD NL METER -

SETTER 726-207WX2D 33

DO NOT WRAP AROUND SETTER

CONTINUOUS TRACER WIRE -

(BLUE JACKET) 6" ABOVE PIPE

12 GAUGE SOLID COATED COPPER

20" POLYMER COVER FOR 5/8" x 3/4" METERS. —

AND NOT REST ON THE HDPE TUBING.

BY CITY)

A.Y. McDONALD HINGED —

SADDLE 3891

36" MIN.

MAIN

A.Y. McDONALD HINGED —

SADDLE 3891

TAPPING SADDLE

TAPPING SADDLE

CONNECTOR

2-INCH METER SETTER


NOTES:

1. COORDINATE INSTALLATION AND CONFIGURATIONOF ALL 1-1/2" AND LARGER METER SETTINGS WITH THE CITY.

2. ALL METER BOXES SHALL BE INSTALLED IN NON-PAVED AREAS. ANY METER BOX THAT GETS PLACED IN A PAVED AREA SHALL BE RELOCATED AT THE OWNER'S EXPENSE BEFORE A WATER METER WILL BE INSTALLED.

3. SUPPORT METER INSTALLATION WITH 1"x24" SCH40 PVC THROUGH EACH BRACE EYE.

2" WATER SERVICE AND WATER METER



ARKANSAS

REGISTERED
PROFESSIONAL
ENGINEER

No. 9540

PROJECT NUMBER:

SHEET ISSUE DATE: 5/25/2022

GE TITLE:

WATER & SEWER DETAILS

SHEET NUMBER:

C-1.5

Structu 23620 Inte

REVISION:


SENGINEERING, + Civil Consultants

LEWIS

PHILLIP

REVISION:

BRYANT, ARKANSAS BRYANT, ARKANSAS



PHILLIP LEWIS ENGINEERING, I Structural + Civil Consultants

PHILLIP Stru

REVISION:

SPLASH CARWASH
BRYANT

ARKANSAS

REGISTERED
PROFESSIONAL
ENGINEER

No. 9540

PROJECT NUMBER:

SHEET ISSUE DATE: 5/25/2022


5/25/2022

GE TITLE:

LANDSCAPE

SHEET NUMBER:

PLAN



ENGINEERING,

PHILLIP

REVISION:

A. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGES OCCURRING TO ANY PROPERTY DURING THE CONSTRUCTION OF THIS PROJECT. SAID CONTRACTOR SHALL TAKE ALL NECESSARY

B. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL SOLELY AND COMPLETELY BE RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE LIMITED TO NORMAL WORKING

THE DUTY OF BRYANT TO CONDUCT CONSTRUCTION INSPECTION REVIEWS OF THE CONTRACTOR'S PERFORMANCE IS NOT AN INSPECTION OR REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE.


- ALL WATER AND SEWER IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION TO THE CITY OF BRYANT'S WATER AND WASTEWATER (SANITARY SEWER) STANDARD SPECIFICATIONS.
- THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF ALL UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS
- CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH, AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.
- PRIOR TO INSTALLATION OF ANY UTILITIES, THE CONTRACTOR IS TO EXCAVATE, VERIFY AND CALCULATE ALL CROSSINGS AND INFORM ANY AND
- G. CONSTRUCTION SHALL NOT START ON ANY WATER UTILITY TIE-INS UNTIL APPROVAL IS GIVEN BY BRYANT WATER. SAID CONTRACTOR SHALL NOT OPERATE ANY VALVE, HYDRANT, OR WATER UTILITY APPURTENANCE NOR SHALL HE ATTACH TO OR TAP ANY WATER UTILITY MAIN WITHOUT APPROVAL. THE CONTRACTOR SHALL BEAR THE COST AND CONSEQUENCE OF ANY DISRUPTION OF UTILITY OPERATION CAUSED BY CONSTRUCTION.
- FIBER OPTIC CABLE ON AND/OR ADJACENT TO THIS SITE WERE NOT LOCATED BY THE SURVEY AND ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ANY FIBER OPTIC CABLES ASSOCIATED WITH THIS SITE AND TAKE ALL NECESSARY AND REQUIRED PRECAUTIONS TO PROTECT ANY EXISTING FIBER OPTIC CABLES. CONTRACTORS SHALL COORDINATE ALL EFFORTS WITH OWNER OF FIBER OPTIC CABLES OR THEIR DESIGNATED
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING "ONECALL" SERVICE TO MARK ALL UTILITIES PRIOR TO ANY DEMOLITION, EARTHWORK, OR UTILITY

S


SHEET ISSUE DATE: 5/25/2022

STORM WATER POLLUTION PREVENTION PLAN

SHEET NUMBER:



ENGINEERING, LEWIS PHILLIP



REVISION:

N

S


ROFESSIONAL ENGINEER


PROJECT NUMBER:

HEET ISSUE DATE: 5/25/2022

**EROSION** CONTROL **DETAILS I** 

SHEET NUMBER: C-1.8





**EROSION** CONTROL

## **DRAINAGE REPORT**


## **Splash Carwash**

Date: 05-11-2022

Located in: Bryant, Arkansas

Prepared for:
City of Bryant, Arkansas

### Prepared by:



## PHILLIP LEWIS ENGINEERING

Structural + Civil Consultants

23620 Interstate 30 | Bryant, AR PH: 501-350-9840


PHILLIP LEWIS ENGINEERING, INC. Structural/Civil Design 23620 Interstate 30 N Bryant, Arkansas 72022

#### **Description of Project**

The proposed project is for development of Splash Carwash facility located at 2116 Reynolds Rood in Bryant, Arkansas. The 1.09 acres is located at the intersection of Reynolds Road and Evans loop (old filling station site).

The scope of the project includes the construction of a drive thru tunnel carwash with self service vacuum bays and a covered pay kiosk. In addition to the vacuum bays, new interior landscape islands will be added around the vacuum bays as well as new landscape areas at the South and West side of the property.

Post-development runoff conditions will be reduced from Pre-development runoff conditions after completion of the devlopement with a detention pond constructed in the North East Corner of the property. Post-development site conditions will have an increase in pervious areas. Detention is calculated and sized for the 100 year storm.



Splash Carwash Bryant
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022

Page 2

#### **Area Listing (all nodes)**

Area	С	Description
(acres)		(subcatchment-numbers)
0.516	0.95	ASPHALT SURFACE (2S)
0.390	0.46	GRASS LANDSCAPING (2S)
0.712	0.65	GRAVEL PARKING (1S)
0.152	0.97	ROOF TOP (2S)
0.345	0.77	SHRUB POOR CONDITION BRUSH (1S)
2.115	0.73	TOTAL AREA

Splash Car Wash Bryant, Arkansas

Splash Carwash Bryant
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022

Page 3

#### **Pipe Listing (all nodes)**

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Width	Diam/Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	3P	384.50	384.00	10.0	0.0500	0.011	0.0	12.0	0.0

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 4

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: PRE-DEVELOPMENT Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=0.63" Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=2.53 cfs 0.056 af

**Subcatchment 2S: POST-DEVELOPMENT** Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=0.71" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=2.82 cfs 0.062 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.19' Max Vel=4.94 fps Inflow=2.82 cfs 0.062 af n=0.013 L=4.0' S=0.0200 '/' Capacity=12.61 cfs Outflow=2.83 cfs 0.062 af

Pond 3P: DETENTION POND

Peak Elev=385.57' Storage=1,038 cf Inflow=2.83 cfs 0.062 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=2.26 cfs 0.062 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.118 af Average Runoff Depth = 0.67" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac

Prepared by Phillip Lewis Engineering

Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 5


## **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 2.53 cfs @ 0.26 hrs, Volume= 0.056 af, Depth= 0.63"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr

A	rea (sf)	С	Description	1		
	31,035	0.65	GRAVEL P	GRAVEL PARKING		
	15,020	0.77	SHRUB PO	SHRUB POOR CONDITION BRUSH		
	46,055	0.69	Weighted A	Average		
	46,055		100.00% P	ervious Are	ea	
Tc	Length	Slope	,	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE	
					Range n= 0.130 P2= 4.19"	

#### **Subcatchment 1S: PRE-DEVELOPMENT**



# **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

			•		
Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	0.98	5.20	0.00	10.30	0.00
0.20	1.96	5.30	0.00	10.40	0.00
0.30	2.20	5.40	0.00	10.50	0.00
0.40	1.22	5.50	0.00	10.60	0.00
0.50	0.24	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80 0.90	0.00 0.00	5.90 6.00	0.00 0.00	11.00 11.10	0.00 0.00
1.00	0.00	6.10	0.00	11.10	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80 1.90	0.00 0.00	6.90 7.00	0.00 0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70 2.80	0.00 0.00	7.80 7.90	0.00 0.00		
2.80	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60 3.70	0.00 0.00	8.70 8.80	0.00 0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40	0.00	9.50 9.60	0.00 0.00		
4.50 4.60	0.00 0.00	9.60 9.70	0.00		
4.70	0.00	9.70	0.00		
4.80	0.00	9.90	0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		

## **Summary for Subcatchment 2S: POST-DEVELOPMENT**


Runoff = 2.82 cfs @ 0.15 hrs, Volume= 0.062 af, Depth= 0.71"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr

	Α	rea (sf)	С	Description	1			
		22,479	0.95	ASPHALT	SURFACE			
		6,603	0.97	<b>ROOF TOP</b>	ROOF TOP			
		16,973	0.46	<b>GRASS LA</b>	GRASS LANDSCAPING			
		46,055	0.77	Weighted A	Weighted Average			
		16,973		36.85% Pe	rvious Area	a e e e e e e e e e e e e e e e e e e e		
		29,082		63.15% Im	pervious Ai	rea		
	Тс	Length	Slope	•	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	6.7	40	0.0150	0.10		Sheet Flow, GRASS		
						Grass: Dense n= 0.240 P2= 4.19"		
	2.1	320	0.0150	2.49		Shallow Concentrated Flow, PAVEMENT		
						Paved Kv= 20.3 fps		
	8.8	360	Total					

### **Subcatchment 2S: POST-DEVELOPMENT**



## **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

		,			
Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	1.92	5.20	0.00	10.30	0.00
0.20	2.82	5.30	0.00	10.40	0.00
0.30	2.18	5.40	0.00	10.50	0.00
0.40	0.26	5.50	0.00	10.60	0.00
0.50	0.00	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30 1.40	0.00 0.00	6.40 6.50	0.00 0.00	11.50 11.60	0.00 0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90	0.00	7.00	0.00		
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70 2.80	0.00 0.00	7.80 7.90	0.00 0.00		
2.80	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60	0.00	8.70	0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10 4.20	0.00 0.00	9.20 9.30	0.00 0.00		
4.20	0.00	9.40	0.00		
4.40	0.00	9.40	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70	0.00	9.80	0.00		
4.80	0.00	9.90	0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		

Splash Car Wash Bryant, Arkansas

## **Splash Carwash Bryant**

Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 9

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Summary for Reach 4R: CURB CUT WIER**

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.71" for 2-yr event

Inflow = 2.82 cfs @ 0.15 hrs, Volume= 0.062 af

Outflow = 2.83 cfs @ 0.16 hrs, Volume= 0.062 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 4.94 fps, Min. Travel Time= 0.0 min Avg. Velocity = 3.92 fps, Avg. Travel Time= 0.0 min

Peak Storage= 2 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.19', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs

3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish

Length= 4.0' Slope= 0.0200 '/'


Inlet Invert= 387.25', Outlet Invert= 387.17'

Prepared by Phillip Lewis Engineering


HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022 Page 10

#### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 11

## **Reach 4R: CURB CUT WIER**



Splash Car Wash Bryant, Arkansas Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr Printed 5/11/2022

Splash Carwash Bryant

Little Rock Rainfall 2-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 12

# Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	387.25	0.00
0.50	0.00	0	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	0	387.25	0.00
2.00	0.00	0	387.25	0.00
2.50	0.00	0	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	0	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Printed 5/11/2022 Page 13

Splash Carwash Bryant

Little Rock Rainfall 2-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation	Velocity	Discharge
(feet)	(ft/sec)	(cfs)
387.25	0.00	0.00
387.26	0.75	0.02
387.27	1.18	0.07
387.28	1.54	0.14
387.29	1.86	0.22
387.30	2.15	0.32
387.31	2.41	0.43
387.32	2.66	0.56
387.33	2.90	0.70
387.34	3.12	0.84
387.35	3.34	1.00
387.36	3.54	1.17
387.37	3.74	1.35
387.38	3.92	1.53
387.39	4.11	1.72
387.40	4.28	1.93
387.41	4.45	2.14
387.42	4.62	2.36
387.43	4.78	2.58
387.44	4.93	2.81
387.45	5.09	3.05
387.46	5.23	3.30
387.47	5.38	3.55
387.48	5.52	3.81
387.49	5.65	4.07
387.50	5.79	4.34
387.51	5.92	4.62
387.52	6.05	4.90
387.53	6.17	5.19
387.54	6.30	5.48
387.55	6.42	5.77
387.56	6.53	6.08
387.57	6.65	6.38
387.58	6.76	6.69
387.59	6.87	7.01
387.60	6.98	7.33
387.61	7.09	7.65
387.62	7.19	7.98
387.63	7.30	8.32
387.64	7.40	8.65
387.65	7.50	9.00
387.66	7.59	9.34
387.67	7.69	9.69
387.68	7.79	10.04
387.69	7.88	10.40
387.70	7.97	10.76
387.71	8.06	11.12
387.72	8.15	11.49
387.73	8.24	11.86
387.74	8.32	12.23
387.75	<b>8.41</b>	<b>12.61</b>

Printed 5/11/2022 Page 14

Splash Carwash Bryant

Little Rock Rainfall 2-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Reach 4R: CURB CUT WIER

Elevation	End-Area	Storage
(feet)	(sq-ft)	(cubic-feet)
387.25	0.0	0
387.26	0.0	0
387.27	0.1	0
387.28	0.1	Ö
387.29	0.1	0
387.30	0.1	1
387.31	0.2	1
	0.2	1
387.32 387.33	0.2	1
387.34		1
	0.3	1
387.35	0.3	
387.36	0.3	1
387.37	0.4	1
387.38	0.4	2
387.39	0.4	2
387.40	0.4	2
387.41	0.5	2
387.42	0.5	2
387.43	0.5	2
387.44	0.6	2
387.45	0.6	2
387.46	0.6	3
387.47	0.7	3
387.48	0.7	2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3 3 3
387.49	0.7	3
387.50	0.8	3
387.51	0.8	3
387.52	0.8	3
387.53	0.8	3
387.54	0.9	3
387.55	0.9	4
387.56	0.9	4
387.57	1.0	4
387.58	1.0	4
387.59	1.0	4
387.60	1.1	4
387.61	1.1	4
387.62	1.1	4
387.63	1.1 1.2	5
387.64	1.2	5
387.65	1.2	5
387.66	1.2	5
387.67	1.3	5
387.68	1.3	5
387.69	1.3	5
387.70	1.4	5
387.71	1.4	6
387.72	1.4	6
387.73	1.4	6
387.74	1.5	6
387.75	1.5	6

## Splash Carwash Bryant

Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr

Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022 Page 15

#### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.71" for 2-yr event

Inflow = 2.83 cfs @ 0.16 hrs, Volume= 0.062 af

Outflow = 2.26 cfs @ 0.30 hrs, Volume= 0.062 af, Atten= 20%, Lag= 8.2 min

Primary = 2.26 cfs @ 0.30 hrs, Volume= 0.062 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 385.57' @ 0.30 hrs Surf.Area= 1,150 sf Storage= 1,038 cf

Plug-Flow detention time= 10.9 min calculated for 0.062 af (100% of inflow)

Center-of-Mass det. time= 10.8 min ( 23.3 - 12.4 )

Volume	Inv	ert Avai	I.Storage	Storage	Storage Description		
#1	384.	50'	2,986 cf	Custom	Stage Data (Pri	ismatic) Listed below (Recalc)	
Elevatio		Surf.Area (sq-ft)		c.Store pic-feet)	Cum.Store (cubic-feet)		
384.5	50	724		0	0		
385.0	00	986		428	428		
386.0	00	1,273		1,130	1,557		
387.0	00	1,585		1,429	2,986		
Device	Routing	In	vert Ou	tlet Device	s		
#1	Primary	384		0" Round			
				40 0' CN	D projecting no	baadwall Ka- 0 000	

L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf


Primary OutFlow Max=2.26 cfs @ 0.30 hrs HW=385.57' (Free Discharge) 1=12" RCP (Inlet Controls 2.26 cfs @ 2.87 fps)

Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC


Page 16

3/11 12320 © 2022 Hydrocad Goldware Golddolfs ELC

#### **Pond 3P: DETENTION POND**




#### **Pond 3P: DETENTION POND**



## **Pond 3P: DETENTION POND**

#### Stage-Area-Storage



Splash Car Wash Bryant, Arkansas Little Rock Rainfall 2-yr Duration=16 min, Inten=3.44 in/hr Printed 5/11/2022

Splash Carwash Bryant

Little Rock Rainfall 2-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 18

# **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	384.50	0.00
0.50	0.00	375	384.95	0.61
1.00	0.00	79	384.60	0.04
1.50	0.00	41	384.56	0.01
2.00	0.00	27	384.54	0.01
2.50	0.00	20	384.53	0.00
3.00	0.00	16	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	10	384.51	0.00
4.50	0.00	8	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	5	384.51	0.00
6.00	0.00	4	384.51	0.00
6.50	0.00	3	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	1	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	0	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Splash Carwash Bryant

Little Rock Rainfall 2-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Pond 3P: DETENTION POND

Elevation	Primary	Elevation	Primary	Elevation	Primary
(feet)	(cfs)	(feet)	(cfs)	(feet)	(cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50	386.72	3.92
384.70	0.13	385.72	2.53	386.74	3.94
384.72 384.74	0.16	385.74	2.57	386.76	3.96
384.74 384.76	0.19 0.22	385.76 385.78	2.60 2.64	386.78 386.80	3.98 4.01
384.78	0.22	385.80	2.67	386.82	4.01
384.80	0.20	385.82	2.70	386.84	4.05
384.82	0.23	385.84	2.74	386.86	4.07
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.59	385.96	2.93	386.98	4.20
384.96	0.64	385.98	2.96	387.00	4.22
384.98	0.69	386.00	2.99		
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91	386.08	3.10		
385.08	0.97	386.10	3.13		
385.10	1.02	386.12	3.16		
385.12	1.08	386.14	3.19		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24		
385.18 385.20	1.26 1.32	386.20 386.22	3.27 3.30		
385.22	1.32	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40	1.90	386.42	3.56		
385.42	1.95	386.44	3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		
	l				

Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## Stage-Area-Storage for Pond 3P: DETENTION POND

Elevation	Surface	Storage
(feet)	(sq-ft)	(cubic-feet)
384.50	724 750	0
384.55	750	37
384.60 384.65	776	75 114
384.70	803 829	155
384.75	855	197
384.80	881	241
384.85	907	285
384.90	934	332
384.95	960	379
385.00	986	428
385.05	1,000	477
385.10	1,015	528
385.15	1,029	579
385.20	1,043	630
385.25 385.30	1,058	683 736
385.35	1,072 1,086	790
385.40	1,101	845
385.45	1,115	900
385.50	1,130	956
385.55	1,144	1,013
385.60	1,158	1,071
385.65	1,173	1,129
385.70	1,187	1,188
385.75	1,201	1,248
385.80	1,216	1,308
385.85 385.90	1,230 1,244	1,369 1,431
385.95	1,244	1,494
386.00	1,273	1,557
386.05	1,289	1,621
386.10	1,304	1,686
386.15	1,320	1,751
386.20	1,335	1,818
386.25	1,351	1,885
386.30	1,367	1,953
386.35	1,382	2,022
386.40 386.45	1,398 1,413	2,091 2,161
386.50	1,413	2,101
386.55	1,445	2,304
386.60	1,460	2,377
386.65	1,476	2,450
386.70	1,491	2,525
386.75	1,507	2,600
386.80	1,523	2,675
386.85	1,538	2,752
386.90	1,554	2,829
386.95 387.00	1,569 <b>1,585</b>	2,907 <b>2,986</b>
307.00	1,505	2,986

Splash Car Wash Bryant, Arkansas

## **Splash Carwash Bryant**

Prepared by Phillip Lewis Engineering

Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 21

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: PRE-DEVELOPMENT Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=0.75" Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=3.01 cfs 0.066 af

**Subcatchment 2S: POST-DEVELOPMENT** Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=0.84" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=3.36 cfs 0.074 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.21' Max Vel=5.27 fps Inflow=3.36 cfs 0.074 af n=0.013 L=4.0' S=0.0200 '/' Capacity=12.61 cfs Outflow=3.36 cfs 0.074 af

Pond 3P: DETENTION POND

Peak Elev=385.75' Storage=1,253 cf Inflow=3.36 cfs 0.074 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=2.59 cfs 0.074 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.140 af Average Runoff Depth = 0.80" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 22


#### **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 3.01 cfs @ 0.26 hrs, Volume= 0.066 af, Depth= 0.75"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr

A	rea (sf)	С	Description	1		
	31,035	0.65	<b>GRAVEL F</b>	GRAVEL PARKING		
	15,020	0.77	SHRUB PO	SHRUB POOR CONDITION BRUSH		
	46,055	0.69	Weighted Average			
	46,055		100.00% P	ervious Are	ea	
Tc	Length	Slope	•	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE	
					Range n= 0.130 P2= 4.19"	

#### **Subcatchment 1S: PRE-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 5-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 23

# **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

			•		
Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	1.16	5.20	0.00	10.30	0.00
0.20 0.30	2.33 2.62	5.30	0.00	10.40 10.50	0.00
0.30	1.46	5.40 5.50	0.00 0.00	10.50	0.00 0.00
0.50	0.29	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70 0.80	0.00 0.00	5.80 5.90	0.00 0.00	10.90 11.00	0.00 0.00
0.80	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20 1.30	0.00	6.30	0.00 0.00	11.40 11.50	0.00
1.40	0.00 0.00	6.40 6.50	0.00	11.60	0.00 0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70 1.80	0.00 0.00	6.80 6.90	0.00 0.00	11.90 12.00	0.00 0.00
1.90	0.00	7.00	0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20 2.30	0.00 0.00	7.30 7.40	0.00 0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60 2.70	0.00 0.00	7.70 7.80	0.00 0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10 3.20	0.00 0.00	8.20 8.30	0.00 0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50 3.60	0.00 0.00	8.60 8.70	0.00 0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90 4.00	0.00 0.00	9.00 9.10	0.00 0.00		
4.10	0.00	9.10	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40 4.50	0.00 0.00	9.50 9.60	0.00 0.00		
4.60	0.00	9.70	0.00		
4.70	0.00	9.80	0.00		
4.80 4.90	0.00 0.00	9.90 10.00	0.00 0.00		
5.00	0.00	10.00	0.00		

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 24

## **Summary for Subcatchment 2S: POST-DEVELOPMENT**


Runoff = 3.36 cfs @ 0.15 hrs, Volume= 0.074 af, Depth= 0.84"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr

A	rea (sf)	С	Description	1		_
	22,479	0.95	ASPHALT	SURFACE		
	6,603	0.97	<b>ROOF TOP</b>	<b>D</b>		
	16,973	0.46	GRASS LA	NDSCAPI	NG	
•	46,055	0.77	Weighted A	Average		_
	16,973		36.85% Pe	rvious Area	a e e e e e e e e e e e e e e e e e e e	
	29,082		63.15% Im	pervious Ai	rea	
Tc	Length	Slope	Velocity	Capacity	Description	
/ • \						
<u>(min)</u>	(feet)	(ft/ft)	(ft/sec)	(cfs)		_
(min) 6.7	(feet) 40			(cfs)	Sheet Flow, GRASS	_
		(ft/ft)		(cfs)	Sheet Flow, GRASS Grass: Dense n= 0.240 P2= 4.19"	_
		(ft/ft)	0.10	(cfs)	•	_
6.7	40	(ft/ft) 0.0150	0.10	(cfs)	Grass: Dense n= 0.240 P2= 4.19"	_

#### **Subcatchment 2S: POST-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 5-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours)	(cfs)	(hours)	(cfs)
0.00 0.10	0.00 <b>2.29</b>	5.10 5.20	0.00 0.00	10.20 10.30	0.00 0.00
0.10	3.36	5.30	0.00	10.30	0.00
0.30	2.59	5.40	0.00	10.50	0.00
0.40	0.31	5.50	0.00	10.60	0.00
0.50	0.00	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70 0.80	0.00 0.00	5.80 5.90	0.00 0.00	10.90 11.00	0.00 0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30 1.40	0.00 0.00	6.40 6.50	0.00 0.00	11.50 11.60	0.00 0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90 2.00	0.00 0.00	7.00 7.10	0.00 0.00		
2.10	0.00	7.10	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50 2.60	0.00 0.00	7.60 7.70	0.00 0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00 3.10	0.00 0.00	8.10 8.20	0.00 0.00		
3.10	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60 3.70	0.00 0.00	8.70 8.80	0.00 0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20 4.30	0.00 0.00	9.30 9.40	0.00 0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00 0.00	9.80 9.90	0.00 0.00		
4.80	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		

Splash Car Wash Bryant, Arkansas

## **Splash Carwash Bryant**

Prepared by Phillip Lewis Engineering

Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 26

#### **Summary for Reach 4R: CURB CUT WIER**

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.84" for 5-yr event

Inflow = 3.36 cfs @ 0.15 hrs, Volume= 0.074 af

Outflow = 3.36 cfs @ 0.16 hrs, Volume= 0.074 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 5.27 fps, Min. Travel Time= 0.0 min Avg. Velocity = 4.18 fps, Avg. Travel Time= 0.0 min

Peak Storage= 3 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.21', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs

3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish

Length= 4.0' Slope= 0.0200 '/'


Inlet Invert= 387.25', Outlet Invert= 387.17'

Prepared by Phillip Lewis Engineering


HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 27

#### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 28

## **Reach 4R: CURB CUT WIER**



Splash Car Wash Bryant, Arkansas Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr Printed 5/11/2022

Splash Carwash Bryant

Little Rock Rainfall 5-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 29

# Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	387.25	0.00
0.50	0.00	Ŏ	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	Ö	387.25	0.00
2.00	0.00	Ö	387.25	0.00
2.50	0.00	Ö	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	Ö	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Printed 5/11/2022 Page 30

Splash Carwash Bryant

Little Rock Rainfall 5-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation	Velocity	Discharge
(feet)	(ft/sec)	(cfs)
387.25	0.00	0.00
387.26	0.75	0.02
387.27	1.18	0.07
387.28	1.54	0.14
387.29	1.86	0.22
387.30	2.15	0.32
387.31	2.41	0.43
387.32	2.66	0.56
387.33	2.90	0.70
387.34	3.12	0.84
387.35	3.34	1.00
387.36	3.54	1.17
387.37	3.74	1.35
387.38	3.92	1.53
387.39	4.11	1.72
387.40	4.28	1.93
387.41	4.45	2.14
387.42	4.62	2.36
387.43	4.78	2.58
387.44	4.93	2.81
387.45	5.09	3.05
387.46	5.23	3.30
387.47	5.38	3.55
387.48	5.52	3.81
387.49	5.65	4.07
387.50	5.79	4.34
387.51	5.92	4.62
387.52	6.05	4.90
387.53	6.17	5.19
387.54	6.30	5.48
387.55	6.42	5.77
387.56	6.53	6.08
387.57	6.65	6.38
387.58	6.76	6.69
387.59	6.87	7.01
387.60	6.98	7.33
387.61	7.09	7.65
387.62	7.19	7.98
387.63	7.30	8.32
387.64	7.40	8.65
387.65	7.50	9.00
387.66	7.59	9.34
387.67	7.69	9.69
387.68	7.79	10.04
387.69	7.88	10.40
387.70	7.97	10.76
387.71	8.06	11.12
387.72	8.15	11.49
387.73	8.24	11.86
387.74	8.32	12.23
387.75	<b>8.41</b>	<b>12.61</b>

Printed 5/11/2022 Page 31

Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Reach 4R: CURB CUT WIER

Elevation		Storage
(feet)	(sq-ft)	(cubic-feet)
387.25 387.26	0.0 0.0	0
387.27	0.0	0
387.28	0.1	0
387.29	0.1	0
387.30	0.2	1
387.31	0.2	1
387.32	0.2	1
387.33 387.34	0.2 0.3	1 1
387.35	0.3	1
387.36	0.3	1
387.37	0.4	1
387.38	0.4	2
387.39	0.4	2
387.40 387.41	0.4 0.5	2
387.42	0.5	2
387.43	0.5	2
387.44	0.6	2
387.45	0.6	2
387.46	0.6	3
387.47 387.48	0.7 0.7	ა 3
387.49	0.7	2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3 3 4
387.50	0.8	3
387.51	0.8	3
387.52	0.8	3
387.53 387.54	0.8 0.9	ა ვ
387.55	0.9	4
387.56	0.9	4
387.57	1.0	4
387.58	1.0	4
387.59 387.60	1.0 1.1	4 4
387.61	1.1	4
387.62	1.1	4
387.63	1.1	5
387.64	1.2	5
387.65 387.66	1.2 1.2	5 5
387.67	1.2	5
387.68	1.3	5
387.69	1.3	5
387.70	1.4	5
387.71	1.4	6
387.72 387.73	1.4 1.4	6 6
387.74	1.5	6
387.75	1.5	6

# Splash Carwash Bryant Prepared by Phillip Lewis Engineering

Little Rock Rainfall 5-yr Duration=16 min, Inten=4.09 in/hr
Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 32

#### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.84" for 5-yr event

Inflow = 3.36 cfs @ 0.16 hrs, Volume= 0.074 af

Outflow = 2.59 cfs @ 0.30 hrs, Volume= 0.074 af, Atten= 23%, Lag= 8.4 min

Primary = 2.59 cfs @ 0.30 hrs, Volume= 0.074 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 385.75' @ 0.30 hrs Surf.Area= 1,202 sf Storage= 1,253 cf

Plug-Flow detention time= 10.0 min calculated for 0.074 af (100% of inflow)

Center-of-Mass det. time= 10.4 min ( 22.9 - 12.4 )

Volume	Inv	ert Avai	I.Storage	Storage	Description	
#1	384.	50'	2,986 cf	Custom	Stage Data (Pri	ismatic) Listed below (Recalc)
Elevatio		Surf.Area (sq-ft)		c.Store pic-feet)	Cum.Store (cubic-feet)	
384.5	50	724		0	0	
385.0	00	986		428	428	
386.0	00	1,273		1,130	1,557	
387.0	00	1,585		1,429	2,986	
Device	Routing	In	vert Ou	tlet Device	s	
#1	Primary	384		0" Round		
				40 0' CN	D projecting no	baadwall Ka- 0 000

L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf


Primary OutFlow Max=2.59 cfs @ 0.30 hrs HW=385.75' (Free Discharge) 1=12" RCP (Inlet Controls 2.59 cfs @ 3.30 fps)

Prepared by Phillip Lewis Engineering


Page 33

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

**Pond 3P: DETENTION POND** 



**Pond 3P: DETENTION POND** 




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Pond 3P: DETENTION POND**

#### Stage-Area-Storage



## **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	Ó	384.50	0.00
0.50	0.00	439	385.01	0.78
1.00	0.00	82	384.61	0.04
1.50	0.00	42	384.56	0.01
2.00	0.00	28	384.54	0.01
2.50	0.00	20	384.53	0.00
3.00	0.00	16	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	10	384.51	0.00
4.50	0.00	8	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	5	384.51	0.00
6.00	0.00	4	384.51	0.00
6.50	0.00	3	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	1	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	0	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Splash Carwash Bryant

Little Rock Rainfall 5-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Pond 3P: DETENTION POND

Clayation	Drimon, I	Elevation	Drimon	Loyetien	Drimon
Elevation (feet)	Primary (cfs)	(feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50 2.53	386.72	3.92 3.94
384.70 384.72	0.13 0.16	385.72 385.74	2.53	386.74 386.76	3.94
384.74	0.10	385.76	2.60	386.78	3.98
384.76	0.13	385.78	2.64	386.80	4.01
384.78	0.26	385.80	2.67	386.82	4.03
384.80	0.29	385.82	2.70	386.84	4.05
384.82	0.33	385.84	2.74	386.86	4.07
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.59	385.96	2.93	386.98	4.20
384.96	0.64	385.98	2.96	387.00	4.22
384.98	0.69	386.00	2.99		
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91 0.97	386.08	3.10		
385.08 385.10	1.02	386.10 386.12	3.13 3.16		
385.12	1.02	386.14	3.10		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24		
385.18	1.26	386.20	3.27		
385.20	1.32	386.22	3.30		
385.22	1.38	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40 385.42	1.90 1.95	386.42 386.44	3.56 3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		

Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 37

## Stage-Area-Storage for Pond 3P: DETENTION POND

384.50     724     0       384.55     750     37       384.60     776     75       384.65     803     114       384.70     829     155       384.75     855     197       384.80     881     241       384.85     907     285       384.90     934     332	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
384.60       776       75         384.65       803       114         384.70       829       155         384.75       855       197         384.80       881       241         384.85       907       285	384.50	724	0
384.65       803       114         384.70       829       155         384.75       855       197         384.80       881       241         384.85       907       285			
384.75       855       197         384.80       881       241         384.85       907       285	384.65	803	114
384.80       881       241         384.85       907       285			
	384.80	881	241
384.95 960 379			
385.00 986 428 385.05 1,000 477			
385.10 1,015 528			
385.15 1,029 579 385.20 1,043 630			
385.25 1,058 683	385.25		
385.30 1,072 736 385.35 1,086 790			
385.40 1,101 845	385.40		845
385.45 1,115 900 385.50 1,130 956			
385.55 1,144 1,013	385.55	1,144	1,013
385.60 1,158 1,071 385.65 1,173 1,129			
385.70 1,173 1,129 1,187 1,188		•	
385.75 1,201 1,248 385.80 1,216 1,308			
385.85 1,230 1,369			
385.90 1,244 1,431 385.95 1,259 1,494			
386.00 1,273 1,494 1,557			
386.05       1,289       1,621         386.10       1,304       1,686			
386.15 1,320 1,751	386.15		
386.20 1,335 1,818 386.25 1,351 1,885			
386.30 1,367 1,953			
386.35 1,382 2,022 386.40 1,398 2,091			
386.45 1,413 2,161	386.45	1,413	2,161
386.50 1,429 2,233 386.55 1,445 2,304			
386.60 1,460 2,377		1,460	
386.65 1,476 2,450 386.70 1,491 2,525			
386.75 1,507 2,600	386.75	1,507	2,600
386.80       1,523       2,675         386.85       1,538       2,752			
386.90 1,554 2,829	386.90	1,554	2,829
386.95 1,569 2,907 387.00 <b>1,585 2,986</b>			

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 10-yr Duration=16 min, Inten=4.60 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 38

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

- - - - - -

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: PRE-DEVELOPMENT**Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=0.85"
Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=3.39 cfs 0.075 af

**Subcatchment 2S: POST-DEVELOPMENT** Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=0.94" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=3.77 cfs 0.083 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.23' Max Vel=5.50 fps Inflow=3.77 cfs 0.083 af n=0.013 L=4.0' S=0.0200 '/' Capacity=12.61 cfs Outflow=3.78 cfs 0.083 af

Pond 3P: DETENTION POND

Peak Elev=385.90' Storage=1,433 cf Inflow=3.78 cfs 0.083 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=2.83 cfs 0.083 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.158 af Average Runoff Depth = 0.89" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC


#### **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 3.39 cfs @ 0.26 hrs, Volume= 0.075 af, Depth= 0.85"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 10-yr Duration=16 min, Inten=4.60 in/hr

	rea (sf)	С	Description	1	
	31,035	0.65	GRAVEL F	ARKING	
	15,020	0.77	SHRUB PO	OOR CONE	DITION BRUSH
	46,055	0.69	Weighted A	Average	
	46,055		100.00% P	ervious Are	ea
Tc	Length	Slope	•	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE
					Range n= 0.130 P2= 4.19"

#### **Subcatchment 1S: PRE-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 10-yr Did

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

<b>-</b>	<b>5</b> "	ı <del></del> .	- ·	ı <del></del> .	<b>5</b> "
Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours) 5.10	(cfs)	(hours) 10.20	(cfs)
0.00 0.10	0.00 1.31	5.10	0.00 0.00	10.20	0.00 0.00
0.10	2.62	5.30	0.00	10.30	0.00
0.20	2.95	5.40	0.00	10.50	0.00
0.40	1.64	5.50	0.00	10.60	0.00
0.50	0.33	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40 1.50	0.00 0.00	6.50 6.60	0.00 0.00	11.60 11.70	0.00 0.00
1.60	0.00	6.70	0.00	11.70	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90	0.00	7.00	0.00		
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50 2.60	0.00 0.00	7.60 7.70	0.00 0.00		
2.70	0.00	7.70	0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60	0.00	8.70	0.00		
3.70 3.80	0.00 0.00	8.80 8.90	0.00 0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00 0.00	9.80 9.90	0.00 0.00		
4.80 4.90	0.00	10.00	0.00		
5.00	0.00	10.00	0.00		
<del>-</del>					

### **Summary for Subcatchment 2S: POST-DEVELOPMENT**


Runoff = 3.77 cfs @ 0.15 hrs, Volume= 0.083 af, Depth= 0.94"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 10-yr Duration=16 min, Inten=4.60 in/hr

	Α	rea (sf)	С	Description	1	
		22,479	0.95	ASPHALT	SURFACE	
		6,603	0.97	<b>ROOF TOP</b>	<b>D</b>	
		16,973	0.46	<b>GRASS LA</b>	NDSCAPI	NG
		46,055	0.77	Weighted A	Average	
		16,973		36.85% Pe	rvious Area	a e e e e e e e e e e e e e e e e e e e
		29,082		63.15% Im	pervious Ai	rea
	Тс	Length	Slope	•	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	6.7	40	0.0150	0.10		Sheet Flow, GRASS
						Grass: Dense n= 0.240 P2= 4.19"
	2.1	320	0.0150	2.49		Shallow Concentrated Flow, PAVEMENT
						Paved Kv= 20.3 fps
	8.8	360	Total			

### **Subcatchment 2S: POST-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 10-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours)	(cfs)	(hours)	(cfs)
0.00 0.10	0.00 <b>2.57</b>	5.10 5.20	0.00 0.00	10.20 10.30	0.00 0.00
0.20	3.77	5.30	0.00	10.40	0.00
0.30	2.92	5.40	0.00	10.50	0.00
0.40	0.34	5.50	0.00	10.60	0.00
0.50	0.00	5.60	0.00	10.70	0.00
0.60 0.70	0.00 0.00	5.70 5.80	0.00 0.00	10.80 10.90	0.00 0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20 1.30	0.00 0.00	6.30 6.40	0.00 0.00	11.40 11.50	0.00 0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70 1.80	0.00 0.00	6.80 6.90	0.00 0.00	11.90 12.00	0.00 0.00
1.90	0.00	7.00	0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30 2.40	0.00 0.00	7.40 7.50	0.00 0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90 3.00	0.00 0.00	8.00 8.10	0.00 0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40 3.50	0.00 0.00	8.50 8.60	0.00 0.00		
3.60	0.00	8.70	0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90 4.00	0.00 0.00	9.00 9.10	0.00 0.00		
4.00	0.00	9.10	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40 4.50	0.00 0.00	9.50 9.60	0.00 0.00		
4.50 4.60	0.00	9.60	0.00		
4.70	0.00	9.80	0.00		
4.80	0.00	9.90	0.00		
4.90 5.00	0.00 0.00	10.00 10.10	0.00 0.00		
5.00	0.00	10.10	0.00		
	'		·		

Splash Car Wash Bryant, Arkansas

### **Splash Carwash Bryant**

Little Rock Rainfall 10-yr Duration=16 min, Inten=4.60 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 43

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### **Summary for Reach 4R: CURB CUT WIER**

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.94" for 10-yr event

Inflow = 3.77 cfs @ 0.15 hrs, Volume= 0.083 af

Outflow =  $3.78 \text{ cfs } \bigcirc 0.16 \text{ hrs}$ , Volume= 0.083 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 5.50 fps, Min. Travel Time= 0.0 min Avg. Velocity = 4.37 fps, Avg. Travel Time= 0.0 min

Peak Storage= 3 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.23', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs

3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish


Length= 4.0' Slope= 0.0200 '/'

Inlet Invert= 387.25', Outlet Invert= 387.17'


Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 44

### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Reach 4R: CURB CUT WIER**



Splash Carwash Bryant

Little Rock Rainfall 10-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	Ó	387.25	0.00
0.50	0.00	0	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	0	387.25	0.00
2.00	0.00	0	387.25	0.00
2.50	0.00	0	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	0	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Printed 5/11/2022 Page 47

Splash Carwash Bryant

Little Rock Rainfall 10-yr Did

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation	Velocity	Discharge
(feet)	(ft/sec)	(cfs)
387.25	0.00	0.00
387.26	0.75	0.02
387.27	1.18	0.07
387.28	1.54	0.14
387.29	1.86	0.22
387.30	2.15	0.32
387.31	2.41	0.43
387.32	2.66	0.56
387.33	2.90	0.70
387.34	3.12	0.84
387.35	3.34	1.00
387.36	3.54	1.17
387.37	3.74	1.35
387.38	3.92	1.53
387.39	4.11	1.72
387.40	4.28	1.93
387.41	4.45	2.14
387.42	4.62	2.36
387.43	4.78	2.58
387.44	4.93	2.81
387.45	5.09	3.05
387.46	5.23	3.30
387.47	5.38	3.55
387.48	5.52	3.81
387.49	5.65	4.07
387.50	5.79	4.34
387.51	5.92	4.62
387.52	6.05	4.90
387.53	6.17	5.19
387.54	6.30	5.48
387.55	6.42	5.77
387.56	6.53	6.08
387.57	6.65	6.38
387.58	6.76	6.69
387.59	6.87	7.01
387.60	6.98	7.33
387.61	7.09	7.65
387.62	7.19	7.98
387.63	7.30	8.32
387.64	7.40	8.65
387.65	7.50	9.00
387.66	7.59	9.34
387.67	7.69	9.69
387.68	7.79	10.04
387.69	7.88	10.40
387.70	7.97	10.76
387.71	8.06	11.12
387.72	8.15	11.49
387.73	8.24	11.86
387.74	8.32	12.23
387.75	<b>8.41</b>	<b>12.61</b>

Splash Carwash Bryant

Little Rock Rainfall 10-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Reach 4R: CURB CUT WIER

Elevation	End-Area	Storage
(feet) 387.25	(sq-ft)	(cubic-feet)
387.26	0.0 0.0	0
387.27	0.1	0
387.28	0.1	0
387.29 387.30	0.1 0.2	0 1
387.31	0.2	1
387.32	0.2	1
387.33	0.2	1
387.34 387.35	0.3 0.3	1 1
387.36	0.3	1
387.37	0.4	1
387.38	0.4	2
387.39 387.40	0.4 0.4	2
387.41	0.5	2
387.42	0.5	2
387.43 387.44	0.5 0.6	2
387.45	0.6	2
387.46	0.6	3
387.47 387.48	0.7 0.7	3
387.49	0.7	3
387.50	0.8	2 2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3 3 4
387.51	0.8	3
387.52 387.53	0.8 0.8	ა 3
387.54	0.9	3
387.55	0.9	
387.56 387.57	0.9 1.0	4 4
387.58	1.0	4
387.59	1.0	4
387.60 387.61	1.1	4 4
387.62	1.1 1.1	4
387.63	1.1	
387.64	1.2	5
387.65 387.66	1.2 1.2	5 5
387.67	1.3	5
387.68	1.3	5 5 5 5 5 5 5
387.69 387.70	1.3 1.4	5 5
387.71	1.4	6
387.72	1.4	6
387.73 387.74	1.4 1.5	6 6
387.75	1.5 <b>1.5</b>	<b>6</b>

Little Rock Rainfall 10-yr Duration=16 min, Inten=4.60 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 49

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 0.94" for 10-yr event

Inflow = 3.78 cfs @ 0.16 hrs, Volume= 0.083 af

Outflow = 2.83 cfs @ 0.30 hrs, Volume= 0.083 af, Atten= 25%, Lag= 8.6 min

Primary = 2.83 cfs @ 0.30 hrs, Volume= 0.083 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 385.90' @ 0.30 hrs Surf.Area= 1,245 sf Storage= 1,433 cf

Plug-Flow detention time= 9.9 min calculated for 0.083 af (100% of inflow)


Center-of-Mass det. time= 10.3 min ( 22.7 - 12.4 )

Volume	Inve	ert Avai	l.Storage	Storage D	escription	
#1	384.5	50'	2,986 cf	Custom S	tage Data (Pri	ismatic) Listed below (Recalc)
Elevatio		Surf.Area (sq-ft)		:.Store c-feet)	Cum.Store (cubic-feet)	
384.5	50	724		0	0	
385.0	00	986		428	428	
386.0	00	1,273		1,130	1,557	
387.0	00	1,585		1,429	2,986	
Device	Routing	In	vert Outl	et Devices		
#1	Primary	384	.50' <b>12.0</b>	" Round 1	2" RCP	


L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf

Primary OutFlow Max=2.83 cfs @ 0.30 hrs HW=385.90' (Free Discharge) 1=12" RCP (Inlet Controls 2.83 cfs @ 3.61 fps)

#### **Pond 3P: DETENTION POND**



**Pond 3P: DETENTION POND** 




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Pond 3P: DETENTION POND**

#### Stage-Area-Storage



# **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	Ó	384.50	0.00
0.50	0.00	499	385.07	0.94
1.00	0.00	85	384.61	0.04
1.50	0.00	43	384.56	0.01
2.00	0.00	28	384.54	0.01
2.50	0.00	21	384.53	0.00
3.00	0.00	16	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	11	384.51	0.00
4.50	0.00	8	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	5	384.51	0.00
6.00	0.00	4	384.51	0.00
6.50	0.00	4	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	1	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	0	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Splash Carwash Bryant

Little Rock Rainfall 10-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Pond 3P: DETENTION POND

Elevation	Primary	Elevation	Primary	Elevation	Primary
(feet)	(cfs)	(feet)	(cfs)	(feet)	(cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50	386.72	3.92
384.70	0.13	385.72	2.53	386.74	3.94
384.72	0.16	385.74	2.57	386.76	3.96
384.74	0.19	385.76	2.60	386.78	3.98
384.76	0.22	385.78	2.64	386.80	4.01
384.78	0.26	385.80	2.67	386.82	4.03
384.80	0.20	385.82	2.70	386.84	4.05
384.82	0.23	385.84	2.74	386.86	4.07
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.55	385.96	2.09	386.98	4.10
384.96				387.00	4.20 <b>4.22</b>
	0.64 0.69	385.98	2.96 2.99	307.00	4.22
384.98		386.00			
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91	386.08	3.10		
385.08	0.97	386.10	3.13		
385.10	1.02	386.12	3.16		
385.12	1.08	386.14	3.19		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24		
385.18	1.26	386.20	3.27		
385.20	1.32	386.22	3.30		
385.22	1.38	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40	1.90	386.42	3.56		
385.42	1.95	386.44	3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		
	l			l	

Splash Carwash Bryant

Little Rock Rainfall 10-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Pond 3P: DETENTION POND

Elevation	Surface	Storage
(feet)	(sq-ft)	(cubic-feet)
384.50	724	0
384.55 384.60	750 776	37 75
384.65	803	114
384.70	829	155
384.75	855	197
384.80	881	241
384.85	907	285
384.90 384.95	934 960	332 379
385.00	986	428
385.05	1,000	477
385.10	1,015	528
385.15	1,029	579
385.20	1,043	630
385.25 385.30	1,058 1,072	683 736
385.35	1,086	790
385.40	1,101	845
385.45	1,115	900
385.50	1,130	956
385.55	1,144	1,013
385.60 385.65	1,158 1,173	1,071 1,129
385.70	1,187	1,188
385.75	1,201	1,248
385.80	1,216	1,308
385.85	1,230	1,369
385.90 385.95	1,244 1,259	1,431 1,494
386.00	1,273	1,557
386.05	1,289	1,621
386.10	1,304	1,686
386.15	1,320	1,751
386.20 386.25	1,335	1,818
386.30	1,351 1,367	1,885 1,953
386.35	1,382	2,022
386.40	1,398	2,091
386.45	1,413	2,161
386.50	1,429	2,233
386.55 386.60	1,445 1,460	2,304 2,377
386.65	1,476	2,450
386.70	1,491	2,525
386.75	1,507	2,600
386.80	1,523	2,675
386.85 386.90	1,538 1,554	2,752 2,829
386.95	1,569	2,829 2,907
387.00	1,585	2,986
	•	•

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 55

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: PRE-DEVELOPMENT Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=0.97" Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=3.90 cfs 0.086 af

**Subcatchment 2S: POST-DEVELOPMENT** Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=1.09" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=4.35 cfs 0.096 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.25' Max Vel=5.80 fps Inflow=4.35 cfs 0.096 af n=0.013 L=4.0' S=0.0200 '/' Capacity=12.61 cfs Outflow=4.36 cfs 0.096 af

Pond 3P: DETENTION POND

Peak Elev=386.11' Storage=1,698 cf Inflow=4.36 cfs 0.096 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=3.14 cfs 0.096 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.182 af Average Runoff Depth = 1.03" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac


### **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 3.90 cfs @ 0.26 hrs, Volume= 0.086 af, Depth= 0.97"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

A	rea (sf)	С	Description	1			
	31,035	0.65	GRAVEL P	ARKING			
	15,020	0.77	SHRUB PO	HRUB POOR CONDITION BRUSH			
	46,055	0.69	Weighted A	Average			
	46,055		100.00% P	ervious Are	ea		
Tc	Length	Slope	,	Capacity	Description		
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE		
					Range n= 0.130 P2= 4.19"		

#### **Subcatchment 1S: PRE-DEVELOPMENT**



Printed 5/11/2022 Page 57

Splash Carwash Bryant

Little Rock Rainfall 25-yr Did

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

Time	Runoff	Time	Runoff	Time	Runoff
(hours) 0.00	(cfs) 0.00	(hours) 5.10	(cfs) 0.00	(hours) 10.20	(cfs) 0.00
0.00	1.51	5.20	0.00	10.20	0.00
0.20	3.02	5.30	0.00	10.40	0.00
0.30	3.39	5.40	0.00	10.50	0.00
0.40 0.50	1.89 0.38	5.50 5.60	0.00 0.00	10.60 10.70	0.00 0.00
0.60	0.00	5.70	0.00	10.70	0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80 0.90	0.00 0.00	5.90 6.00	0.00 0.00	11.00 11.10	0.00 0.00
1.00	0.00	6.10	0.00	11.10	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30 1.40	0.00 0.00	6.40 6.50	0.00 0.00	11.50 11.60	0.00 0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70 1.80	0.00 0.00	6.80 6.90	0.00 0.00	11.90 12.00	0.00 0.00
1.90	0.00	7.00	0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20 2.30	0.00 0.00	7.30 7.40	0.00 0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60 2.70	0.00 0.00	7.70 7.80	0.00 0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00 3.10	0.00 0.00	8.10 8.20	0.00 0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40 3.50	0.00 0.00	8.50 8.60	0.00 0.00		
3.60	0.00	8.70	0.00		
3.70	0.00	8.80	0.00		
3.80 3.90	0.00 0.00	8.90 9.00	0.00 0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20 4.30	0.00 0.00	9.30 9.40	0.00 0.00		
4.40	0.00	9.40	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00 0.00	9.80 9.90	0.00 0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		
		I		1	

### **Summary for Subcatchment 2S: POST-DEVELOPMENT**


Runoff = 4.35 cfs @ 0.15 hrs, Volume= 0.096 af, Depth= 1.09"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

A	rea (sf)	С	Description	1		_
	22,479	0.95	ASPHALT	SURFACE		
	6,603	0.97	<b>ROOF TOP</b>	<b>D</b>		
	16,973	0.46	GRASS LA	NDSCAPI	NG	
•	46,055	0.77	Weighted A	Average		_
	16,973		36.85% Pe	rvious Area	a e e e e e e e e e e e e e e e e e e e	
	29,082		63.15% Im	pervious Ai	rea	
Tc	Length	Slope	Velocity	Capacity	Description	
/ • \						
<u>(min)</u>	(feet)	(ft/ft)	(ft/sec)	(cfs)		_
(min) 6.7	(feet) 40			(cfs)	Sheet Flow, GRASS	_
		(ft/ft)		(cfs)	Sheet Flow, GRASS Grass: Dense n= 0.240 P2= 4.19"	_
		(ft/ft)	0.10	(cfs)	•	_
6.7	40	(ft/ft) 0.0150	0.10	(cfs)	Grass: Dense n= 0.240 P2= 4.19"	_

#### Subcatchment 2S: POST-DEVELOPMENT



Splash Carwash Bryant

Little Rock Rainfall 25-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022 Page 59

# **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours)	(cfs)	(hours)	(cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	2.97	5.20	0.00	10.30	0.00
0.20	4.35	5.30	0.00	10.40	0.00
0.30	3.36	5.40	0.00	10.50	0.00
0.40 0.50	0.40 0.00	5.50 5.60	0.00 0.00	10.60 10.70	0.00 0.00
0.60	0.00	5.70	0.00	10.70	0.00
0.70	0.00	5.80	0.00	10.80	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90 2.00	0.00 0.00	7.00 7.10	0.00 0.00		
2.10	0.00	7.10	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30 8.40	0.00 0.00		
3.30 3.40	0.00 0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60	0.00	8.70	0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60 4.70	0.00 0.00	9.70 9.80	0.00 0.00		
4.70	0.00	9.80	0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		
		-			

Splash Car Wash Bryant, Arkansas

### **Splash Carwash Bryant**

Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 60

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### **Summary for Reach 4R: CURB CUT WIER**

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.09" for 25-yr event

Inflow = 4.35 cfs @ 0.15 hrs, Volume= 0.096 af

Outflow = 4.36 cfs @ 0.16 hrs, Volume= 0.096 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 5.80 fps, Min. Travel Time= 0.0 min Avg. Velocity = 4.60 fps, Avg. Travel Time= 0.0 min

Peak Storage= 3 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.25', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs


3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish

Length= 4.0' Slope= 0.0200 '/'


Inlet Invert= 387.25', Outlet Invert= 387.17'

Page 61

### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Reach 4R: CURB CUT WIER**



Splash Car Wash Bryant, Arkansas Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

Printed 5/11/2022 Page 63

Splash Carwash Bryant

Little Rock Rainfall 25-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	387.25	0.00
0.50	0.00	0	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	0	387.25	0.00
2.00	0.00	0	387.25	0.00
2.50	0.00	0	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	0	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Splash Carwash Bryant

Little Rock Rainfall 25-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation	Velocity	Discharge
(feet)	(ft/sec)	(cfs)
387.25	0.00	0.00
387.26	0.75	0.02
387.27	1.18	0.07
387.28	1.54	0.14
387.29	1.86	0.22
387.30	2.15	0.32
387.31	2.41	0.43
387.32	2.66	0.56
387.33	2.90	0.70
387.34	3.12	0.84
387.35	3.34	1.00
387.36	3.54	1.17
387.37	3.74	1.35
387.38	3.92	1.53
387.39	4.11	1.72
387.40	4.28	1.93
387.41	4.45	2.14
387.42	4.62	2.36
387.43	4.78	2.58
387.44	4.93	2.81
387.45	5.09	3.05
387.46	5.23	3.30
387.47	5.38	3.55
387.48	5.52	3.81
387.49	5.65	4.07
387.50	5.79	4.34
387.51	5.92	4.62
387.52	6.05	4.90
387.53	6.17	5.19
387.54	6.30	5.48
387.55	6.42	5.77
387.56	6.53	6.08
387.57	6.65	6.38
387.58	6.76	6.69
387.59	6.87	7.01
387.60	6.98	7.33
387.61	7.09	7.65
387.62	7.19	7.98
387.63	7.30	8.32
387.64	7.40	8.65
387.65	7.50	9.00
387.66	7.59	9.34
387.67	7.69	9.69
387.68	7.79	10.04
387.69	7.88	10.40
387.70	7.97	10.76
387.71	8.06	11.12
387.72	8.15	11.49
387.73	8.24	11.86
387.74	8.32	12.23
387.75	8.41	12.61

Splash Carwash Bryant

Little Rock Rainfall 25-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Reach 4R: CURB CUT WIER

Elevation	End-Area	Storage
(feet)	(sq-ft)	(cubic-feet)
387.25	0.0	0
387.26 387.27	0.0 0.1	0
387.28	0.1	0
387.29	0.1	0
387.30	0.2	1
387.31	0.2 0.2	1 1
387.32 387.33	0.2	1
387.34	0.3	1
387.35	0.3	1
387.36 387.37	0.3 0.4	1 1
387.38	0.4	2
387.39	0.4	2
387.40	0.4	2
387.41 387.42	0.5 0.5	2
387.43	0.5	2
387.44	0.6	2
387.45 387.46	0.6 0.6	2
387.47	0.0	3
387.48	0.7	3
387.49	0.7	2 2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3 4
387.50 387.51	0.8 0.8	3
387.52	0.8	3
387.53	0.8	3
387.54 387.55	0.9 0.9	3
387.56	0.9	4
387.57	1.0	4
387.58	1.0	4
387.59 387.60	1.0 1.1	4 4
387.61	1.1	4
387.62	1.1	4
387.63 387.64	1.1 1.2	5 5
387.65	1.2	
387.66	1.2	5 5
387.67	1.3 1.3	5
387.68 387.69	1.3	5 5
387.70	1.4	5
387.71	1.4	6
387.72 387.73	1.4 1.4	6 6
387.74	1.5	6
387.75	1.5	6

Little Rock Rainfall 25-yr Duration=16 min, Inten=5.30 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 66

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.09" for 25-yr event

Inflow = 4.36 cfs @ 0.16 hrs, Volume= 0.096 af

Outflow = 3.14 cfs @ 0.31 hrs, Volume= 0.096 af, Atten= 28%, Lag= 8.9 min

Primary = 3.14 cfs @ 0.31 hrs, Volume= 0.096 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 386.11' @ 0.31 hrs Surf.Area= 1,307 sf Storage= 1,698 cf

Plug-Flow detention time= 9.9 min calculated for 0.096 af (100% of inflow)


Center-of-Mass det. time= 10.2 min ( 22.7 - 12.4 )

Volume	Inv	ert Ava	il.Storage	Storage	Description	
#1	384.	50'	2,986 cf	Custon	n Stage Data (Pri	ismatic) Listed below (Recalc)
Elevation	<b>.</b> n	Surf.Area	ln	c.Store	Cum.Store	
			•••			
(fee		(sq-ft)	(cub	ic-feet)	(cubic-feet)	
384.5	50	724		0	0	
385.0	00	986		428	428	
386.0	00	1,273		1,130	1,557	
387.0	00	1,585		1,429	2,986	
Device	Routing	In	vert Out	let Device	es	
#1	Primary	384	1.50' <b>12.</b>	0" Round	1 12" RCP	


L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf

Primary OutFlow Max=3.14 cfs @ 0.31 hrs HW=386.11' (Free Discharge) 1=12" RCP (Inlet Controls 3.14 cfs @ 4.00 fps)

#### **Pond 3P: DETENTION POND**



#### **Pond 3P: DETENTION POND**




Splash Carwash Bryant

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

## **Pond 3P: DETENTION POND**

#### Stage-Area-Storage



# **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	384.50	0.00
0.50	0.00	600	385.17	1.23
1.00	0.00	90	384.62	0.05
1.50	0.00	44	384.56	0.01
2.00	0.00	29	384.54	0.01
2.50	0.00	21	384.53	0.00
3.00	0.00	16	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	11	384.51	0.00
4.50	0.00	9	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	6	384.51	0.00
6.00	0.00	4	384.51	0.00
6.50	0.00	4	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	1	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	0	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Splash Carwash Bryant

Little Rock Rainfall 25-yr Did

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022 Page 70

# Stage-Discharge for Pond 3P: DETENTION POND

Elevation	Primary	Elevation	Primary	Elevation	Primary
(feet)	(cfs)	(feet)	(cfs)	(feet)	(cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50	386.72	3.92
384.70	0.13	385.72	2.53	386.74	3.94
384.72 384.74	0.16 0.19	385.74 385.76	2.57 2.60	386.76 386.78	3.96 3.98
384.74 384.76	0.19	385.78	2.64	386.80	3.96 4.01
384.78	0.22	385.80	2.67	386.82	4.01
384.80	0.20	385.82	2.70	386.84	4.05
384.82	0.23	385.84	2.74	386.86	4.03
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.59	385.96	2.93	386.98	4.20
384.96	0.64	385.98	2.96	387.00	4.22
384.98	0.69	386.00	2.99		
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91	386.08	3.10		
385.08	0.97	386.10	3.13		
385.10	1.02	386.12	3.16		
385.12	1.08	386.14	3.19		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24 3.27		
385.18 385.20	1.26 1.32	386.20 386.22	3.27		
385.22	1.32	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40	1.90	386.42	3.56		
385.42	1.95	386.44	3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		

Printed 5/11/2022 Page 71

Splash Carwash Bryant

Little Rock Rainfall 25-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# Stage-Area-Storage for Pond 3P: DETENTION POND

Elevation	Surface	Storage
(feet)	(sq-ft)	(cubic-feet)
384.50	724	0
384.55	750	37
384.60	776	75
384.65 384.70	803 829	114 155
384.75	855	197
384.80	881	241
384.85	907	285
384.90	934	332
384.95	960	379
385.00 385.05	986 1,000	428 477
385.10	1,015	528
385.15	1,029	579
385.20	1,043	630
385.25	1,058	683
385.30	1,072	736
385.35 385.40	1,086 1,101	790 845
385.45	1,115	900
385.50	1,130	956
385.55	1,144	1,013
385.60	1,158	1,071
385.65	1,173	1,129
385.70 385.75	1,187 1,201	1,188 1,248
385.80	1,216	1,308
385.85	1,230	1,369
385.90	1,244	1,431
385.95	1,259	1,494
386.00	1,273	1,557
386.05 386.10	1,289 1,304	1,621 1,686
386.15	1,320	1,751
386.20	1,335	1,818
386.25	1,351	1,885
386.30	1,367	1,953
386.35 386.40	1,382 1,398	2,022 2,091
386.45	1,413	2,161
386.50	1,429	2,233
386.55	1,445	2,304
386.60	1,460	2,377
386.65	1,476	2,450
386.70 386.75	1,491 1,507	2,525 2,600
386.80	1,523	2,675
386.85	1,538	2,752
386.90	1,554	2,829
386.95	1,569	2,907
387.00	1,585	2,986

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 50-yr Duration=16 min, Inten=5.84 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 72

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: PRE-DEVELOPMENT Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=1.07" Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=4.30 cfs 0.095 af

**Subcatchment 2S: POST-DEVELOPMENT** Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=1.20" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=4.79 cfs 0.106 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.27' Max Vel=6.00 fps Inflow=4.79 cfs 0.106 af n=0.013 L=4.0' S=0.0200 '/' Capacity=12.61 cfs Outflow=4.80 cfs 0.106 af

Pond 3P: DETENTION POND

Peak Elev=386.27' Storage=1,914 cf Inflow=4.80 cfs 0.106 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=3.37 cfs 0.106 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.200 af Average Runoff Depth = 1.14" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac


### **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 4.30 cfs @ 0.26 hrs, Volume= 0.095 af, Depth= 1.07"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 50-yr Duration=16 min, Inten=5.84 in/hr

	rea (sf)	С	Description	1		
	31,035	0.65	GRAVEL F	PARKING		
	15,020	0.77	SHRUB PO	OOR CONE	DITION BRUSH	
	46,055	0.69	Weighted A	Average		
	46,055		100.00% P	00.00% Pervious Area		
Tc	3	Slope	•	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE	
					Range n= 0.130 P2= 4.19"	

#### **Subcatchment 1S: PRE-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

<b>-</b>	<b>5</b> "		- · · ·	ı <del></del> .	<b>5</b> "
Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours) 5.10	(cfs)	(hours) 10.20	(cfs)
0.00 0.10	0.00 1.66	5.10	0.00 0.00	10.20	0.00 0.00
0.10	3.33	5.30	0.00	10.30	0.00
0.20	3.74	5.40	0.00	10.50	0.00
0.40	2.08	5.50	0.00	10.60	0.00
0.50	0.42	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40 1.50	0.00 0.00	6.50 6.60	0.00 0.00	11.60 11.70	0.00 0.00
1.60	0.00	6.70	0.00	11.70	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90	0.00	7.00	0.00		
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50 2.60	0.00 0.00	7.60 7.70	0.00 0.00		
2.70	0.00	7.70	0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60	0.00	8.70	0.00		
3.70 3.80	0.00 0.00	8.80 8.90	0.00 0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20	0.00	9.30	0.00		
4.30	0.00	9.40	0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00 0.00	9.80 9.90	0.00 0.00		
4.80	0.00	10.00	0.00		
5.00	0.00	10.00	0.00		

### **Summary for Subcatchment 2S: POST-DEVELOPMENT**


Runoff = 4.79 cfs @ 0.15 hrs, Volume= 0.106 af, Depth= 1.20"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 50-yr Duration=16 min, Inten=5.84 in/hr

_	Α	rea (sf)	С	Description	)				
		22,479	0.95	.95 ASPHALT SURFACE					
		6,603	0.97	<b>ROOF TOP</b>	<b>-</b>				
_		16,973	0.46	GRASS LA	NDSCAPI	NG			
		46,055	0.77	Weighted A	Average				
		16,973		36.85% Pe	rvious Area	a			
		29,082		63.15% Im	pervious Ai	rea			
	To	Longth	Clono	Volocity	Canacity	Description			
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description			
-					(015)	Object Floor ORAGO			
	6.7	40	0.0150	0.10		Sheet Flow, GRASS			
	0.4	000	0.0450	0.40		Grass: Dense n= 0.240 P2= 4.19"			
	2.1	320	0.0150	2.49		Shallow Concentrated Flow, PAVEMENT			
_						Paved Kv= 20.3 fps			
	88	360	Total						

### **Subcatchment 2S: POST-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

# **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

T:	D	T:	Duneff	T:	D #
Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	3.27	5.20	0.00	10.30	0.00
0.20	4.79	5.30	0.00	10.40	0.00
0.30	3.70	5.40	0.00	10.50	0.00
0.40	0.44	5.50	0.00	10.60	0.00
0.50 0.60	0.00 0.00	5.60 5.70	0.00 0.00	10.70 10.80	0.00 0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10 1.20	0.00 0.00	6.20 6.30	0.00 0.00	11.30 11.40	0.00 0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80 1.90	0.00 0.00	6.90 7.00	0.00 0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30	0.00	7.40 7.50	0.00		
2.40 2.50	0.00 0.00	7.50 7.60	0.00 0.00		
2.60	0.00	7.70	0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90 3.00	0.00 0.00	8.00 8.10	0.00 0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50 3.60	0.00 0.00	8.60 8.70	0.00 0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10 4.20	0.00 0.00	9.20 9.30	0.00 0.00		
4.20	0.00	9.40	0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00	9.80 9.90	0.00		
4.80 4.90	0.00 0.00	9.90 10.00	0.00 0.00		
5.00	0.00	10.10	0.00		

Splash Car Wash Bryant, Arkansas

#### **Splash Carwash Bryant**

Little Rock Rainfall 50-yr Duration=16 min, Inten=5.84 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 77

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Summary for Reach 4R: CURB CUT WIER

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.20" for 50-yr event

Inflow = 4.79 cfs @ 0.15 hrs, Volume= 0.106 af

Outflow = 4.80 cfs @ 0.16 hrs, Volume= 0.106 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 6.00 fps, Min. Travel Time= 0.0 min Avg. Velocity = 4.77 fps, Avg. Travel Time= 0.0 min

Peak Storage= 3 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.27', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs


3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish

Length= 4.0' Slope= 0.0200 '/'


Inlet Invert= 387.25', Outlet Invert= 387.17'

Page 78


#### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**



#### **Reach 4R: CURB CUT WIER**



Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	Ó	387.25	0.00
0.50	0.00	0	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	0	387.25	0.00
2.00	0.00	0	387.25	0.00
2.50	0.00	0	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	0	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation (feet)	Velocity (ft/sec)	Discharge (cfs)
387.25 387.26	0.00 0.75	0.00
387.27	1.18	0.07
387.28 387.29	1.54 1.86	0.14 0.22
387.30	2.15	0.32
387.31 387.32	2.41 2.66	0.43 0.56
387.33	2.90	0.70
387.34 387.35	3.12 3.34	0.84 1.00
387.36	3.54	1.17
387.37 387.38	3.74 3.92	1.35 1.53
387.39	4.11	1.72
387.40 387.41	4.28 4.45	1.93 2.14
387.42	4.62	2.36
387.43 387.44	4.78 4.93	2.58 2.81
387.45	5.09	3.05
387.46 387.47	5.23 5.38	3.30 3.55
387.48	5.52	3.81
387.49 387.50	5.65 5.79	4.07 4.34
387.51	5.92	4.62
387.52 387.53	6.05 6.17	4.90 5.19
387.54	6.30	5.48
387.55 387.56	6.42 6.53	5.77 6.08
387.57	6.65	6.38
387.58 387.59	6.76 6.87	6.69 7.01
387.60	6.98	7.33
387.61 387.62	7.09 7.19	7.65 7.98
387.63	7.30	8.32
387.64 387.65	7.40 7.50	8.65 9.00
387.66 387.67	7.59	9.34
387.68	7.69 7.79	9.69 10.04
387.69	7.88	10.40
387.70 387.71 387.72	7.97 8.06	10.76 11.12
387.72 387.73	8.15 8.24	11.49 11.86
387.74	8.32	12.23
387.75	8.41	12.61

Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### Stage-Area-Storage for Reach 4R: CURB CUT WIER

Elevation	End-Area	Storage
(feet) 387.25	(sq-ft)	(cubic-feet)
387.26	0.0 0.0	0
387.27	0.1	0
387.28	0.1	0
387.29 387.30	0.1 0.2	0 1
387.31	0.2	1
387.32	0.2	1
387.33	0.2	1
387.34 387.35	0.3 0.3	1 1
387.36	0.3	1
387.37	0.4	1
387.38	0.4	2
387.39 387.40	0.4 0.4	2
387.41	0.5	2
387.42	0.5	2
387.43 387.44	0.5 0.6	2
387.45	0.6	2
387.46	0.6	3
387.47 387.48	0.7 0.7	3
387.49	0.7	3
387.50	0.8	2 2 2 2 2 2 2 2 2 3 3 3 3 3 3 3 3 3 4
387.51	0.8	3
387.52 387.53	0.8 0.8	ა 3
387.54	0.9	3
387.55	0.9	
387.56 387.57	0.9 1.0	4 4
387.58	1.0	4
387.59	1.0	4
387.60 387.61	1.1	4 4
387.62	1.1 1.1	4
387.63	1.1	
387.64	1.2	5
387.65 387.66	1.2 1.2	5 5
387.67	1.3	5
387.68	1.3	5 5 5 5 5 5 5
387.69 387.70	1.3 1.4	5 5
387.71	1.4	6
387.72	1.4	6
387.73 387.74	1.4 1.5	6 6
387.75	1.5 <b>1.5</b>	<b>6</b>

Little Rock Rainfall 50-yr Duration=16 min, Inten=5.84 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 83

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.20" for 50-yr event

Inflow = 4.80 cfs @ 0.16 hrs, Volume= 0.106 af

Outflow = 3.37 cfs @ 0.31 hrs, Volume= 0.106 af, Atten= 30%, Lag= 9.0 min

Primary = 3.37 cfs @ 0.31 hrs, Volume= 0.106 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 386.27' @ 0.31 hrs Surf.Area= 1,358 sf Storage= 1,914 cf

Plug-Flow detention time= 9.9 min calculated for 0.106 af (100% of inflow)


Center-of-Mass det. time= 10.3 min ( 22.7 - 12.4 )

Volume	Inve	ert Avai	I.Storage	Storage	Description	
#1	384.5	50'	2,986 cf	Custom	Stage Data (Pri	smatic) Listed below (Recalc)
Elevatio		Surf.Area (sq-ft)		:.Store c-feet)	Cum.Store (cubic-feet)	
384.5	50	724		0	0	
385.0	0	986		428	428	
386.0	0	1,273		1,130	1,557	
387.0	0	1,585		1,429	2,986	
Device	Routing	ln	vert Outl	et Devices	5	
#1	Primary	384	.50' <b>12.0</b>	" Round	12" RCP	


L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf

Primary OutFlow Max=3.37 cfs @ 0.31 hrs HW=386.27' (Free Discharge) 1=12" RCP (Inlet Controls 3.37 cfs @ 4.29 fps)

#### **Pond 3P: DETENTION POND**




#### **Pond 3P: DETENTION POND**



# Splash Carwash Bryant Prepared by Phillip Lewis Engineering HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Stage-Area-Storage

**Pond 3P: DETENTION POND** 



#### **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	384.50	0.00
0.50	0.00	697	385.26	1.51
1.00	0.00	93	384.62	0.05
1.50	0.00	45	384.56	0.01
2.00	0.00	29	384.54	0.01
2.50	0.00	21	384.53	0.00
3.00	0.00	17	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	11	384.51	0.00
4.50	0.00	9	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	6	384.51	0.00
6.00	0.00	4	384.51	0.00
6.50	0.00	4	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	1	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	0	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Page 87

Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### Stage-Discharge for Pond 3P: DETENTION POND

Elevation	Primary	Elevation	Primary	Elevation	Primary
(feet)	(cfs)	(feet)	(cfs)	(feet)	(cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50	386.72	3.92
384.70	0.13	385.72	2.53	386.74	3.94
384.72	0.16	385.74	2.57	386.76	3.96
384.74	0.19	385.76	2.60	386.78	3.98
384.76	0.22	385.78	2.64	386.80	4.01
384.78	0.26	385.80	2.67	386.82	4.03
384.80	0.29	385.82	2.70	386.84	4.05
384.82	0.33	385.84	2.74	386.86	4.07
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.59	385.96	2.93	386.98	4.20
384.96	0.64	385.98	2.96	387.00	4.22
384.98	0.69	386.00	2.99		
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91	386.08	3.10		
385.08	0.97	386.10	3.13		
385.10	1.02	386.12	3.16		
385.12	1.08	386.14	3.19		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24		
385.18	1.26	386.20	3.27		
385.20	1.32	386.22	3.30		
385.22	1.38	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40	1.90	386.42	3.56		
385.42	1.95	386.44	3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		
				1	

Page 88

Splash Carwash Bryant

Little Rock Rainfall 50-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Stage-Area-Storage for Pond 3P: DETENTION POND

Elevation	Surface	Storage
(feet)	(sq-ft)	(cubic-feet)
384.50 384.55	724 750	0 37
384.60	730 776	75
384.65	803	114
384.70	829	155
384.75	855	197
384.80	881	241
384.85	907	285
384.90	934	332
384.95 385.00	960 986	379 428
385.05	1,000	477
385.10	1,015	528
385.15	1,029	579
385.20	1,043	630
385.25	1,058	683
385.30 385.35	1,072 1,086	736 790
385.40	1,101	845
385.45	1,115	900
385.50	1,130	956
385.55	1,144	1,013
385.60	1,158	1,071
385.65 385.70	1,173 1,187	1,129 1,188
385.75	1,201	1,248
385.80	1,216	1,308
385.85	1,230	1,369
385.90	1,244	1,431
385.95	1,259	1,494
386.00 386.05	1,273 1,289	1,557 1,621
386.10	1,304	1,686
386.15	1,320	1,751
386.20	1,335	1,818
386.25	1,351	1,885
386.30	1,367	1,953
386.35 386.40	1,382 1,398	2,022 2,091
386.45	1,413	2,091
386.50	1,429	2,233
386.55	1,445	2,304
386.60	1,460	2,377
386.65	1,476	2,450
386.70 386.75	1,491 1,507	2,525
386.75 386.80	1,507	2,600 2,675
386.85	1,538	2,752
386.90	1,554	2,829
386.95	1,569	2,907
387.00	1,585	2,986

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 100-yr Duration=16 min, Inten=6.31 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 89

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

----

Time span=0.00-12.00 hrs, dt=0.01 hrs, 1201 points
Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: PRE-DEVELOPMENT Runoff Area=46,055 sf 0.00% Impervious Runoff Depth=1.16" Flow Length=270' Slope=0.0250 '/' Tc=15.5 min C=0.69 Runoff=4.65 cfs 0.102 af

Subcatchment 2S: POST-DEVELOPMENT Runoff Area=46,055 sf 63.15% Impervious Runoff Depth=1.30" Flow Length=360' Slope=0.0150 '/' Tc=8.8 min C=0.77 Runoff=5.18 cfs 0.114 af

**Reach 4R: CURB CUT WIER**Avg. Flow Depth=0.28' Max Vel=6.18 fps Inflow=5.18 cfs 0.114 af n=0.013 L=4.0' S=0.0200'/ Capacity=12.61 cfs Outflow=5.19 cfs 0.114 af

Pond 3P: DETENTION POND

Peak Elev=386.41' Storage=2,110 cf Inflow=5.19 cfs 0.114 af 12.0" Round Culvert n=0.011 L=10.0' S=0.0500 '/' Outflow=3.55 cfs 0.114 af

Total Runoff Area = 2.115 ac Runoff Volume = 0.216 af Average Runoff Depth = 1.23" 68.43% Pervious = 1.447 ac 31.57% Impervious = 0.668 ac

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 90

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC


#### **Summary for Subcatchment 1S: PRE-DEVELOPMENT**

Runoff = 4.65 cfs @ 0.26 hrs, Volume= 0.102 af, Depth= 1.16"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 100-yr Duration=16 min, Inten=6.31 in/hr

A	rea (sf)	С	Description	1	
	31,035	0.65	GRAVEL P	ARKING	
	15,020	0.77	SHRUB PO	OR CONE	DITION BRUSH
	46,055	0.69	Weighted A	Average	
	46,055		100.00% P	ervious Are	ea
Tc	Length	Slope	,	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
15.5	270	0.0250	0.29		Sheet Flow, SHEET FLOW SURFACE
					Range n= 0.130 P2= 4.19"

#### **Subcatchment 1S: PRE-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Hydrograph for Subcatchment 1S: PRE-DEVELOPMENT**

Time	Runoff	Time	Runoff	Time	Runoff
(hours)	(cfs)	(hours)	(cfs)	(hours)	(cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	1.80	5.20	0.00	10.30	0.00
0.20	3.59	5.30	0.00	10.40	0.00
0.30	4.04	5.40	0.00	10.50	0.00
0.40	2.25	5.50	0.00	10.60	0.00
0.50	0.45	5.60	0.00	10.70	0.00
0.60	0.00	5.70	0.00	10.80	0.00
0.70 0.80	0.00 0.00	5.80 5.90	0.00 0.00	10.90 11.00	0.00 0.00
0.80	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.10	0.00
1.10	0.00	6.20	0.00	11.30	0.00
1.20	0.00	6.30	0.00	11.40	0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80	0.00	6.90	0.00	12.00	0.00
1.90	0.00	7.00	0.00		
2.00 2.10	0.00 0.00	7.10 7.20	0.00 0.00		
2.10	0.00	7.20	0.00		
2.30	0.00	7.40	0.00		
2.40	0.00	7.50	0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90	0.00	8.00	0.00		
3.00	0.00	8.10	0.00		
3.10	0.00	8.20	0.00		
3.20 3.30	0.00 0.00	8.30 8.40	0.00 0.00		
3.40	0.00	8.50	0.00		
3.50	0.00	8.60	0.00		
3.60	0.00	8.70	0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10	0.00	9.20	0.00		
4.20	0.00	9.30	0.00		
4.30 4.40	0.00 0.00	9.40 9.50	0.00 0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70	0.00	9.80	0.00		
4.80	0.00	9.90	0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 92

#### Summary for Subcatchment 2S: POST-DEVELOPMENT


Runoff = 5.18 cfs @ 0.15 hrs, Volume= 0.114 af, Depth= 1.30"

Routed to Reach 4R: CURB CUT WIER

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Little Rock Rainfall 100-yr Duration=16 min, Inten=6.31 in/hr

	Α	rea (sf)	С	Description	1			
		22,479	0.95	ASPHALT SURFACE				
		6,603	0.97	<b>ROOF TOP</b>	<b>D</b>			
		16,973	0.46	<b>GRASS LA</b>	NDSCAPI	NG		
		46,055	0.77	Weighted A	Average			
		16,973		36.85% Pe	rvious Area	a e e e e e e e e e e e e e e e e e e e		
		29,082		63.15% Im	pervious Ai	rea		
	Тс	Length	Slope	•	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	6.7	40	0.0150	0.10		Sheet Flow, GRASS		
						Grass: Dense n= 0.240 P2= 4.19"		
	2.1	320	0.0150	2.49		Shallow Concentrated Flow, PAVEMENT		
						Paved Kv= 20.3 fps		
	8.8	360	Total					

#### **Subcatchment 2S: POST-DEVELOPMENT**



Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Hydrograph for Subcatchment 2S: POST-DEVELOPMENT**

Time	Dunoff	Time	Dunoff	l Time	Dunoff
Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)	Time (hours)	Runoff (cfs)
0.00	0.00	5.10	0.00	10.20	0.00
0.10	3.53	5.20	0.00	10.30	0.00
0.20	5.18	5.30	0.00	10.40	0.00
0.30	4.00	5.40	0.00	10.50	0.00
0.40	0.47	5.50	0.00	10.60	0.00
0.50 0.60	0.00 0.00	5.60 5.70	0.00 0.00	10.70 10.80	0.00 0.00
0.70	0.00	5.80	0.00	10.90	0.00
0.80	0.00	5.90	0.00	11.00	0.00
0.90	0.00	6.00	0.00	11.10	0.00
1.00	0.00	6.10	0.00	11.20	0.00
1.10 1.20	0.00 0.00	6.20 6.30	0.00 0.00	11.30 11.40	0.00 0.00
1.30	0.00	6.40	0.00	11.50	0.00
1.40	0.00	6.50	0.00	11.60	0.00
1.50	0.00	6.60	0.00	11.70	0.00
1.60	0.00	6.70	0.00	11.80	0.00
1.70	0.00	6.80	0.00	11.90	0.00
1.80 1.90	0.00 0.00	6.90 7.00	0.00 0.00	12.00	0.00
2.00	0.00	7.10	0.00		
2.10	0.00	7.20	0.00		
2.20	0.00	7.30	0.00		
2.30 2.40	0.00 0.00	7.40 7.50	0.00 0.00		
2.50	0.00	7.60	0.00		
2.60	0.00	7.70	0.00		
2.70	0.00	7.80	0.00		
2.80	0.00	7.90	0.00		
2.90 3.00	0.00 0.00	8.00 8.10	0.00 0.00		
3.10	0.00	8.20	0.00		
3.20	0.00	8.30	0.00		
3.30	0.00	8.40	0.00		
3.40	0.00	8.50	0.00		
3.50 3.60	0.00 0.00	8.60 8.70	0.00 0.00		
3.70	0.00	8.80	0.00		
3.80	0.00	8.90	0.00		
3.90	0.00	9.00	0.00		
4.00	0.00	9.10	0.00		
4.10 4.20	0.00 0.00	9.20 9.30	0.00 0.00		
4.30	0.00	9.40	0.00		
4.40	0.00	9.50	0.00		
4.50	0.00	9.60	0.00		
4.60	0.00	9.70	0.00		
4.70 4.80	0.00 0.00	9.80 9.90	0.00 0.00		
4.90	0.00	10.00	0.00		
5.00	0.00	10.10	0.00		
				1	

Splash Car Wash Bryant, Arkansas

**Splash Carwash Bryant** 

Little Rock Rainfall 100-yr Duration=16 min, Inten=6.31 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 94

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Summary for Reach 4R: CURB CUT WIER**

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.30" for 100-yr event

Inflow = 5.18 cfs @ 0.15 hrs, Volume= 0.114 af

Outflow = 5.19 cfs @ 0.16 hrs, Volume= 0.114 af, Atten= 0%, Lag= 0.6 min

Routed to Pond 3P: DETENTION POND

Routing by Stor-Ind+Trans method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs

Max. Velocity= 6.18 fps, Min. Travel Time= 0.0 min Avg. Velocity = 4.91 fps, Avg. Travel Time= 0.0 min

Peak Storage= 3 cf @ 0.16 hrs

Average Depth at Peak Storage= 0.28', Surface Width= 3.00' Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.61 cfs


3.00' x 0.50' deep channel, n= 0.013 Concrete, trowel finish

Length= 4.0' Slope= 0.0200 '/'


Inlet Invert= 387.25', Outlet Invert= 387.17'

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Reach 4R: CURB CUT WIER**




#### **Reach 4R: CURB CUT WIER**



Splash Carwash Bryant

Little Rock Rainfall 100-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Reach 4R: CURB CUT WIER**



Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Printed 5/11/2022 Page 97

#### Hydrograph for Reach 4R: CURB CUT WIER

Time	Inflow	Storage	Elevation	Outflow
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	387.25	0.00
0.50	0.00	0	387.25	0.00
1.00	0.00	0	387.25	0.00
1.50	0.00	0	387.25	0.00
2.00	0.00	0	387.25	0.00
2.50	0.00	0	387.25	0.00
3.00	0.00	0	387.25	0.00
3.50	0.00	0	387.25	0.00
4.00	0.00	0	387.25	0.00
4.50	0.00	0	387.25	0.00
5.00	0.00	0	387.25	0.00
5.50	0.00	0	387.25	0.00
6.00	0.00	0	387.25	0.00
6.50	0.00	0	387.25	0.00
7.00	0.00	0	387.25	0.00
7.50	0.00	0	387.25	0.00
8.00	0.00	0	387.25	0.00
8.50	0.00	0	387.25	0.00
9.00	0.00	0	387.25	0.00
9.50	0.00	0	387.25	0.00
10.00	0.00	0	387.25	0.00
10.50	0.00	0	387.25	0.00
11.00	0.00	0	387.25	0.00
11.50	0.00	0	387.25	0.00
12.00	0.00	0	387.25	0.00

Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

### Stage-Discharge for Reach 4R: CURB CUT WIER

Elevation (feet)	Velocity (ft/sec)	Discharge (cfs)
387.25 387.26	0.00 0.75	0.00 0.02
387.27 387.28	1.18 1.54	0.07 0.14
387.29	1.86	0.22
387.30 387.31	2.15 2.41	0.32 0.43
387.32	2.66	0.56
387.33 387.34	2.90 3.12	0.70 0.84
387.35	3.34	1.00
387.36 387.37	3.54 3.74	1.17 1.35
387.38	3.92	1.53
387.39 387.40	4.11 4.28	1.72 1.93
387.41	4.45	2.14
387.42 387.43	4.62 4.78	2.36 2.58
387.44	4.93	2.81
387.45 387.46	5.09 5.23	3.05 3.30
387.47	5.38	3.55
387.48 387.49	5.52 5.65	3.81 4.07
387.50	5.79	4.34
387.51 387.52	5.92 6.05	4.62 4.90
387.53	6.17	5.19
387.54 387.55	6.30 6.42	5.48 5.77
387.56	6.53	6.08
387.57 387.58	6.65 6.76	6.38 6.69
387.59	6.76	7.01
387.60 387.61	6.98 7.09	7.33 7.65
387.62	7.09 7.19	7.65
387.63	7.30	8.32 8.65
387.64 387.65	7.40 7.50	9.00
387.66 387.67	7.59 7.69	9.34 9.69
387.68	7.09	10.04
387.69	7.88	10.40
387.70 387.71	7.97 8.06	10.76 11.12
387.71 387.72 387.73	8.15 8.24	11.49 11.86
387.73	8.24 8.32	12.23
387.75	8.41	12.61

Printed 5/11/2022

Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

Page 99

#### Stage-Area-Storage for Reach 4R: CURB CUT WIER

387.25         0.0         0           387.26         0.0         0           387.27         0.1         0           387.28         0.1         0           387.29         0.1         0           387.30         0.2         1           387.31         0.2         1           387.32         0.2         1           387.33         0.2         1           387.34         0.3         1           387.35         0.3         1           387.36         0.3         1           387.37         0.4         1           387.38         0.4         2           387.39         0.4         2           387.40         0.4         2           387.41         0.5         2           387.42         0.5         2           387.43         0.5         2           387.44         0.6         2           387.45         0.6         2           387.46         0.6         3           387.49         0.7         3           387.50         0.8         3           387.51         0.8 <th>Elevation</th> <th>End-Area</th> <th>Storage (cubic-feet)</th>	Elevation	End-Area	Storage (cubic-feet)
387.75 <b>1.5</b> 6	(feet)  387.25 387.26 387.27 387.28 387.29 387.30 387.31 387.32 387.33 387.34 387.35 387.36 387.37 387.38 387.40 387.41 387.42 387.43 387.44 387.45 387.46 387.47 387.48 387.50 387.51 387.52 387.53 387.54 387.55 387.56 387.57 387.58 387.59 387.60 387.61 387.62 387.63 387.63 387.64 387.63	(sq-ft)  0.0  0.0  0.1  0.1  0.1  0.2  0.2  0.2	(cubic-feet) 0 0 0 0 1 1 1 1 1 1 1 1 2 2 2 2 2 2 2 3 3 3 3 3
	387.75	1.5	6

Little Rock Rainfall 100-yr Duration=16 min, Inten=6.31 in/hr

Prepared by Phillip Lewis Engineering

Printed 5/11/2022 Page 100

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Summary for Pond 3P: DETENTION POND**

Inflow Area = 1.057 ac, 63.15% Impervious, Inflow Depth = 1.30" for 100-yr event

Inflow = 5.19 cfs @ 0.16 hrs, Volume= 0.114 af

Outflow = 3.55 cfs @ 0.31 hrs, Volume= 0.114 af, Atten= 32%, Lag= 9.2 min

Primary = 3.55 cfs @ 0.31 hrs, Volume= 0.114 af

Routing by Stor-Ind method, Time Span= 0.00-12.00 hrs, dt= 0.01 hrs Peak Elev= 386.41' @ 0.31 hrs Surf.Area= 1,402 sf Storage= 2,110 cf

Plug-Flow detention time= 10.4 min calculated for 0.114 af (100% of inflow)

Center-of-Mass det. time= 10.4 min ( 22.8 - 12.4 )


Volume	Inv	ert Ava	I.Storage	Storage	Description	
#1	384.	50'	2,986 cf	Custom	Stage Data (Pri	smatic) Listed below (Recalc)
Elevation		Surf.Area		c.Store	Cum.Store	
(fee	et)	(sq-ft)	(cub	ic-feet)	(cubic-feet)	
384.5	50	724		0	0	
385.0	00	986		428	428	
386.0	00	1,273		1,130	1,557	
387.0	00	1,585		1,429	2,986	
Device	Routing	In	vert Out	let Device	es	
#1	Primary	384	.50' <b>12.0</b>	" Round	I 12" RCP	

L= 10.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 384.50' / 384.00' S= 0.0500 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 0.79 sf


Primary OutFlow Max=3.55 cfs @ 0.31 hrs HW=386.41' (Free Discharge) 1=12" RCP (Inlet Controls 3.55 cfs @ 4.52 fps)

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Pond 3P: DETENTION POND**



**Pond 3P: DETENTION POND** 




Page 102

Splash Carwash Bryant

Little Rock Rainfall 100-yr Do
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Pond 3P: DETENTION POND**

#### Stage-Area-Storage



Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **Hydrograph for Pond 3P: DETENTION POND**

Time	Inflow	Storage	Elevation	Primary
(hours)	(cfs)	(cubic-feet)	(feet)	(cfs)
0.00	0.00	0	384.50	0.00
0.50	0.00	797	385.36	1.78
1.00	0.00	97	384.63	0.06
1.50	0.00	46	384.56	0.01
2.00	0.00	29	384.54	0.01
2.50	0.00	21	384.53	0.00
3.00	0.00	17	384.52	0.00
3.50	0.00	13	384.52	0.00
4.00	0.00	11	384.51	0.00
4.50	0.00	9	384.51	0.00
5.00	0.00	7	384.51	0.00
5.50	0.00	6	384.51	0.00
6.00	0.00	5	384.51	0.00
6.50	0.00	4	384.50	0.00
7.00	0.00	3	384.50	0.00
7.50	0.00	2	384.50	0.00
8.00	0.00	2	384.50	0.00
8.50	0.00	2	384.50	0.00
9.00	0.00	1	384.50	0.00
9.50	0.00	1	384.50	0.00
10.00	0.00	1	384.50	0.00
10.50	0.00	1	384.50	0.00
11.00	0.00	1	384.50	0.00
11.50	0.00	0	384.50	0.00
12.00	0.00	0	384.50	0.00

Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Stage-Discharge for Pond 3P: DETENTION POND

Elevation	Primary	Elevation	Primary	Elevation	Primary
(feet)	(cfs)	(feet)	(cfs)	(feet)	(cfs)
384.50	0.00	385.52	2.15	386.54	3.70
384.52	0.00	385.54	2.19	386.56	3.73
384.54	0.01	385.56	2.23	386.58	3.75
384.56	0.01	385.58	2.27	386.60	3.78
384.58	0.02	385.60	2.31	386.62	3.80
384.60	0.03	385.62	2.35	386.64	3.82
384.62	0.05	385.64	2.39	386.66	3.85
384.64	0.07	385.66	2.43	386.68	3.87
384.66	0.09	385.68	2.46	386.70	3.89
384.68	0.11	385.70	2.50	386.72	3.92
384.70	0.13	385.72	2.53	386.74	3.94
384.72	0.16	385.74	2.57	386.76	3.96
384.74	0.19	385.76	2.60	386.78	3.98
384.76	0.22	385.78	2.64	386.80	4.01
384.78	0.26	385.80	2.67	386.82	4.03
384.80	0.29	385.82	2.70	386.84	4.05
384.82	0.33	385.84	2.74	386.86	4.07
384.84	0.37	385.86	2.77	386.88	4.09
384.86	0.41	385.88	2.80	386.90	4.12
384.88	0.45	385.90	2.83	386.92	4.14
384.90	0.50	385.92	2.86	386.94	4.16
384.92	0.55	385.94	2.89	386.96	4.18
384.94	0.59	385.96	2.93	386.98	4.20
384.96	0.64	385.98	2.96	387.00	4.22
384.98	0.69	386.00	2.99	007.00	7.22
385.00	0.75	386.02	3.02		
385.02	0.80	386.04	3.04		
385.04	0.85	386.06	3.07		
385.06	0.91	386.08	3.10		
385.08	0.97	386.10	3.13		
385.10	1.02	386.12	3.16		
385.12	1.08	386.14	3.19		
385.14	1.14	386.16	3.22		
385.16	1.20	386.18	3.24		
385.18	1.26	386.20	3.27		
385.20	1.32	386.22	3.30		
385.22	1.38	386.24	3.32		
385.24	1.44	386.26	3.35		
385.26	1.50	386.28	3.38		
385.28	1.56	386.30	3.40		
385.30	1.62	386.32	3.43		
385.32	1.68	386.34	3.46		
385.34	1.74	386.36	3.48		
385.36	1.79	386.38	3.51		
385.38	1.85	386.40	3.53		
385.40	1.90	386.42	3.56		
385.42	1.95	386.44	3.58		
385.44	2.00	386.46	3.61		
385.46	2.04	386.48	3.63		
385.48	2.08	386.50	3.66		
385.50	2.11	386.52	3.68		

Splash Carwash Bryant

Little Rock Rainfall 100-yr Du
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### Stage-Area-Storage for Pond 3P: DETENTION POND

Elevation	Surface	Storage
(feet)	(sq-ft)	(cubic-feet)
384.50	724	0
384.55	750	37
384.60	776	75 114
384.65 384.70	803 829	155
384.75	855	197
384.80	881	241
384.85	907	285
384.90	934	332
384.95 385.00	960 986	379 428
385.05	1,000	477
385.10	1,015	528
385.15	1,029	579
385.20	1,043	630
385.25 385.30	1,058 1,072	683 736
385.35	1,072	790
385.40	1,101	845
385.45	1,115	900
385.50	1,130	956
385.55 385.60	1,144 1,158	1,013 1,071
385.65	1,173	1,129
385.70	1,187	1,188
385.75	1,201	1,248
385.80	1,216	1,308
385.85 385.90	1,230 1,244	1,369 1,431
385.95	1,244	1,494
386.00	1,273	1,557
386.05	1,289	1,621
386.10	1,304	1,686
386.15 386.20	1,320	1,751
386.25	1,335 1,351	1,818 1,885
386.30	1,367	1,953
386.35	1,382	2,022
386.40	1,398	2,091
386.45 386.50	1,413 1,429	2,161 2,233
386.55	1,429	2,233
386.60	1,460	2,377
386.65	1,476	2,450
386.70	1,491	2,525
386.75 386.80	1,507 1,523	2,600 2,675
386.85	1,523	2,752
386.90	1,554	2,829
386.95	1,569	2,907
387.00	1,585	2,986

## Splash Car Wash Bryant, Arkansas *Table of Contents*Printed 5/11/2022

#### **Splash Carwash Bryant**

Prepared by Phillip Lewis Engineering

HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

#### **TABLE OF CONTENTS**

#### **Project Reports**

- 1 Routing Diagram
- 2 Area Listing (all nodes)
- 3 Pipe Listing (all nodes)

#### 2-yr Event

- 4 Node Listing
- 5 Subcat 1S: PRE-DEVELOPMENT
- 7 Subcat 2S: POST-DEVELOPMENT
- 9 Reach 4R: CURB CUT WIER
- 15 Pond 3P: DETENTION POND

#### 5-yr Event

- 21 Node Listing
- 22 Subcat 1S: PRE-DEVELOPMENT
- 24 Subcat 2S: POST-DEVELOPMENT
- 26 Reach 4R: CURB CUT WIER
- 32 Pond 3P: DETENTION POND

#### 10-yr Event

- 38 Node Listing
- 39 Subcat 1S: PRE-DEVELOPMENT
- 41 Subcat 2S: POST-DEVELOPMENT
- 43 Reach 4R: CURB CUT WIER
- 49 Pond 3P: DETENTION POND

#### 25-yr Event

- 55 Node Listing
- 56 Subcat 1S: PRE-DEVELOPMENT
- 58 Subcat 2S: POST-DEVELOPMENT
- 60 Reach 4R: CURB CUT WIER
- 66 Pond 3P: DETENTION POND

#### 50-yr Event

- 72 Node Listing
- 73 Subcat 1S: PRE-DEVELOPMENT
- 75 Subcat 2S: POST-DEVELOPMENT
- 77 Reach 4R: CURB CUT WIER
- 83 Pond 3P: DETENTION POND

#### <u> 100-yr Event</u>


- 89 Node Listing
- 90 Subcat 1S: PRE-DEVELOPMENT
- 92 Subcat 2S: POST-DEVELOPMENT
- 94 Reach 4R: CURB CUT WIER

Splash Car Wash Bryant, Arkansas Table of Contents Printed 5/11/2022

Splash Carwash Bryant
Prepared by Phillip Lewis Engineering
HydroCAD® 10.10-7c s/n 12520 © 2022 HydroCAD Software Solutions LLC

100 Pond 3P: DETENTION POND

**o** 2



EXPRESS TUNNEL SPLASH CARWASH

REVISIONS:

PROJECT NO. 21129 DATE: APRIL 22, 2022

BUILDING ELEVATIONS

A6.01

S C M A R C H I T E C T S P.L.L.C.

PHILLIP LEWIS ENGINEERING, INC. Structural/Civil Design 23620 Interstate 30 Bryant, AR 72022

May 25, 2022

Colton Leonard Planning Department 210 SW 3<sup>rd</sup> Street City of Bryant, AR

Re: DRC staff comments for Splash Carwash

Mr. Leonard,

Please let this letter to serve as our written response to DRC comments provided 5/19/22.

#### 1. Splash Carwash

#### **Engineering**

- 1. Utility Plan indicates Oil/Water/Sand Separator is sized for a max flow of 314 GPM. What is the maximum demand on Domestic Water and Sewer? Does it match the sizing? Carwash Has recycle wash and only uses approx. 25 gallons per car totaling maximum use of 60 gallons per minute
- 2. Oil/Water/Sand Separator will require a permit. See Code Enforcement. Will pull permit with building permit
- 3. Verify there is no Bathroom (public or private) on site. There is a bathroom in the wash tunnel office
- 4. Provide Stormwater Calculations and Design for 2-,5-,10-, 25-, 50-, & 100-yr Events. **PROVIDED.**
- 5. Verify wash water will be contained on site and not collecting in Detention Basin. Wash water will be contained and processed through the separator to the sewer system not the storm water
- 6. Verify Floodplain data for site. Does site require an Elevation Certificate? Property is not in the floodplain
- 7. Discuss Half-Street Improvements along Reynolds (183) will improve by adding required sidewalk
- 8. Discuss Half-Street Improvements along Evans Loop. Will widen to 28' bc-bc and provide sidewalk as planned

#### **Public Works**

- 1. Concrete detail for all concrete shown on sheet C 1.4 shall show a concrete rating of 4000 PSI, 3000 PSI is not allowable in the Bryant Minimum Standards for Streets Specifications. All concrete on site will be 4000 psi not 3000 and noted on detail sheet
- Stabilization rules need to be added to the erosion control plan. "DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS STOPPED FOR AT LEAST 14 DAYS, SHALL BE TEMPORARILY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS." Note added as requested
- 3. Verify wash water will be contained on site and not collecting in Detention Basin. Wash water is not collected in detention it is routed through separator then to sanitary
- 4. Site will need a Small Scale Development Permit from ADEQ. provided

PHILLIP LEWIS ENGINEERING, INC. Structural/Civil Design 23620 Interstate 30 Bryant, AR 72022

- 5. Note on plans to specify whom and how often the catch basin filter sack will be checked and maintenanced. Note added on SWPPP plan
- 6. Discuss Half-Street Improvements along Evans Loop. Same as above
- 7. Further Discussion of Basin Design. Added trickle channel, outlow pipe changed to RCP and added a concrete overflow 6" below pond top
- 8. Note added to plans thats states "Site must comply with all Bryant Minimum Standards for Streets Specifications. Noted added to plans

#### **Planning**

- 1. What material are the architectural panels made of? Tresspa aluminum composite panels
- 2. Aluminum storefront Is this ACP? yes
- 3. Where is the payment kiosk overhang in relation to the building setback line? Kiosk Canopy is within the building setback line
- 4. Vacuums on east side of lot are located within the BSL. Vac equipment moved to a new island outside the BSL the vac hose stands are agreed to be left inside the Curb Line as shown
- 5. WBD plan shows a proposed trail along Evans Loop. Plat shows sidewalk. Road width is 22ft to BOC for local roads with trail spec. agreed to build offsite sidewalk and HCP ramps connecting our proposed sidewalks along Reynolds and Evans loop with unconnected sidewalks in LIEU of 12' Trail.

If you have any questions, please call or email. (501) 831-9870 mark@philliplewisengineering.com
Sincerely,

Mark Blakeley Phillip Lewis Engineering



City of Bryant, Arkansas Community Development 210 SW 3<sup>rd</sup> Street Bryant, AR 72022 501-943-0943

5/25/2022 Staff Approved CZ 1 Sign

#### SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form.

The Sign Ordinance is available at www.cityofbrys	ant.com under the Planning and Community
Developme	ent tab.
Date: 5/23/2022	Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.
Sign Co. or Sign Owner	Property Owner
Name L. Graphics  Address 70/ N. Reynolds Rd  City, State, Zip Bryant, AR72022  Phone (501) 653-4444	Name Vape City Somke Tobacco Address 3411 Main & Swife 3 City, State, Zip Boggart, AR72022
Phone (501) 653-4444	Phone (501) 909-754-7777
Email Address Joe a LG raphix. com	Email Address
Name of Business VAPUTY SMOKE TANDERS Address/Location of sign 3411 MCV STORMS Zoning Classification  Please use following page to provide details on the provided on this application, a Site Plan showing plate property is required to be submitted. Renderings of required to be submitted with the application. A this collected at the time of permit issuance. According to special sign permit request shall be one hundred doller required by Sign Administrator.	signs requesting approval. Along with information accement of sign(s) and any existing sign(s) on the the sign(s) showing the correct dimensions is also rty-five dollar (\$35) per sign payment will be to the Sign Ordinance a fee for and sign variance or
READ CAREFULLY BEFORE SIGNING	
and correct. I fully understand that the terms of the Sign Ordinan signs must fully comply with all terms of the Sign Ordinance regar authorized by the owner of the property and that I am authorized	dless of approval. I further certify that the proposed sign is

that no sign may be placed in public right of way. I understand that I must comply with all Building and Electrical Codes and that it is my responsibility to obtain all necessary permits.

### Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering.

SIGN	<b>Type</b> (Façade, Pole, Monument, other)	<b>Dimensions</b> (Height, Length, Width)	Sqft (Measured in whole as rectangle)	Height of Sign (Measured from lot surface)		Column for Admin Certifying Approval
	Wall want cabint	-15/x2/	30	Top of Sign	Bottom of Sign	
А	usall mount	15'X 2	30	16	14	
В					,	
С						
Е						
F						
G						

