



Bryant Development and Review Committee Meeting

Boswell Municipal Complex - City Hall Conference Room

210 SW 3rd Street

Date: May 29, 2025 - **Time:** 9:00 AM

Call to Order

Old Business

1. 6221 Hwy 5 - Ste. 1 - Site Addition for Deck

Paul Clark - Requesting Site Plan Approval for Deck Addition

- [0960-PLN-01.pdf](#)

2. Springhill Storage - Arey Dr - Site Plan

GarNat Engineering - Requesting Site Plan Approval

- [0962-RSP-02.pdf](#)
- [0962-RSP-01.pdf](#)
- [0962-PLN-01.pdf](#)

3. Bethel Middle School - Solar Field Project - Site Plan

Scenic Hill Solar - Requesting Recommendation Site Plan Approval

- [0957-SWPPP-01.pdf](#)
- [0957-SPEC-01.pdf](#)
- [0957-PLN-02.pdf](#)
- [0957-SMP-01.pdf](#)
- [0957-404-01.pdf](#)

New Business

4. Outdoor Storage Yard - I-30 Frontage Road - Site Plan

Hope Consulting - Requesting Site Plan Approval

- [0966-PLN-01.pdf](#)
- [0966-DRN-01.pdf](#)

5. Good Day Farm - 3205 Hwy 5 - Site Plan

Regan Etheridge - Requesting Site Plan Approval

- [0967-ELV-01.pdf](#)
- [0967-PLN-01.pdf](#)
- [0967-LTR-01.pdf](#)

6. Subdivision Signage - Midland Road Estates - Sign Permit

Lektron LED Technologies - Requesting Sign Permit Approval

- [93762-SGNAPP-01.pdf](#)

Staff Approved

7. La Ta Da Learning and Creative Arts - 5920 Hwy 5 Ste. 5 & 6-7

Rod's Signs - Requesting Sign Permit Approval - STAFF APPROVED


- [093790-SGNAPP-01.pdf](#)

Permit Report

Adjournments

PAUL CLARK
(501) 258 3635
Paul.Clark 0715 @ iCloud.com

6221 AR-5
#1





DRC Staff Comments 5/15/25

Vernon Williams <garnatengineering@gmail.com>

Wed, May 21, 2025 at 8:43 AM

To: Colton Leonard <cleonard@cityofbryant.com>

Cc: Jennifer Williams <jennifergarnat@gmail.com>, Shak Mukhitdinov <shakgarnat@gmail.com>, Tariq Morshed <tariqgarnat@gmail.com>

Colton,

See GNE's responses to your comments below in **RED**.

Vernon J. Williams, P.E.

GarNat Engineering, LLC

Mailing Address:

Physical Address:

P.O. Box 116

3825 Mt Carmel Road

Benton, AR 72018

Bryant, AR 72022

Ph: (501) 408-4650

Cell: (501) 425-2771

www.garnatengineering.com

On Tue, May 20, 2025 at 11:00 AM Colton Leonard <cleonard@cityofbryant.com> wrote:

Verenon,

Below are the comments from the DRC meeting. If you have any questions, just let us know.

Best,
Colton

GNE General Comment.....We are not trying to fully develop this site at this time. The property owner is trying to utilize some capital gains from the sale of another property to purchase this land and do some minimal improvements - grading, fencing, one structure and a previously promised fire hydrant. The new structure is a style that has not been previously built at the facility - covered RV parking

. They want to build one to see how well it rents before they build more. They are trying to keep costs low for this experiment. After a decision is made on the long term development of this property, we will bring a full site plan package back.

1. Springhill Storage Rezoning/ site plan

Public Works

1. Submit a complete site plan, showing access, utilities and other improvements on-site **We believe that the attached revised plans consitute a complete package for this limited project.**

Stormwater

1. Stormwater Calculations will be required **We respectfully request that we be allowed to postpone this until we bring the entire project forward. Please note that the detention required for the previously approved project was already constructed. The only impervious surface included in this phase of the project is the roof of the structure. However, that structure will have gravel under it, not pavement, so water will still be allowed to soak in even where it is built.**

Engineering

1. See Stormwater Comments **No response.**
2. Driveway apron must meet ARDOT requirements **We do not have a driveway apron in the scope of this project.**

Planning

1. Sign will need to be posted on property 15 days in advance of the meeting. **See attached photo of sign posted as discussed with Colton.**

2. Provide proof of publication from the Courier once that is run. **Will comply. In the meantime, we've attached our receipt for the purchasing the ad.**
3. Provide a copy of the green return receipts once those are received. **See attached.**
4. Are there no plans to put any structures on this property? **See general comment.**
5. Building setbacks for C-2 are 15ft Side and Front, 25ft rear. **We acknowledge your comment. There is no front setback. We do not plan on building against the rear or west setback at this time. We'd like to leave the east setback at 25' to allow for grading.**
6. With the CUP application that was previously approved, a condition was placed on the property that the fencing had to be visually solid around that new section of the storage facility. That will need to be shown on the Site Plan. **We have added a wooden fence to the site plan.**
7. Before future plans are approved to expand the storage use to the portion of the property being rezoned, a CUP would be required for the new piece of property. **We agree. See general comment at the beginning of the email.**

Fire





1. No Comment. **There were comments in a separate email. We'll provide those responses separately.**

[Quoted text hidden]

5 attachments



Zoning Sign.JPG
356K

-  **Springhill Storage - Arey Drive - C1.0 SITE PLAN-R2.pdf**
968K
-  **Proof for Ad to be ran 5-17-25.pdf**
46K
-  **Receipt Printed from Order 00187787_2025-05-16-09-57-40.pdf**
43K
-  **Certified mailing receipts.pdf**
227K



Colton Leonard <cleonard@cityofbryant.com>

Fwd: Springhill Storage Site Plan

Vernon Williams <garnatengineering@gmail.com>

Wed, May 21, 2025 at 8:44 AM

To: dslack@cityofbryant.com, Colton Leonard <cleonard@cityofbryant.com>, Jennifer Williams <jennifergarnat@gmail.com>, Tariq Morshed <tariqgarnat@gmail.com>, Shak Mukhitdinov <shakgarnat@gmail.com>

See GNE responses below in **RED**.

Vernon J. Williams, P.E.

GarNat Engineering, LLC

Mailing Address:

Physical Address:

P.O. Box 116

3825 Mt Carmel Road

Benton, AR 72018

Bryant, AR 72022

Ph: (501) 408-4650

Cell: (501) 425-2771

www.garnatengineering.com

----- Forwarded message -----

From: **Jennifer Williams** <jennifergarnat@gmail.com>

Date: Tue, May 20, 2025 at 11:20 AM

Subject: Fwd: Springhill Storage Site Plan

To: <cleonard@cityofbryant.com>

Cc: Vernon Williams <garnatengineering@gmail.com>

Colton,

Fire Marshall comments below for your records.

Thanks,

Jennifer

----- Forwarded message -----

From: **David Slack** <dslack@cityofbryant.com>

Date: Thu, May 15, 2025 at 3:41 PM

Subject: Springhill Storage Site Plan

To: <jennifergarnat@gmail.com>

Hell Mrs. Williams,


After the DRC meeting today, I looked up the fire hydrant and fire apparatus access requirements. The Arkansas Fire Prevention Code, 2021 Edition is the current applicable code.

- A fire apparatus access road is required to extend to within 150 feet of any portion of the facility. [Vol1, Section 503.1.1] **I believe that we comply.**
- The fire apparatus access road shall support the imposed load of a fire apparatus weighing 75,000 pounds, [Appendix D102.1] and shall be surfaced to provide all-weather driving capabilities. [503.2.3] **Will comply.**
- Dead-end fire apparatus access roads in excess of 150 feet need to have an approved area for turning around. [Appendix D103.4, Figure D103.1] Current plans will be adequate if you can show that one of the turnaround conditions is met on the plans. I have attached a copy of Appendix D and I suspect the current site plan has enough room for the 96' diameter cul-de-sac requirement. **We have drawn the limits of a 96' diameter cul-de-sac on our site plan.**

A fire hydrant is required to be within 400 feet of any portion of the facility. [507.5.1] The closest hydrant is about 420 feet south of the lot line in the storage building area. A fire hydrant placed at the entrance to this area will provide adequate coverage under this provision. **The previously approved plans included a fire main extension and hydrant. We have added the proposed fire hydrant location to our site plan. We propose to build it as part of this phase of the project.**

[Quoted text hidden]

 **Appendix D - Fire Apparatus Access Roads.pdf**
3100K



BY	
REVISION	
DATE	
1	
2	
3	
4	

Designing our client's success
GarNat Engineering, LLC
P.O. Box 116 Benton, AR 72018 Ph (501) 408-4650
3825 Mt Camel Rd Bryant, AR 72022 garnateengineering@gmail.com

RV STORAGE LAYOUT
FOR: TISDALE PROPERTIES & DEVELOPMENT LLC - AREY DRIVE
CITY OF BRYANT
SALINE COUNTY, ARKANSAS

STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
KERNON J. WILLIAMS
NO. 9551

05-02-2025

CONTENTS:
SITE, GRADING, AND DRAINAGE PLAN

PROJECT NO:
25008

DATE:
APRIL 2025

SHEET NO:
C1.0

Stormwater Pollution Prevention Plan (SWPPP) for Construction Activity for Large Construction Sites

**National Pollutant Discharge Elimination System (NPDES)
General Permit # ARR150000**

**Prepared for:
Sun Hog Solar – Bryant School District (SD)
Bryant, Arkansas**

**Date:
May 15, 2025**



A  **terracon** Company

ARR150000 – Scenic Hill Solar – Bryant SD

Project Name and Location: Scenic Hill Solar –Bryant SDProperty Parcel Number (Optional): 840-11623-030Operator Name and Address: SCENIC HILL SOLAR XLV, LLC

A. Site Description

- a. Project description intended use after NOI is filed: Scenic Hill Solar plans on creating a solar array near Bryant, Arkansas on the Scenic Hill Solar site. The subject property is approximately 11.35 acres of soil disturbance, with a total site area of approximately 27.45 acres.
- b. Sequence of major activities which disturb soils: NOC's will be posted, BMPs will be installed. The array area will be cleared, array installed and seeded within 14 days of earth disturbing activities are completed.
- c. Total Area¹: 27.45 Disturbed Area²: 11.35
- d. Soils Information:
- Runoff Coefficient Pre-Construction (See Appendix A) : 0.10
 - Runoff Coefficient Post-Construction (See Appendix A) : 0.38
 - Describe the soil or the quality of any discharge from the site: silt loam

B. Responsible Parties

Be sure to assign all SWPPP related activities to an individual or position; even if the specific individual is not yet known (i.e. contractor has not been chosen).

Individual/Company	Phone Number	Service Provided for SWPPP (i.e., Inspector, SWPPP revisions, Stabilization Activities, BMP Maintenance, etc.)
Brian Brown	713-826-0630	Inspector, Construction Manager
Carrie Kyhl	501-707-0555	Responsible Official

C. Receiving Waters

- a. The following waterbody (or waterbodies) receives stormwater from this construction site: Unnamed tributaries to Hurricane Creek, to Hurricane Lake, then to Saline River thence to the Ouachita River
- b. Is the project located within the jurisdiction of an MS4? ☒ Yes ☐ No
- If yes, Name of MS4: City of Bryant
- c. Ultimate Receiving Water:
- | | |
|--|--|
| <input type="checkbox"/> Red River | <input type="checkbox"/> White River |
| <input checked="" type="checkbox"/> Ouachita River | <input type="checkbox"/> St. Francis River |
| <input type="checkbox"/> Arkansas River | <input type="checkbox"/> Mississippi River |

D. Documentation of Permit Eligibility Related to the 303(d) list and Total Maximum Daily Loads (TMDL) (<https://www.adeg.state.ar.us/water/planning/>)

a. Does the stormwater enter a waterbody on the 303(d) list or with an approved TMDL? ☐ Yes ☒ No

b. If yes:

i. Waterbody identified on 303(d) list: _____

ii. Pollutant addressed on 303(d) list or TMDL: _____

iii. This specific project, or generally construction activity i.e. surface erosion, is identified on 303(d) list or associated assumptions and allocations identified in the TMDL for the discharge: ☐ Yes ☐ No

iv. Additional controls implemented: _____

E. Attainment of Water Quality Standards After Authorization

a. Sediment- and erosion-control measures along the construction project such as silt fences and rock check dams will be installed prior to ground disturbing activities begin to minimize the discharge of sediment and other pollutants into surrounding water bodies. The controls will be implemented and updated as necessary to be stringent enough to prevent an excursion above applicable water quality standards.

b. At any time after authorization, the Department may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, the Department will require the permittee to:

i. Develop a supplemental BMP action plan describing SWPPP modifications to address adequately the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

ii. Cease discharges of pollutants from construction activity and submit an individual permit application.

I understand and agree to follow the above text regarding the attainment of water quality standards after authorization. ☒ Yes ☐ No

F. Site Map Requirements (Attach Site Map):

a. Pre-construction topographic view;

- b. Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
- c. Delineate on the site map areas of soil disturbance and areas that will not be disturbed under the coverage of this permit;
- d. Location of major structural and nonstructural controls identified in the plan;
- e. Location of main construction entrance and exit;
- f. Location where stabilization practices are expected to occur;
- g. Locations of off-site materials, waste, borrow area, or equipment storage area;
- h. Location of areas used for concrete wash-out;
- i. Location of all surface water bodies (including wetlands) with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
- j. Locations where stormwater is discharged to a surface water and/or municipal separate storm sewer system if applicable,
- k. Locations where stormwater is discharged off-site (should be continuously updated);
- l. Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
- m. A legend that identifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
- n. Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

G. Stormwater Controls

- a. Initial Site Stabilization, Erosion and Sediment Controls, and Best Management Practices:

- i. Initial Site Stabilization: Most of the present vegetation will be cleared. Erosion- and sediment-control BMPs will be installed as necessary to protect drainage paths prior to earth-disturbing activities.
- ii. Erosion and Sediment Controls: good housekeeping practices, BMP installation before clearing begins, maintenance completed within 14 days of an inspection report noting deficiencies.
- iii. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the operator will replace or modify the control for site situations: ☒ Yes ☐ No

If No, explain: _____

- iv. Off-site accumulations of sediment will be removed at a frequency sufficient to minimize off-site impacts: ☒ Yes ☐ No
If No, explain: _____
- v. Sediment will be removed from sediment traps or sedimentation ponds when design capacity has been reduced by 50%: ☒ Yes ☐ No
If No, explain: _____
- vi. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges: ☒ Yes ☐ No
If No, explain: _____
- vii. Off-site material storage areas used solely by the permitted project are being covered by this SWPPP: ☐ Yes ☒ No
If Yes, explain additional BMPs implemented at off-site material storage area: _____

b. Stabilization Practices

- i. Description and Schedule: For this project, adequate measures needed to limit erosion at this site will consist of installing silt fencing and/or rock check dams as needed. Specifically, areas around newly disturbed and graded surfaces will be protected using primarily silt fences, rock check dams as needed, and a gravel site entrance to reduce erosion and sediment transport.
- ii. Are buffer areas required? ☒ Yes ☐ No
If Yes, are buffer areas being used? ☒ Yes ☐ No

If Yes, describe natural buffer areas: natural buffer areas will remain at a minimum of 25 feet from any jurisdictional wetland and streams

If No, explain why not: _____

- iii. A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included with the plan. ☒ Yes ☐ No

If No, explain: _____

iv. Deadlines for stabilization:

1. Stabilization procedures will be initiated 14 days after construction activity temporarily ceases on a portion of the site.
2. Stabilization procedures will be initiated immediately in portions of the site where construction activities have permanently ceased.

c. Structural Practices

- i. Describe any structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site: Silt fences will be installed, and rock check dams will be used to slow water down if needed.
- ii. Describe Velocity Dissipation Devices: Rock check dams and hay bales will be utilized as velocity dissipation devices.

iii. Sediment Basins:

Are 10 or more acres draining to a common point? ☐ Yes ☒ No

Is a sediment basin included in the project? ☐ Yes ☒ No

If Yes, what is the designed capacity for the storage?

☐ 3600 cubic feet per acre = : _____

or

☐ 10 year, 24 hour storm = : _____

☐ Other criteria were used to design basin: _____

If No, explain why no sedimentation basin was included and describe required natural buffer areas and other controls implemented instead: Natural buffers, silt fences and the amount of room left on the site prevents a sediment pond. Scenic Hill Solar has met with City of Bryant to mitigate the sediment pond.

H. Other Controls

- a. Solid materials, including building materials, shall be prevented from being discharged to Waters of the State: ☒ Yes ☐ No

- b. Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of:

☒ A stabilized construction entrance and exit

☐ Vehicle tire washing

☐ Other controls, describe: _____

- c. Temporary Sanitary Facilities: If temporary sanitary facilities are needed, they will be placed inside the silt fence to prevent site runoff from leaving the site.

d. Concrete Waste Area Provided:

☒ Yes

☐ No. Concrete is used on the site, but no concrete washout is provided.

Explain why: _____

☐ N/A, no concrete will be used with this project

e. Fuel Storage Areas, Hazardous Waste Storage, and Truck Wash Areas: _____

I. Non-Stormwater Discharges

a. The following allowable non-stormwater discharges comingled with stormwater are present or anticipated at the site:

☐ Fire-fighting activities;

☐ Fire hydrant flushings;

☐ Water used to wash vehicles (where detergents or other chemicals are not used) or control dust in accordance with Part II.A.4.H.2;

☐ Potable water sources including uncontaminated waterline flushings;

☐ Landscape Irrigation;

☐ Routine external building wash down which does not use detergents or other chemicals;

☐ Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents or other chemicals are not used;

☐ Uncontaminated air conditioning, compressor condensate (See Part I.B.13.C of the permit);

☐ Uncontaminated springs, excavation dewatering and groundwater (See Part I.B.13.C of the permit);

☐ Foundation or footing drains where flows are not contaminated with process materials such as solvents (See Part I.B.13.C of the permit);

b. Describe any controls associated with non-stormwater discharges present at the site: No anticipated non-stormwater discharges are expected to occur.

J. Permanent Controls for Post-Construction Stormwater Management:

Describe measures installed during the construction process to control pollutants in stormwater discharges that will occur after construction operations have been completed: All disturbed areas will be seeded and mulched within 14 days of completing work activities that resulted in the disturbance of soil. The seeding of the areas will be done more than one time if adequate turf coverage is not accomplished in the first seeding event.

K. Applicable State or Local Programs: The SWPPP will be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site. ☒ Yes ☐ No

L. Inspections

a. Inspection frequency:

☒ Every 7 calendar days

or

☐ At least once every 14 calendar days and within 24 hours of the end of a storm even 0.25 inches or greater (a rain gauge must be maintained on-site)

b. Inspections:

Completed inspection forms will be kept with the SWPPP.

☒ ADEQ's inspection form will be used (See Appendix B)

or

☐ A form other than ADEQ's inspection form will be used and is attached (See inspection form requirements Part II.A.4.L.2)

c. Inspection records will be retained as part of the SWPPP for at least 3 years from the date of termination.

d. It is understood that the following sections describe waivers of site inspection requirements. All applicable documentation requirements will be followed in accordance with the referenced sections.

- i. Winter Conditions (Part II.A.4.L.4)
- ii. Adverse Weather Conditions (Part II.A.4.L.5)

M. Maintenance:

The following procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition will be followed: All disturbed areas will be seeded and mulched within 14 days of completing work activities that resulted in the disturbance of soil. The seeding of the areas will be done more than one time if adequate turf coverage is not accomplished in the first seeding event.

Any necessary repairs will be completed, when practicable, before the next storm event, but not to exceed a period of 3 business days of discovery, or as otherwise directed by state or local officials.

N. Employee Training:

The following is a description of the training plan for personnel (including contractors and subcontractors) on this project: Scenic Hill Solar employees and contractors whose normal duties could potentially affect stormwater discharges and installed BMPs will be trained on contents of the SWPPP. Personnel will be trained in their responsibilities while on-site. At a minimum, training will include brief discussions on the following: contents of the SWPPP, summary of stormwater BMPs used on the project, and review of reporting requirements in the case of a spill or damage to a BMP.

**Note, Formal training classes given by Universities or other third-party organizations are not required, but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.

Certification

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official: _____

Carrie Kyhl

Title: _____

COO

Date: _____

5/15/25

Computation Sheet for Determining Runoff Coefficients

Appendix A

Total Site Area = 27.45 Acres [A]

Existing Site Conditions

Impervious Site Area ¹ = 0 Acres [B]

Impervious Site Area Runoff Coefficient ^{2, 4} = 0.95

Pervious Site Area ³ = 27.45 Acres [D]

Pervious Site Area Runoff Coefficient ⁴ = 0.10 [E]

Pre-Construction Runoff Coefficient

$$\frac{[B \times C] + [D \times E]}{[A]} = 0.1$$

Proposed Site Conditions (after construction)

Impervious Site Area ¹ = 11.35 Acres [F]

Impervious Site Area Runoff Coefficient ^{2, 4} = 0.80 [G]

Pervious Site Area ³ = 16.1 Acres [H]

Pervious Site Area Runoff Coefficient ⁴ = 0.10 [I]

Post-Construction Runoff Coefficient

$$\frac{[F \times G] + [H \times I]}{[A]} = 0.38$$

1. Includes paved areas, areas covered by buildings, and other impervious surfaces.
2. Use 0.95 unless lower or higher runoff coefficient can be verified.
3. Includes areas of vegetation, most unpaved or uncovered soil surfaces, and other pervious areas.
4. Refer to local Hydrology Manual for typical C values.

Note: The impervious and pervious surfaces should equal the total area.

ARR150000 Inspection Form

Appendix B

Inspector Name: _____

Date of Inspection: _____

Inspector Title: _____

Date of Rainfall: _____

Duration of Rainfall: _____

Days Since Last Rain Event: _____ days

Rainfall Since Last Rain Event: _____ inches

Description of any Discharges During Inspection: _____

Location of Discharges of Sediment/Other Pollutant (specify pollutant & location): _____

Locations in Need of Additional BMPs: _____

Information on Location of Construction Activities

Location	Activity Begin Date	Activity Occurring Now (y/n)?	Activity Ceased Date	Stabilization Initiated Date	Stabilization Complete Date

Information on BMPs in Need of Maintenance

Location	In Working Order?	Maintenance Scheduled Date	Maintenance Completed Date	Maintenance to be Performed By

Changes required to the SWPPP: _____

Reasons for changes: _____

SWPPP changes completed (date): _____

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official: _____ Date: _____

Title: _____

BMP Consideration Checklist

The BMPs listed here should be considered for every project. Those BMPs that are not included in the SWPPP should be checked as "Not Used" with a brief statement describing why it is not being used.

Note: Appendix C and D do not have to be submitted with the SWPPP. These attachments are for use during the development of the SWPPP.

EROSION CONTROL BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
EC-1 Scheduling	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
EC-2 Preservation of Existing Vegetation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
EC-3 Hydraulic Mulch	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
EC-4 Hydroseeding	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
EC-5 Soil Binders	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
EC-6 Straw Mulch	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
EC-7 Geotextiles & Mats	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
EC-8 Wood Mulching	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
EC-9 Earth Dikes & Drainage Swales	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
EC-10 Velocity Dissipation Devices	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
EC-11 Slope Drains	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
EC-12 Stream bank Stabilization	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SEDIMENT CONTROL BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
SE-1 Silt Fence	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SE-2 Sediment Basin	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-3 Sediment Trap	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-4 Check Dam	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SE-5 Fiber Rolls	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-6 Gravel Bag Berm	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-7 Street Sweeping and Vacuuming	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SE-8 Sand Bag Barrier	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-9 Straw Bale Barrier	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SE-10 Storm Drain Inlet Protection	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
SE-11 Chemical Treatment	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WIND EROSION CONTROL BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
WE-1 Wind Erosion Control	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary

BMP Consideration Checklist

Appendix C

TRACKING CONTROL BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
TR-1 Stabilized Construction Entrance/Exit	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
TR-2 Stabilized Construction Roadway	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
TR-3 Entrance/Outlet Tire Wash	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NON-STORM WATER MANAGEMENT BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
NS-1 Water Conservation Practices	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-2 Dewatering Operations	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-3 Paving and Grinding Operations	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-4 Temporary Stream Crossing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-5 Clear Water Diversion	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-6 Illicit Connection/ Discharge	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-7 Potable Water/Irrigation	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-8 Vehicle and Equipment Cleaning	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-9 Vehicle and Equipment Fueling	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-10 Vehicle and Equipment Maintenance	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-11 Pile Driving Operations	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-12 Concrete Curing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-13 Concrete Finishing	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-14 Material and Equipment Use Over Water	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-15 Demolition Adjacent to Water	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
NS-16 Temporary Batch Plants	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WASTE MANAGEMENT AND MATERIALS POLLUTION CONTROL BMPs				
BMP	BMP Considered for project	BMP Used	BMP Not Used	If not used, state reason
WM-1 Material Delivery and Storage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
WM-2 Material Use	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
WM-3 Stockpile Management	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
WM-4 Spill Prevention and Control	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
WM-5 Solid Waste Management	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WM-6 Hazardous Waste Management	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WM-7 Contaminated Soil Management	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WM-8 Concrete Waste Management	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
WM-9 Sanitary/Septic Waste Management	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary
WM-10 Liquid Waste Management	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Not necessary

SWPPP Completion Checklist

Appendix D

Yes = Complete

No = Incomplete/Deficient

N/A = Not applicable to project

			A site description, including:	Permit Section Citation
Yes	No	N/A		
<input checked="" type="checkbox"/>			1. Project description, intended use after NOT	<u>Part II.A.4.A.1</u>
<input checked="" type="checkbox"/>			2. Sequence of major activities	<u>Part II.A.4.A.2</u>
<input checked="" type="checkbox"/>			3. Total & disturbed acreage	<u>Part II.A.4.A.3</u>
<input checked="" type="checkbox"/>			4. Pre- and post-construction runoff coefficient OR soil/discharge data	<u>Part II.A.4.A.4</u>
<input checked="" type="checkbox"/>			B. Responsible Parties: All parties dealing with the SWPPP and the areas they are responsible for on-site.	<u>Part II.A.4.B</u>
<input checked="" type="checkbox"/>			C. Receiving Water.	<u>Part II.A.4.C</u>
<input checked="" type="checkbox"/>			-MS4 Name	<u>Part II.A.4.C</u>
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	-Ultimate Receiving Water	<u>Part II.A.4.C</u>
<input checked="" type="checkbox"/>			D. Documentation of permit eligibility related to Impaired Water Bodies and Total Maximum Daily Loads (TMDL	
<input checked="" type="checkbox"/>			1. Identify pollutant on 303(d) list or TMDL	<u>Part II.A.4.D.1</u>
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		2. Is construction activity or the specific site listed as cause?	<u>Part II.A.4.D.2</u>
<input checked="" type="checkbox"/>			3. Measures taken to reduce pollutants from the site.	<u>Part II.A.4.D.3</u>
<input checked="" type="checkbox"/>			E. Attainment of Water Quality Standards After Authorization.	<u>Part II.A.4.E</u>
<input checked="" type="checkbox"/>			F. Site Map --- See End of Evaluation Form	<u>Part II.A.4.F</u>
			G. Description of Controls:	
<input checked="" type="checkbox"/>			1. Erosion and sediment controls, including:	
<input checked="" type="checkbox"/>			a. Initial site stabilization	<u>Part II.A.4.G.1.a</u>
<input checked="" type="checkbox"/>			b. Erosion and sediment controls	<u>Part II.A.4.G.1.b</u>
<input checked="" type="checkbox"/>			c. Replacement of inadequate controls	<u>Part II.A.4.G.1.c</u>
<input checked="" type="checkbox"/>			d. Removal of off-site accumulations	<u>Part II.A.4.G.1.d</u>
<input checked="" type="checkbox"/>			e. Maintenance of sediment traps/basins @ 50% capacity	<u>Part II.A.4.G.1.e</u>
<input checked="" type="checkbox"/>			f. Litter, construction debris and chemicals properly handled	<u>Part II.A.4.G.1.f</u>
		<input checked="" type="checkbox"/>	g. Off-site storage areas and controls	<u>Part II.A.4.G.1.g</u>
<input checked="" type="checkbox"/>			2. Stabilization practices:	
<input checked="" type="checkbox"/>			a. Description and schedule for stabilization	<u>Part II.A.4.G.2.a</u>
<input checked="" type="checkbox"/>			b. Description of buffer areas	<u>Part II.A.4.G.2.b</u>
<input checked="" type="checkbox"/>			c. Records of stabilization	<u>Part II.A.4.G.2.c</u>
<input checked="" type="checkbox"/>			d. Deadlines for stabilization	<u>Part II.A.4.G.2.d</u>
<input checked="" type="checkbox"/>			3. Structural Practices:	
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		-Describe structural practices to divert flows, store flows, or otherwise limit runoff	<u>Part II.A.4.G.3</u>
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	a. Sediment basins	<u>Part II.A.4.G.3.a.1</u>
	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	-Are more than 10 acres draining to a common point? If so, are sediment basins included?	<u>Part II.A.4.G.3.a.1</u>
		<input checked="" type="checkbox"/>	-Sediment basin dimensions and capacity description and calculations	<u>Part II.A.4.G.3.a.1</u>
		<input checked="" type="checkbox"/>	-If a basin wasn't practicable, are other controls sufficient?	<u>Part II.A.4.G.3.a.1</u>
			b. Velocity dissipation devices concentrated flow from 2 or more acres	<u>Part II.A.4.G.3.b</u>
			H. Other controls including:	<u>Part II.A.4.H.1</u>
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	1. Solid waste control measures	<u>Part II.A.4.H.2</u>
<input checked="" type="checkbox"/>			2. Vehicle off-site tracking controls	<u>Part II.A.4.H.4</u>
<input checked="" type="checkbox"/>			3. Compliance with sanitary waste disposal	<u>Part II.A.4.H.5</u>
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	4. Does the site have a concrete washout area controls? Does the site have fuel storage areas, hazardous waste storage and/or truck wash areas controls?	<u>Part II.A.4.H.6</u>

Revised date: 10/20/2016

SWPPP Completion Checklist

Appendix D

Yes No N/A

☒ ☐ ☒ **I. Identification of allowable non-storm water discharges**
 -Appropriate controls for dewatering, if present

Permit Section Citation

Part II.A.4.I

Part I.B.12.C

☒ ☐ ☐ **J. Post construction stormwater management.**

Part II.A.4.J

☒ ☐ ☐ **K. State or local requirements incorporated into the plan.**

Part II.A.4.K

☒ ☐ ☐ **L. Inspections**

☒ ☐ ☐ 1. Inspection frequency listed?

Part II.A.4.L.1

☒ ☐ ☐ 2. Inspection form

Part II.A.4.L.2

☒ ☐ ☐ Ours.

If not ours, does it contain the following items:

☐ ☐ ☐ a. Inspector name and title

Part II.A.4.L.2.a

☐ ☐ ☐ b. Date of inspection.

Part II.A.4.L.2.b

☐ ☐ ☐ c. Amount of rainfall and days since last rain event (14 day only)

Part II.A.4.L.2.c

☐ ☐ ☐ d. Approx beginning and duration of storm event

Part II.A.4.L.2.d

☐ ☐ ☐ e. Description of any discharges during inspection

Part II.A.4.L.2.e

☐ ☐ ☐ f. Locations of discharges of sediment/other pollutants

Part II.A.4.L.2.f

☐ ☐ ☐ g. BMPs in need of maintenance

Part II.A.4.L.2.g

☐ ☐ ☐ h. BMPs in working order, if maintenance needed (scheduled and completed)

Part II.A.4.L.2.h

☐ ☐ ☐ i. Locations that are in need of additional controls

Part II.A.4.L.2.i

☐ ☐ ☐ j. Location and dates when major construction activities begin, occur or cease

Part II.A.4.L.2.j

☐ ☐ ☐ k. Signature of responsible/cognizant official

Part II.A.4.L.2.k

☒ ☐ ☐ 3. Inspection Records

Part II.A.4.L.3

☒ ☐ ☐ 4. Winter Conditions

Part II.A.4.L.4

5. Adverse Weather Conditions

Part II.A.4.L.5

☒ ☐ ☐ **M. Maintenance Procedures**

Part II.A.4.M

☒ ☐ ☐ **N. Employee Training**

Part II.A.4.N

☒ ☐ ☐ **Signed Plan Certification**

Part II.A.5. and Part II.B.10

☒ ☐ ☐ **F. Site Map showing:**

☒ ☐ ☐ 1. Pre-construction topographic view

Part II.A.4.F.1

☒ ☐ ☐ 2. Drainage flow

Part II.A.4.F.2

☒ ☐ ☐ 3. Approximate slopes after grading activities

Part II.A.4.F.2

☒ ☐ ☐ 4. Areas of soil disturbance and areas not disturbed

Part II.A.4.F.3

☒ ☐ ☐ 5. Location of major structural and non-structural controls.

Part II.A.4.F.4

☒ ☐ ☐ 6. Location of main construction entrance and exit.

Part II.A.4.F.5

☒ ☐ ☐ 7. Areas where stabilization practices are expected to occur.

Part II.A.4.F.6

☐ ☐ ☒ 8. Locations of off-site materials, waste, borrow area or storage area.

Part II.A.4.F.7

☒ ☐ ☐ 9. Locations of areas used for concrete wash-out.

Part II.A.4.F.8

☒ ☐ ☐ 10. Locations of surface waters on site.

Part II.A.4.F.9

☒ ☐ ☐ 11. Locations where water is discharged to a surface water or MS4.

Part II.A.4.F.10

☒ ☐ ☐ 12. Storm water discharge locations.

Part II.A.4.F.11

☒ ☐ ☐ 13. Areas where final stabilization has been accomplished.

Part II.A.4.F.12

☐ ☐ ☒ 14. Legend for symbols/labels used

Part II.A.4.F.13

15. Location of storm drain inlets on site or in immediate vicinity

Part II.A.4.F.14

SWPPP TRAINING CERTIFICATION FORM

This is to acknowledge that I have reviewed the Stormwater Pollution Prevention Plan for Construction for Scenic Hill Solar. I have been trained in its use and purpose and am familiar with its contents.

Name (Please Print)

Name (Please Print)

Signature

Signature

Date

Date

Responsible For

Responsible For

Name (Please Print)

Name (Please Print)

Signature

Signature

Date

Date

Responsible For

Responsible For

Name (Please Print)

Name (Please Print)

Signature


Signature

Date

Date

Responsible For


Responsible For



DRAWING NO. 1

SITE TOPOGRAPHIC MAP TAKEN FROM BRYANT USGS QUADRANGLE

CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
 BRYANT SD SOLAR ARRAY
 SCENIC HILL SOLAR
 BRYANT, ARKANSAS



A Terracon Company

SUBMITTED:	N. JOHNSON
DRAWN:	D. LLOYD
CHECKED:	N. JOHNSON
DATE:	MAY 15, 2025

SCALE:




JOB NUMBER:
KT257024

FILE: KT257024 SWPPP TOPO.DWG



- GENERAL NOTES:
- 1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
 - 2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
 - 3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.

TOTAL PROPERTY APPROXIMATELY 27.45 ACRES
TOTAL DISTURBED AREA APPROXIMATELY 11.35 ACRES



PRELIMINARY

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775

DESIGNED BY: NJ

DRAWN BY: DDL

CHECKED BY: NJ

DATE: APR. 15, 2025
DOL
SCALE: 1" = 80'

REVISIONS:

NO.	DATE	DESCRIPTION	BY:

SITE LAYOUT - AERIAL

CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

JOB NUMBER:
KT257024

DRAWING NUMBER:
2

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775


FILE: N:\AUTOCAD - ENGINEERING\KT257024 - SIS BRYANT SD CIVIL & SWPPP\SWPPP\KT257024 BRYANT SD SWPPP.DWG

BRYANT SD SOLAR ARRAY


SCENIC HILL SOLAR

BRYANT, ARKANSAS

FEBRUARY 2025



Vicinity Map



INDEX OF DRAWINGS	
SHEET #	SHEET TITLE
C1.0	SITE LAYOUT – AERIAL
C1.1	SITE LAYOUT
C1.2	STAKING PLAN
C1.4	EROSION CONTROL PLAN
C2.0	MISCELLANEOUS DETAILS
C2.1	EROSION CONTROL DETAILS



PROJECT NO. KT257024

PRELIMINARY



NOT FOR CONSTRUCTION



- GENERAL NOTES:
1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
 2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
 3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.

PROPERTY
BOUNDARY

PRIMARY ROAD
8,375 SF CLASS 7 BASE
COURSE COMPACTED TO
95% MODIFIED PROCTOR

2 - 10'
WIDE GATES

JURISDICTIONAL
INTERMITTENT
STREAM

3,050 LF CHAIN LINK
SECURITY FENCE
(SEE DETAIL 1, SHEET C2.0)

20' MIN. TYP.

455

450

460

465

470

445

450

455

460

465

470

80

0

80

160

PRELIMINARY

SHEET TITLE:
SITE LAYOUT - AERIAL

PROJECT TITLE:
BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

REVISIONS:

NO.	DATE	DESCRIPTION	BY:

CIVIL ENGINEERING AND
ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775

DESIGNED BY: JTM

DATE: FEB. 25, 2025

DRAWN BY: JTM

SCALE: 1" = 80'

CHECKED BY: JTM

FILE: N:\PROJECTS\2025\KT257024 - SHS BRYANT SD CIVIL & SWPPP\DRAWINGS\KT257024 BRYANT SD CIVIL.DWG

JOB NUMBER:
KT257024

SHEET NUMBER:
C1.0

SUBMITTED FOR
REVIEW

1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.

SUBMITTED FOR
REVIEW

SITE LAYOUT

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:

REVIEWS:		
NO:	DATE:	DESCRIPTION:
		BY:


**CIVIL ENGINEERING AND
ENVIRONMENTAL SERVICES**
3512 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
(501) 221-7122 FX: (501) 221-7222


**CIVIL ENGINEERING AND
ENVIRONMENTAL SERVICES**
3512 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775



JOB NUMBER:
KT257024

SHEET NUMBER:
C1.1





- GENERAL NOTES:
1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
 2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
 3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.

EROSION CONTROL

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

REVISIONS:

NO.	DATE	DESCRIPTION	BY:

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775

DESIGNED BY: JTM
DRAWN BY: JTM
CHECKED BY: JTM

DATE: FEB. 25, 2025
SCALE: 1" = 80'

FILE: N:\PROJECTS\2025\KT257024 - SHS BRYANT SD CIVIL & SWPPP\DRAWINGS\KT257024 BRYANT SD CIVIL.DWG

JOB NUMBER:
KT257024

SHEET NUMBER:
C1.1

SUBMITTED FOR
REVIEW

SUBMITTED FOR
REVIEW

MISCELLANEOUS DETAILS

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:


PROJECT TITLE:

REVISIONS:		BY:	DATE:	DESCRIPTION:
NO.				



CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES 3612 SOUTH SHACKLEFORD RD LITTLE ROCK, ARKANSAS 72205 PH: (501) 221-7122 FX: (501) 221-7775	DESIGNED BY:	JTM	DATE:	FEB. 25, 2025
	DRAWN BY:	JTM	SCALE:	N.T.S.
	CHECKED BY:	JTM		

JOB NUMBER: KT257024
SHEET NUMBER: C2.0



PRELIMINARY




SECURITY FENCE DETAIL
SCALE: NTS




INDUSTRIAL GRAVEL ROAD DETAIL
SCALE: NTS




VEHICULAR GRAVEL ROAD DETAIL
SCALE: NTS






VIEW LOOKING UP STREAM

NOTE: KEY STONE INTO THE DITCH BANKS AND EXTEND IT BEYOND THE ABUTMENTS A MINIMUM OF 18" TO PREVENT OVERFLOW AROUND DAM.



SECTION A-A



'L' = THE DISTANCE SUCH THAT POINTS 'A' AND 'B' ARE OF EQUAL ELEVATION.



SPACING BETWEEN CHECK DAMS


ROCK CHECK DAM DETAIL

SCALE: NTS



VIEW LOOKING UPSTREAM

SCALE: N.T.S.



SPACING BETWEEN CHECK DAMS



SCALE: N.T.S.

NOTES:

1. EMBED BALES 4" INTO THE SOIL AND 'KEY' BALES INTO THE CHANNEL BANKS.
2. POINT 'A' MUST BE HIGHER THAN POINT 'B'. (SPILLWAY HEIGHT)
3. PLACE BALES PERPENDICULAR TO THE FLOW WITH ENDS TIGHTLY ABUTTING. USE STRAW, ROCKS OR FILTER FABRIC TO FILL ANY GAPS AND TAMP BACKFILL MATERIAL TO PREVENT EROSION OR FLOW AROUND THE BALES.
4. SPILLWAY HEIGHT SHALL NOT EXCEED 24".
5. INSPECT AFTER EACH SIGNIFICANT STORM, MAINTAIN AND REPAIR PROMPTLY.

STRAW BALE CHECK DAM DETAIL

SCALE: NTS



STANDARD DETAIL
TRENCH WITH NATIVE BACKFILL


NOTES:

1. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
2. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.

SILT FENCE DETAIL

SCALE: NTS

ALTERNATE DETAIL
TRENCH WITH GRAVEL



20' MIN. TYP.

SUBMITTED FOR
REVIEW

EROSION CONTROL DETAILS

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS


SHEET TITLE:

REVISIONS:		BY:	DATE:
NO.	DESCRIPTION:		

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES 3612 SOUTH SHACKLEFORD RD LITTLE ROCK, ARKANSAS 72205 PH: (501) 221-7122 FX: (501) 221-7775		DATE: FEB. 25, 2025	SCALE: N.T.S.
DESIGNED BY: JTM	DRAWN BY: JTM	CHECKED BY: JTM	

JOB NUMBER: KT257024	SHEET NUMBER: C2.0
-------------------------	-----------------------

PRELIMINARY



STANDARD SPECIFICATIONS

Engineering: ASCE 7-10/7-16/CPP Wind Tunnel Tested

Grounding: Fully Integrated UL2703

Foundation: Dual Ground Screw

Tilt Angles: 5°-35° Tilt Options

Racking Coating: Galvanized; G90

Foundation Coating: HDG

Wind Loading: Up to 165mph


Snow Loading: Up to 100psf

Mounting Orientation: 2-High in Portrait

Warranty: 25 Years

DUAL GROUND SCREWS

TITAN Duo is designed to tackle the most challenging sites. It's dual ground screw foundation is the ideal solution for sites with glacial till, cobble, hardpan, or solid bedrock. The heavy walled tube and welded connections allow for massive amounts of torque and pressure to be applied, helping the screw advance into the toughest soils.



TITAN^{DUO} 4-RAIL DESIGN


Designed by installers for installers, TITAN[™] is the most advanced hardware in the industry. TITAN's innovative features allow for flexibility in the field while streamlining the install process. With the lowest part count per MW and integrated grounding and cable trays, TITAN is installers preferred choice. The 4-rail design is an excellent solution for areas with high snow loads and large format modules. TITAN Duo comes standard with dual 3" diameter ground screws to manage rocky soil conditions.

In business since 2008, APA offers a versatile line of racking and foundation solutions for projects in even the most challenging environments. With projects nationwide, APA is a trusted racking partner.

WHY USE TITAN DUO™ 4-RAIL?

WIRE MANAGEMENT

Integrated cable trays and custom wire clips keep your project organized, safe, and code compliant for the life of the project, without adding costly third-party solutions.



4-RAIL DESIGN

- Capable of handling snow loads up to 100psf
- Works with large format modules
- 2-High Portrait, ideal for split cell modules
- Low back panel shading for bifacial modules

ADJUSTABLE BRACING

C-channel bracing allows for easy adjustments in the field.

TELESCOPING POST

Allows for quick adjustment in the field for high degrees of topography on site.

GROUND SCREWS STANDARD

TITAN Duo is specifically designed for sites with glacial till, cobble, hardpan and bedrock.



TITAN^{DUO}



APA
SOLAR RACKING

STRUCTURAL PRINT PACKAGE

RIDGEVILLE CORNERS, OH 43555

SAMPLE


RACKING PROVIDER



20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OHIO 43555
(P) 419.267.5280
(F) 419.267.5214
WWW.APASOLAR.COM


STRUC. ENGINEER OF RECORD

RACKING PRODUCT LINE



USE WITH THE FOLLOWING PRINTS
& PACKAGES. INCLUDE WITH
SUBMISSION TO PERMIT/INSPECTION
AGENCY:

- ☒ CALCULATION PACKAGE:
SAMPLE CALC SET – STAMPED
- ☒ FOUNDATION DESIGN REPORT (SITE
SPECIFIC, & ONLY WHERE REQUIRED
BY EOR OR AHJ)



SITE ADDRESS: 20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OH 43555

REVISION: A

PERMIT SET/
STRUCTURAL PACKET

APPROVED

SOLAR PHOTOVOLTAIC GROUND MOUNT




IMAGE FOR REFERENCE ONLY

SHEET INDEX

STRUCTURAL		
S-000	A	STRUCTURAL COVER
S-100	A	RACKING OVERVIEW
S-200	A	GROUND SCREW
S-300	A	STRUCTURAL COMPONENTS
S-400	A	CONNECTIONS
S-500	A	STRUCTURAL PURLINS
S-600	A	CLAMPS & BRACES

GOVERNING STRUCTURAL CODE/S

2018 INTERNATIONAL BUILDING CODE

PACKAGE COVERAGE – LOADING
AND SETUP RANGES & CONSTANTS

TILT ANGLES: 20°
MAX GROUND SNOW LOAD (PSF): 40
MAX WIND LOADS (MPH): 105
WIND EXPOSURE CATEGORY: C
MAX SEISMIC Ss: 0.169 g
MAX SEISMIC S1: 0.048 g

PV MODULE: BYD MSTK-33

MAX. PANEL WIDTH: 51.30"
MAX. PANEL LENGTH: 93.86"
MAX. PANEL HEIGHT: 2.00"
MAX. PANEL WEIGHT: 80.00 LBS

RISK CATEGORY: I
MAX FRONT LIP CLEARANCE: 48"




A1	ELEVATION VIEW FROM FRONT (NORTH-FACING)
----	--

SEE VIEW A1 ON S600 FOR VIEW OF TRANSVERSE BRACE

1. STANDARD FRONT LIP HEIGHT AND TILT
ANGLES MEASURED FROM LEVEL GROUND
2. FOUNDATION TESTING, WHERE REQUIRED, SHALL
BE DONE ACCORDING TO THE "QUICK TEST
METHOD" PER ASTM D1143 & D3689.
3. PRINT DIMENSIONS: DIMENSIONS SHOWN
REFLECT POST HEIGHTS ON LEVEL GROUND. ON
UNEVEN TERRAIN, REAR FOUNDATION POST
HEIGHT WILL BE DICTATED BY FRONT LIP
HEIGHT, PANEL TILT, AND NORTH/SOUTH POST
SPACING.
4. ADDITIONAL TOLERANCES: POST PLUMBNESS
SHOULD BE WITHIN $\pm 2^{\circ}$
5. SPECIAL INSPECTIONS (WHERE REQUIRED):

SPECIAL INSPECTIONS ARE NOT REQUIRED BY APA
SOLAR OR THE STRUCTURAL ENGINEER OF RECORD
WHERE REQUIRED BY OWNER, CUSTOMER, AND/OR
AUTHORITY HAVING JURISDICTION, MINIMUM
INSPECTION SHALL FOLLOW IBC OR LOCAL AHJ
SPECIAL INSPECTIONS GUIDELINES.

RACKING PROVIDER



RACKING TYPE



PROFESSIONAL SEAL/STAMP

DOCUMENT NAME: STRUCTURAL PRINT PACKAGE

SITE STREET ADDRESS:
20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OH 43555

SHEET REVISIONS		
REV.	DESCRIPTION	DATE
A	INITIAL RELEASE	4/28/202

SAMPLE

APPROVED

DRAWN SDS	REVIEWED TM	APPROVED JDI	SIZE D
SHEET NAME			

RACKING OVERVIEW

PROJECT NUMBER

DRAWING NUMBER

REV

IMAGE REFERENCE ONLY. NOT INDICATIVE OF REQUIRED QUANTITIES.











SCALE IS REDUCED WHEN SHEET SIZE IS 11" x 17"

1
2
3
4
5
6


E
D
C
B
A

1
2
3
4
5
6

1
2
3
4
5
6



MATERIAL: A653 STR. STL.
STRENGTH: MIN. YIELD (Fy): 80 KSI.



CUSTOMER

RACKING PROVIDER

APA
SOLAR RACKING
20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OHIO 43555
(P) 419.267.5280
(F) 419.267.5214
WWW.APASOLAR.COM

RACKING TYPE

TITAN
R15

PROFESSIONAL SEAL/STAMP

DOCUMENT NAME:
STRUCTURAL PRINT PACKAGE
SITE STREET ADDRESS:
20-345 COUNTY ROAD X
SITE CITY, STATE, ZIP:
RIDGEVILLE CORNERS, OH 43555

SHEET REVISIONS			
REV.	DESCRIPTION	DATE	
A	INITIAL RELEASE	4/28/2023	

SAMPLE

APPROVED

DRAWN	REVIEWED	APPROVED	SIZE
SDS	TM	JDI	D

SHEET NAME
STRUCTURAL COMPONENTS


PROJECT NUMBER
SAMPLE

DRAWING NUMBER
S.300

REV.
A


PROPRIETARY AND CONFIDENTIAL. THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF AP RACKING, LLC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE EXPRESS WRITTEN PERMISSION IS PROHIBITED.

IMAGE FOR REFERENCE ONLY




B1 FOUNDATION SET CONNECTIONS OVERVIEW

IMAGE FOR REFERENCE ONLY




ATTACHED TO OUTER HOLE SET FOR REFERENCE ONLY. SEE NOTES.

A1 CONNECTION: ROLL BAR-TO-NS CHORD




A2 CONNECTION: KNEE BRACE-TO-FRONT POST

IMAGE FOR REFERENCE ONLY



B4 CONNECTION: REAR POST-TO-NS CHORD

IMAGE FOR REFERENCE ONLY



A4 KNEE BRACE-TO-REAR POST

NOTES:

- HARDWARE TORQUE VALUES:

3/8"-16 STAINLESS STEEL
MIN.: 17.5 FT-LBS
NOM.: 19.6 FT-LBS
MAX.: 50.0 FT-LBS

1/2"-13 STAINLESS STEEL
MIN: 25 FT-LBS
- DEPICTED HARDWARE AND PART PLACEMENT NOT INDICATIVE OF PREFERRED OR REQUIRED POSITIONS.
- HOLE/SLOT PATTERNS IN PARTS ALLOW FOR DEVIATION FROM NOMINAL DIMENSIONS, MULTIPLE PART POSITIONS, AND MULTIPLE TILT ANGLES.
- SEE INSTALLATION MANUAL FOR SETUP INSTRUCTIONS.
- SERRATED FLANGED BOLTS MAY BE REPLACED WITH EQUIVALENT PRESS-IN BOLTS. SEE NOTE 10 FOR MORE OPTIONS.
- PRESS-IN BOLTS, WHERE PRESENT, TO BE INSTALLED TO MANUFACTURERS RECOMMENDED VALUES.
- OTHER SPECIFIC CONNECTIONS ELSEWHERE IN PRINT SET.
- ROLL BAR MUST CONNECT TO THE CORRECT HOLES IN CEE CHANNEL (INNER, OR OUTER TYPICALLY), AS DETERMINED BY PV MODULE MANUFACTURERS ALLOWABLE CLAMPING ZONE.
- USE CORRECT NOMINAL HOLES IN CEE TO CONNECT TO FOUNDATION POST, AS INDICATED. ADJACENT HOLES AND SLOTS FOR FIELD ADJUSTMENTS.
- SERRATED HARDWARE MAY BE REPLACED WITH EQUIVALENT HARDWARE WITH WASHERS IF NECESSARY.
- IN ALL DETAILS, THE PRESENCE OF TWO SETS OF HARDWARE INDICATES THE REQUIREMENT OF TWO SETS OF HARDWARE.
- STAINLESS STEEL HARDWARE MAY BE REPLACED WITH GALVANIZED STEEL HARDWARE OR CORROSION AND STRENGTH COMPARABLE HARDWARE MATERIALS AND FINISHES.
- UNLESS NOTED OTHERWISE, ALL HARDWARE MAY BE INSTALLED IN EITHER DIRECTION (NUT/BOLT MAY BE ON EITHER SIDE OF CONNECTION).
- WHEN NECESSARY, ADDITIONAL HOLES MAY BE DRILLED TO COMPLETE CONNECTION. ENGINEERING SHALL BE CONTRACTED PRIOR TO FIELD MODIFICATIONS OF PARTS.

CUSTOMER

RACKING PROVIDER

APA
SOLAR RACKING
20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OHIO 43555
(P) 419.267.5280
(F) 419.267.5214
WWW.APASOLAR.COM

RACKING TYPE

TITAN
R15

PROFESSIONAL SEAL/STAMP

DOCUMENT NAME:
STRUCTURAL PRINT PACKAGE


SITE STREET ADDRESS:
20-345 COUNTY ROAD X
SITE CITY, STATE, ZIP:
RIDGEVILLE CORNERS, OH 43555

SHEET REVISIONS			DATE
REV.	DESCRIPTION	INITIAL RELEASE	4/28/2023
A			


SAMPLE

APPROVED


DRAWN	REVIEWED	APPROVED	SIZE
SDS	TM	JDI	D
SHEET NAME			
CONNECTIONS			
PROJECT NUMBER			
SAMPLE			
DRAWING NUMBER			REV.
S.400			A




B1	OVERVIEW: ZEE PURLIN CONNECTIONS (RACK UNDERSIDE)
----	---




A1	CONNECTION: ZEE PURLINS-TO-ROLL BAR
----	-------------------------------------




A2	CONNECTION: ZEE PURLINS-TO-NS CHORD
----	-------------------------------------



E4	DETAIL: ZEE PURLIN PANEL SLOTS
----	--------------------------------



D4	DETAIL: ZEE PURLIN SPLICE SLOTS
----	---------------------------------



C4	CONNECTION: ZEE-TO-ZEE PURLINS SPLICE
----	---------------------------------------

NOTES:

1. HARDWARE TORQUE VALUES:
3/8"–16 STAINLESS STEEL
MIN.: 17.5 FT-LBS
NOM.: 19.6 FT-LBS
MAX.: 50.0 FT-LBS
2. DEPICTED HARDWARE AND PART PLACEMENT NOT INDICATIVE OF PREFERRED OR REQUIRED POSITIONS.
3. HOLE/SLOT PATTERNS IN PARTS ALLOW FOR DEVIATION FROM NOMINAL DIMENSIONS, MULTIPLE PART POSITIONS, AND MULTIPLE TILT ANGLES.
4. SEE INSTALLATION MANUAL FOR SETUP INSTRUCTIONS.
5. SERRATED FLANGED BOLTS MAY BE REPLACED WITH EQUIVALENT PRESS-IN BOLTS.
6. PRESS-IN BOLTS, WHERE PRESENT, TO BE INSTALLED TO MANUFACTURERS RECOMMENDED VALUES.
7. OTHER SPECIFIC CONNECTIONS ELSEWHERE IN PRINT SET.
8. SERRATED HARDWARE MAY BE REPLACED WITH EQUIVALENT HARDWARE WITH WASHERS IF NECESSARY.
9. IN ALL DETAILS, THE PRESENCE OF TWO SETS OF HARDWARE INDICATES THE REQUIREMENT OF TWO SETS OF HARDWARE.
10. STAINLESS STEEL HARDWARE MAY BE REPLACED WITH GALVANIZED STEEL HARDWARE OR CORROSION AND STRENGTH COMPARABLE HARDWARE MATERIALS AND FINISHES.
11. UNLESS NOTED OTHERWISE, ALL HARDWARE MAY BE INSTALLED IN EITHER DIRECTION (NUT/BOLT MAY BE ON EITHER SIDE OF CONNECTION).
12. WHEN NECESSARY, ADDITIONAL HOLES MAY BE DRILLED TO COMPLETE CONNECTION. ENGINEERING SHALL BE CONTRACTED PRIOR TO FIELD MODIFICATIONS OF PARTS.
13. CONNECTION IN DETAIL A1 & A2 SHOWN IN NOMINAL POSITION. ACTUAL CONNECTION MAY BE $\pm 8"$.
14. WHEN CONNECTIONS IN DETAIL A1 & A2 ARE AT THEIR MAX/MIN POSITIONS ($\pm 2"$) INTERFERING SPLICE HARDWARE MAY BE RELOCATED TO NEXT NEAREST SLOTS.
15. WHERE PRESENT, TRANSVERSE BRACE MAY UTILIZE LOWER SPLICE BOLTS. SEE CONNECTIONS SHEET FOR MORE INFORMATION.
16. ZEE-TO-ZEE SPLICE SHALL ALWAYS OVERLAP MINIMUM 32", AS INDICATED, EXCEPT AT ENDS OF ROW, WHERE NO SPLICE IS REQUIRED.
17. SPLICE MAY OVERLAP IN EITHER DIRECTION.
18. ZEE PURLIN MATERIAL AND FINISH ARE MANUFACTURED TO SPECIFICATIONS THAT MEET OR EXCEED OUR STANDARD PRODUCT WARRANTY.
19. ZEE PURLINS GALVANIZED TO CONFORM TO A MINIMUM THICKNESS DESIGNATION EQUAL TO G90 OR INLINE GALVANIZED TO COMPARABLE THICKNESS AS PER ASTM A1057.
20. TYPICAL ZEE PURLIN RETURN LIP ANGLE SHOWN. ACTUAL ANGLE MAY VARY.
21. SLOT DIMENSIONS FOR REFERENCE ONLY. FINAL SHAPE, FREQUENCY, AND DIMENSIONS MAY VARY.
22. LENGTH OF PURLIN VARIES BY PROJECT AND LOCATION WITHIN ARRAY.

CUSTOMER

RACKING PROVIDER

APA
SOLAR RACKING
20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OHIO 43555
(P) 419.267.5280
(F) 419.267.5214
WWW.APASOLAR.COM

	RACKING TYPE
--	--------------

TITAN
DIO

PROFESSIONAL SEAL/STAMP

DOCUMENT NAME: STRUCTURAL PRINT PACKAGE

SITE STREET ADDRESS:
20-345 COUNTY ROAD X

BRIDGEVILLE CORNERS OH 43555

SHEET REVISIONS		
REV.	DESCRIPTION	DATE
A	INITIAL RELEASE	4/28/20

SAMPLE


APPROVED

DRAWN SDS	REVIEWED TM	APPROVED JDI	SU I
SHEET NAME STRUCTURAL PURLINS			
PROJECT NUMBER SAMPLE			
DRAWING NUMBER S.500			REV. A


[illegible]

SCALE IS REDUCED WHEN SHEET SIZE IS 11" x 17"


17/2/2023 2:33:17 PM SHAWKINS 03/26/18 I:\Information Systems\Structural\Drawings\20-345\20-345-4.rvt - Sample.dwg




E1 REAR VIEW: CABLE BRACE FREQUENCY




D1 BOTTOM VIEW: TRANSVERSE BRACE LOCATIONS




C1 PART: CABLE BRACE




C2 PART: TRANSVERSE BRACE (TVS BRACE)




A1 CONNECTION: TVS BRACE-TO-PURLIN




A3 TOP (ISO) VIEW: PV CLAMP LOCATIONS




D4 SEC.: CABLE BRACE




C4 ASSEMBLY: ENDCLAMP



D5 SECTION: TVS BRACE



C5 TVS BRACE ASSEMBLY



A5 ASSEMBLY: MIDCLAMP

NOTES:

- HARDWARE TORQUE VALUES:

1/2"-13 STAINLESS STEEL
MIN.: 40 FT-LBS

M8-1.25 STAINLESS STEEL
MIN.: 14.0 FT-LBS
NOM.: 15.6 FT-LBS
MAX.: 25 FT-LBS
- DEPICTED HARDWARE AND PART PLACEMENT NOT INDICATIVE OF PREFERRED OR REQUIRED POSITIONS.
- HOLE/SLOT PATTERNS IN PARTS ALLOW FOR DEVIATION FROM NOMINAL DIMENSIONS, MULTIPLE PART POSITIONS, AND MULTIPLE TILT ANGLES.
- SEE INSTALLATION MANUAL FOR SETUP INSTRUCTIONS.
- SERRATED FLANGED BOLTS MAY BE REPLACED WITH EQUIVALENT PRESS-IN BOLTS. SEE NOTE 8 FOR MORE INFORMATION.
- PRESS-IN BOLTS, WHERE PRESENT, TO BE INSTALLED TO MANUFACTURERS RECOMMENDED VALUES.
- OTHER SPECIFIC CONNECTIONS ELSEWHERE IN PRINT SET.
- SERRATED HARDWARE MAY BE REPLACED WITH EQUIVALENT HARDWARE WITH WASHERS IF NECESSARY.
- STAINLESS STEEL HARDWARE MAY BE REPLACED WITH GALVANIZED STEEL HARDWARE OR CORROSION AND STRENGTH COMPARABLE HARDWARE MATERIALS AND FINISHES.
- UNLESS NOTED OTHERWISE, ALL HARDWARE MAY BE INSTALLED IN EITHER DIRECTION (NUT/BOLT MAY BE ON EITHER SIDE OF CONNECTION).
- WHEN NECESSARY, ADDITIONAL HOLES MAY BE DRILLED TO COMPLETE CONNECTION. ENGINEERING SHALL BE CONTRACTED PRIOR TO FIELD MODIFICATIONS OF PARTS.
- EAST/WEST CABLE BRACING (C1) TO BE INSTALLED IN THE SPACE BETWEEN ANCHOR SETS (BAY).
- MINIMUM CABLE BREAKING STRENGTH DETERMINED BY PROJECT SPECIFIC STRUCTURAL CALCULATIONS.
- CABLE TO BE STAINLESS STEEL AIRCRAFT CABLE.
- CABLE MAY BE OF ANY CONFIGURATION (IE. 7X7 OR 7X19) AS LONG AS IT MEETS THE REQUIREMENTS LISTED ON THIS SHEET.
- LENGTH OF BRACES WILL VARY DEPENDENT ON PROJECT SPECIFICS.
- TRANSVERSE BRACE SETS SHALL BE INSTALLED AT FREQUENCY INDICATED.
- TRANSVERSE BRACES ARE NOT A REQUIREMENT OF THE STRUCTURAL MODELS. APA REQUIRES THEIR PRESENCE AS AN ASSEMBLY AID ONLY.
- DUE TO IT'S NON-STRUCTURAL NATURE, TRANSVERSE BRACE PROFILE, THICKNESS, MATERIAL, STRENGTH, COATING, FREQUENCY, AND INSTALLATION MAY CHANGE AT ANY TIME AT THE DISCRETION OF APA, BY APPROVAL OF APA ENGINEERING.
- WHERE TRANSVERSE BRACE CANNOT BE INSTALLED DUE TO NS CHORD (OUT OF NOMINAL LOCATION), BRACE SHALL BE RELOCATED TO NEXT NEAREST REASONABLE SPLICE.
- TRANSVERSE BRACE MAY UTILIZE LOWER SPLICE BOLTS, WHERE PRESENT. SEE PURLIN SHEET FOR MORE INFORMATION.
- EACH PV MODULE SHALL BE CLAMPED IN 4 PLACES.
- A MAJORITY OF THE CLAMP BOLT FLANGES MUST TERMINATE OVER THE SLOT, AND NOT OVER THE KEYHOLE.
- SPRING, & PANEL GUIDE MAY NOT BE PRESENT AT ALL LOCATIONS, OR ANY LOCATIONS.
- ALL PANELS MUST BE GROUNDED/BONDED TO ZEE PURLINS. THIS MAY BE ACCOMPLISHED WITH THE PANEL GUIDE, BONDING WASHERS, DYNOBOND EQUIPMENT OR OTHER APPROVED GROUNDING DEVICE.

CUSTOMER

RACKING PROVIDER

APA
SOLAR RACKING
20-345 COUNTY ROAD X
RIDGEVILLE CORNERS, OHIO 43555
(P) 419.267.5280
(F) 419.267.5214
WWW.APASOLAR.COM

RACKING TYPE

TITAN
R15

PROFESSIONAL SEAL/STAMP

DOCUMENT NAME:
STRUCTURAL PRINT PACKAGE

SITE STREET ADDRESS:
20-345 COUNTY ROAD X

SITE CITY, STATE, ZIP:
RIDGEVILLE CORNERS, OH 43555

REV.	DESCRIPTION	DATE
A	INITIAL RELEASE	4/28/2023

SAMPLE

APPROVED


DRAWN	REVIEWED	APPROVED	SIZE
SDS	TM	JDI	D
SHEET NAME			
CLAMPS & BRACES			
PROJECT NUMBER			
SAMPLE			
DRAWING NUMBER		REV.	
S.600		A	

BRYANT SD SOLAR ARRAY


SCENIC HILL SOLAR

BRYANT, ARKANSAS

MAY 2025



Vicinity Map



INDEX OF DRAWINGS	
SHEET #	SHEET TITLE
C1.0	SITE LAYOUT – AERIAL
C1.1	SITE LAYOUT
C1.2	STAKING PLAN
C1.4	EROSION CONTROL PLAN
C2.0	MISCELLANEOUS DETAILS
C2.1	EROSION CONTROL DETAILS



PROJECT NO. KT257024

PRELIMINARY



NOT FOR CONSTRUCTION



- GENERAL NOTES:
1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
 2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
 3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.

SUBMITTED FOR REVIEW

SITE LAYOUT - AERIAL

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:

PROJECT TITLE:

REVISIONS:		BY:	
NO.	DATE:	DESCRIPTION:	

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775

DESIGNED BY: JTM

DRAWN BY: JTM

CHECKED BY: JTM

DATE: MAY 22, 2025
SCALE: 1" = 80'

FILE: N:\AUTOCAD - ENGINEERING\KT257024 - SIS BRYANT SD CIVIL & SWPPP\DRAWINGS\KT257024 BRYANT SD CIVIL.DWG

JOB NUMBER:
KT257024

SHEET NUMBER:
C1.0

SUBMITTED FOR
REVIEW

SITE LAYOUT

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:

REVISIONS:

NO.	DATE	DESCRIPTION	BY:

CIVIL ENGINEERING AND
ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775



JOB NUMBER:
KT257024


SHEET NUMBER:
C1.1

DESIGNED BY: JTM
DRAWN BY: JTM
CHECKED BY: JTM
DATE: MAY 22, 2025
SCALE: 1" = 80'

FILE: N:\AUTOCAD - ENGINEERING\KT257024 - SIS BRYANT SD CIVIL & SWPPP\DRAWINGS\KT257024 BRYANT SD CIVIL.DWG

GENERAL NOTES:

1. THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
2. THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
3. ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.



SUBMITTED FOR
REVIEW

EROSION CONTROL

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:

REVISIONS:

NO.	DATE	BY:	DESCRIPTION:

CIVIL ENGINEERING AND
ENVIRONMENTAL SERVICES
3612 SOUTH SHACKLEFORD RD
LITTLE ROCK, ARKANSAS 72205
PH: (501) 221-7122 FX: (501) 221-7775

DESIGNED BY: JTM
DRAWN BY: JTM
CHECKED BY: JTM


DATE: MAY 22, 2025
SCALE: 1" = 80'

JOB NUMBER:
KT257024

SHEET NUMBER:
C1.1

GENERAL NOTES:

- THE CONTRACTOR IS REQUIRED TO NOTIFY THE ONE CALL CENTER AT 1-800-482-8998 48 HOURS PRIOR TO DIGGING SO THAT UNDERGROUND UTILITIES IN THE AREA CAN BE LOCATED.
- THE LOCATION OF KNOWN SUBSURFACE STRUCTURES, UTILITY PIPING, GAS, FIBER, ETC. ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE SITE AND OBTAIN FURTHER INFORMATION ON THE LOCATION OF SUBSURFACE STRUCTURES SHOWN AND NOT SHOWN. ALL REPAIRS TO DAMAGED UNDERGROUND STRUCTURES SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- ALL ITEMS DISTURBED DURING CONSTRUCTION, STREETS, DRIVES, FENCES, ETC. SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST OF REPAIRS IS THE RESPONSIBILITY OF THE CONTRACTOR.



EROSION CONTROL NOTES:

- REFER TO CITY OF BRYANT SCHOOL DISTRICT SOLAR ARRAY STORMWATER MANAGEMENT PLAN FOR SPECIFICS OF EROSION CONTROL MANAGEMENT PLAN AND MAINTENANCE PLAN.

PRELIMINARY

SUBMITTED FOR
REVIEW

MISCELLANEOUS DETAILS

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

SHEET TITLE:

PROJECT TITLE:

REVISIONS:


NO.	DATE	DESCRIPTION	BY:

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES 3612 SOUTH SHACKLEFORD RD LITTLE ROCK, ARKANSAS 72205 PH: (501) 221-7122 FX: (501) 221-7775	DESIGNED BY:	JTM	DATE:	FEB. 25, 2025
	DRAWN BY:	JTM	SCALE:	N.T.S.
	CHECKED BY:	JTM		

JOB NUMBER:
KT257024



SHEET NUMBER:
C2.0

PRELIMINARY





SECURITY FENCE DETAIL

SCALE: NTS




INDUSTRIAL GRAVEL ROAD DETAIL


SCALE: NTS



VEHICULAR GRAVEL ROAD DETAIL


SCALE: NTS






VIEW LOOKING UP STREAM

NOTE: KEY STONE INTO THE DITCH BANKS AND EXTEND IT BEYOND THE ABUTMENTS A MINIMUM OF 18" TO PREVENT OVERFLOW AROUND DAM.



SECTION A-A



'L' = THE DISTANCE SUCH THAT POINTS 'A' AND 'B' ARE OF EQUAL ELEVATION.



SPACING BETWEEN CHECK DAMS

ROCK CHECK DAM DETAIL



SCALE: NTS



- NOTES:
1. INSTALL SWALE DOWNGRADIENT OF SOLAR ARRAY.
 2. USE 4:1 H:V SLOPE ON EDGES.


FIELD LOCATED SWALE DETAIL

SCALE: NTS



VIEW LOOKING UPSTREAM

SCALE: N.T.S.



SPACING BETWEEN CHECK DAMS



SCALE: N.T.S.

NOTES:

1. EMBED BALES 4" INTO THE SOIL AND 'KEY' BALES INTO THE CHANNEL BANKS.
2. POINT 'A' MUST BE HIGHER THAN POINT 'B'. (SPILLWAY HEIGHT)
3. PLACE BALES PERPENDICULAR TO THE FLOW WITH ENDS TIGHTLY ABUTTING. USE STRAW, ROCKS OR FILTER FABRIC TO FILL ANY GAPS AND TAMP BACKFILL MATERIAL TO PREVENT EROSION OR FLOW AROUND THE BALES.
4. SPILLWAY HEIGHT SHALL NOT EXCEED 24".
5. INSPECT AFTER EACH SIGNIFICANT STORM, MAINTAIN AND REPAIR PROMPTLY.

STRAW BALE CHECK DAM DETAIL

SCALE: NTS




STANDARD DETAIL
TRENCH WITH NATIVE BACKFILL

NOTE:

1. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
2. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.

SILT FENCE DETAIL

SCALE: NTS



EROSION CONTROL DETAILS

SHEET TITLE:

BRYANT SD SOLAR ARRAY
SCENIC HILL SOLAR
BRYANT, ARKANSAS

PROJECT TITLE:

REVISIONS:

NO.	DATE	BY	DESCRIPTION

CIVIL ENGINEERING AND ENVIRONMENTAL SERVICES 3612 SOUTH SHACKLEFORD RD LITTLE ROCK, ARKANSAS 72205 PH: (501) 221-7122 FX: (501) 221-7775	DESIGNED BY: JTM DATE: MAY 21, 2025 DRAWN BY: JTM SCALE: N.T.S. CHECKED BY: JTM
---	---

JOB NUMBER: KT257024	SHEET NUMBER: C2.0
-------------------------	-----------------------

PRELIMINARY



A  Terracon Company

3512 S Shackelford Road,
Little Rock, AR 72205

(501) 221-7122

PMICO.com | Terracon.com

May 21, 2025

City of Bryant Planning and Development
210 Southwest 3rd Street
Bryant, Arkansas 72022

Re: City of Bryant School District Solar Array
Stormwater Management & Maintenance Plan

On behalf of The City of Bryant School District and Scenic Hill Solar, **Pollution Management, Inc., A Terracon Company (PMI)** proposes the following Stormwater Management and Maintenance Plan (SWMMP) measures to reduce stormwater runoff, improve stormwater quality, minimize erosion, minimize impervious areas, and minimize gravel or paved areas. The SWMP will utilize best management practices during construction and utilize alternative methods after construction to achieve these goals.

The proposed site plan minimizes the use of impervious surfaces. The gravel entrance road pathway utilizes the shortest possible path to access the array. This road is comprised of Class 7 Base Course which allows infiltration and is designed to minimum area requirements. Only electrical equipment pads will be located on paved areas for stability.

As described in the SWPPP, adequate measures needed to limit erosion during construction will consist of installing silt fencing and/or rock check dams as needed. Specifically, areas around newly disturbed and graded surfaces will be protected using primarily silt fences, rock check dams as needed, and a gravel site entrance to reduce erosion and sediment transport. Only the areas within the site plan will be distributed to minimize site compaction. Tracked equipment with low impact footprints will be used for driving mounting piles and access the site through the stabilized construction entrance and exit. The site will be inspected every seven calendar days during construction and the ADEQ inspection form will be used.

Upon construction completion, the site will be planted with Bermuda grass. If needed, compacted soils around the array will be tilled to encourage vegetative success with strong root systems. The downgradient areas of the array will contain minor field located swales as shown in Detail 7 of the plans. These measures will aid to reduce stormwater runoff through infiltration and diversion, improve stormwater quality through uptake and sedimentation and minimize erosion using stabilized soils.

Upon site stabilization, maintenance of the site will include ensuring Bermuda grass establishment and mowing as required. If required, restorative planting will occur for vegetative areas that fail and additional grading will occur in areas of erosion. In addition to this SWMMP, PMI requests an in-lieu monetary contribution for the development of the City of Bryant School District solar array. We request the contribution to replace the requirement of additional on-site detention due to the limited space availability of the site.

The City of Bryant School District and Scenic Hill Solar have secured the electrical interconnection ability and continue to move forward with the City of Bryant planning requirements to create a

Explore with us

sustainable power generating facility that will also serve as a learning tool the school district. If you have any questions or comments, please do not hesitate to contact me at 501-221-7122 or jmetrailer@pmico.com.

Sincerely,
Pollution Management, Inc., *A Terracon Company*

A handwritten signature in black ink that reads "John Metrailer". The script is fluid and cursive.

John Metrailer, P.E.
Senior Environmental Engineer

17. DIRECTIONS TO THE SITE

The entrance to the site is located approximately 0.44 miles northeast of the intersection between Zuber Road and Wise Road in Bryant, Arkansas.

18. Nature of Activity (Description of project, include all features)

The proposed project will install a low water concrete crossing allowing site access. The crossing is 30 linear feet and is proposed as shown in the attached drawings.

19. Project Purpose (Describe the reason or purpose of the project, see instructions)

The purpose of the project is to provide access to solar array. The solar array will provide renewable energy for the Bryant School District.

USE BLOCKS 20-23 IF DREDGED AND/OR FILL MATERIAL IS TO BE DISCHARGED

20. Reason(s) for Discharge

Best Management Practices will be used during construction to prevent discharges.

21. Type(s) of Material Being Discharged and the Amount of Each Type in Cubic Yards:

Type Amount in Cubic Yards	Type Amount in Cubic Yards	Type Amount in Cubic Yards
5		

22. Surface Area in Acres of Wetlands or Other Waters Filled (see instructions)

Acres 0.003

or

Linear Feet 30

23. Description of Avoidance, Minimization, and Compensation (see instructions)

Avoidance is inevitable due to site access. Minimization uses only one crossing with minimal length to create access and ensure proper flow. If compensation is required, the applicant will purchase stream credits from an approved mitigation bank.

24. Is Any Portion of the Work Already Complete? ☐ Yes ☒ No IF YES, DESCRIBE THE COMPLETED WORK

25. Addresses of Adjoining Property Owners, Lessees, Etc., Whose Property Adjoins the Waterbody (If more than can be entered here, please attach a supplemental list).

a. Address- Barbara Floyd, 4901 Northlake Road

City - Alexander

State - AR

Zip - 72002

b. Address- Britiany Floyd, 5003 Northlake Road

City - Alexander

State - AR

Zip - 72002

c. Address- Bryant Public School District, 1511 North Reynolds Road

City - Bryant

State - AR

Zip - 72022

d. Address-

City -

State -

Zip -

e. Address-

City -

State -

Zip -

26. List of Other Certificates or Approvals/Denials received from other Federal, State, or Local Agencies for Work Described in This Application.

AGENCY	TYPE APPROVAL*	IDENTIFICATION NUMBER	DATE APPLIED	DATE APPROVED	DATE DENIED
USACE	concurrence	SWL 2024-00238	2024-07-15	2024-09-17	

* Would include but is not restricted to zoning, building, and flood plain permits

27. Application is hereby made for permit or permits to authorize the work described in this application. I certify that this information in this application is complete and accurate. I further certify that I possess the authority to undertake the work described herein or am acting as the duly authorized agent of the applicant.



SIGNATURE OF APPLICANT

04/14/25

DATE

Metrailler, John

SIGNATURE OF AGENT

Digitally signed by Metrailler, John
Date: 2025.04.14 08:38:30 -0500'


2025-04-14

DATE

The Application must be signed by the person who desires to undertake the proposed activity (applicant) or it may be signed by a duly authorized agent if the statement in block 11 has been filled out and signed.

18 U.S.C. Section 1001 provides that: Whoever, in any manner within the jurisdiction of any department or agency of the United States knowingly and willfully falsifies, conceals, or covers up any trick, scheme, or disguises a material fact or makes any false, fictitious or fraudulent statements or representations or makes or uses any false writing or document knowing same to contain any false, fictitious or fraudulent statements or entry, shall be fined not more than \$10,000 or imprisoned not more than five years or both.

I-30 FRONTAGE ROAD, BRYANT, AR



VICINITY MAP

PREPARED BY:




HOPE
CONSULTING
ENGINEERS - SURVEYORS

129 N. Main Street,
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
www.hopeconsulting.com

DRAWING INDEX

SHEET NO.	TITLE
	BOUNDARY SURVEY
C-1.0	SITE PLAN
C-2.0	GRADING PLAN
C-3.0	DETENTION PLAN
C-4.0	EROSION CONTROL PLAN



CIVIL ENGINEER
HOPE CONSULTING INC
129 N. Main Street,
Benton, Arkansas 72015

STRUCTURAL ENGINEER
N/A

ARCHITECT
N/A

GEOTECHNICAL ENGINEER

OWNER:		DEVELOPER:	
Name:	<u>Knoedl Investments, LLC</u>	Name:	<u>Knoedl Investments, LLC</u>
Address:	<u>406 Beachview Circle</u> <u>Hot Springs, AR 71913</u>	Address:	<u>406 Beachview Circle</u> <u>Hot Springs, AR 71913</u>


HOPE
CONSULTING
ENGINEERS - SURVEYORS




129 N. Main Street,
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
www.hopeconsulting.com

FOR USE AND BENEFIT OF:
KNOEDL INVESTMENTS, LLC

OUTDOOR STORAGE YARD COVER SHEET


DATE: 05/16/2025		C.A.D. BY:		DRAWING NUMBER: 23-1109			
REVISED:		CHECKED BY:					
SHEET:		SCALE:					
500	01S	14W	0	13	420	62	1664










 HOPE CONSULTING <u>ENGINEERS - SURVEYORS</u>	129 N. Main Street, Benton, Arkansas 72015 PH. (501)315-2626 FAX (501) 315-0024 www.hopeconsulting.com

					A:\HOPE CONSULTING\9. PROJECTS\3_23-1109 EXPANSION ON I-30\DWG 03.025(SA)_23-1109 PARKING EXTENSION_05-15-2025_FINAL.DWG
--	--	--	--	--	--





GRADING PLAN NOTES


1. DESIGN CONTOURS SHOWN ARE FINISHED GRADE.
2. SPOT ELEVATIONS SHOWN ARE FINISHED ASPHALT, GROUND OR CONCRETE ELEVATIONS.
3. CLEAR AND GRUB AREAS OF THE SITE WHERE CUT OR FILL IS TO OCCUR.
4. FILL SHALL BE COMPACTED AT LEAST 98% OF THE MATERIALS MAXIMUM STANDARD PROCTOR DRY DENSITY.
5. THE MOISTURE CONTENT OF 1% BELOW TO 3% ABOVE THE OPTIMUM MOISTURE CONTENT.
6. SUB-GRADES SHALL BE PROOF-ROLLED WITH A LOADED DUMPTRUCK TO DETECT ZONES OF UNSUITABLE AND/OR EXCESSIVELY WET SOILS. IF PUMPING BEGINS, COMPACTION SHALL BE STOPPED IMMEDIATELY AND RESUMED ONLY WHEN THE MATERIAL IS SUFFICIENTLY DRY THAT PUMPING DOES NOT OCCUR.
7. ALL UNSUABLE SOILS SHALL BE USED ON SITE FOR FILL PURPOSES OUTSIDE THE AREAS OF BUILDING AND PAVEMENT CONSTRUCTION.
8. PROPER DRAINAGE SHALL BE MAINTAINED THROUGHOUT THE PROJECT SITE TO PREVENT THE INCREASE OF THE IN-SITU SOILS MOISTURE CONTENT.






FG = FINISH GRADE
EG = EXISTING GRADE
FL = FLOW LINE

HDPE
BCP



	129 N. Main Street, Benton, Arkansas 72015 PH. (501) 315-2626 FAX (501) 315-0024 www.hopeconsulting.com
---	---




A:\HOPE CONSULTING\9. PROJECTS\3.23-1109 EXPANSION ON I-30\DWG 03.10.25\SAL 23-1109 PARKING EXTENSION_05-15-2025_FINAL.DWG



DETENTION POND MAINTENANCE PLAN

- Background**
The detention pond is located at the **South** of the subjected property. It is designed to temporarily detain stormwater to meet water quantity criteria before discharging off the property.
- Routine Maintenance**
Routine maintenance will include but not be limited to:
-Mowing of the bank slopes and area around the pond on a monthly basis during the growing season and as needed during the cooler months.
- The outlet pipe from the pond and other areas will be inspected monthly for debris which could inhibit the proper flow of discharge. Any debris will be removed immediately and disposed of or placed in a location to prevent future maintenance and to not cause impact up or downstream of the structure.
- Trash will be removed from around the pond to prevent entering the pond. Generally, the site should be kept free of loose trash which could be carried off site by wind or rain.
- Inspect the pond and outlet pipe for non-routine maintenance need.

- Periodic or Non-Routine Maintenance**
The routine inspection of the pond area and discharge pipe will identify needed repairs and non-routine maintenance. These items may include but not be limited to:
- Re-growth of trees on or around the pond bank. These should be cut and removed from the pond area.
 - Sediment from the site may accumulate in the pond bottom and reduce the pond to below design volume requirements. The pond should be excavated if the pond bottom elevation reached a level that allows excessive aquatic growth or reduces the pond efficiency such, that the sediments are passing the discharge structure and release off site.
 - Stabilization or re-grading of side slopes may be required periodically or after excessive rain events. Any disturbance of slopes should be reseeded or may require installation of erosion control materials until seeding can reestablish adequate grasses to prevent future erosion.
 - Any other maintenance or repairs which would minimize other maintenance to the pond or outfall structures.
- For questions or concerns about Tract "A", contact at 501-.




HOPE
CONSULTING
ENGINEERS - SURVEYORS

129 N. Main Street,
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
www.hopeconsulting.com

FOR USE AND BENEFIT OF:
KNOEDL INVESTMENTS, LLC

OUTDOOR STORAGE YARD
DETENTION PLAN
I-30 FRONTAGE ROAD, BRYANT, AR

DATE: 05/16/2025	C.A.D. BY:	DRAWING NUMBER: 23-1109					
REVISED:	CHECKED BY:						
SHEET: C-3.0	SCALE: 1" = 10'						
500	01S	14W	0	13	420	62	1664




STANDARD DETAIL
TRENCH WITH NATIVE BACKFILL

ALTERNATE DETAIL
TRENCH WITH GRAVEL.

NOTE:

- 1.) INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
- 2.) REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
- 3.) SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.

SILT FENCE



PLAN

VIEW LOOKING UPSTREAM

NOTES:

- 1) POINT 'A' MUST BE HIGHER THAN POINT 'B' (SPILLWAY HEIGHT)
- 2) PLACE RIP RAP BARRIER PERPENDICULAR TO THE FLOW WITH TIGHT GROUTING USE STRAW, ROCKS, OR FILTER FABRIC TO FILL ANY GAPS AND TAMP BACKFILL MATERIAL TO PREVENT EROSION OR FLOW UNDER THE DAM.
- 3) SPILLWAY HEIGHT SHALL NOT EXCEED 18" 24"
- 4) INSPECT AFTER EACH SIGNIFICANT STORM MAINTAIN AND REPAIR PROMPTLY.

EROSION CONTROL NOTES

SOD DETENTION AREA POST-CONSTRUCTION

MAXIMUM SLOPE OF 3H:1V ON DETENTION POND LEVEES



CONTRACTOR MUST HAVE INLET PROTECTION MEASURES
INSTALLED IMMEDIATELY AFTER CONSTRUCTION OF DRAINAGE
INLETS/STRUCTURES IS COMPLETE. SEDIMENT BARRIERS SHALL
BE MAINTAINED THROUGHOUT AND INSPECTED THROUGHOUT
CONSTRUCTION PROCESS UNTIL PROJECT IS COMPLETE

RIP RAP SEDIMENT BARRIERS SHALL BE USED AT ALL
STORMWATER DISCHARGE POINTS SHOWN ON PLANS ASAP



CONTRACTOR SHOULD WORK WITH ENGINEER TO ESTABLISH EFFECTIVE AND EFFICIENT PLAN TO PREVENT SEDIMENT RUNOFF BY DETERMINING WHERE SILT FENCING OR OTHER TYPES OF CONTROLS ARE NECESSARY

SOME EROSION CONTROL MEASURES, SILT FENCING, OR CHECK DAMS MAY NOT BE NECESSARY DURING INITIAL SITE CLEARING BUT MAY BE NEEDED ONCE DIRT WORK BEGINS.

EXISTING VEGETATION WILL ONLY BE REMOVED WITHIN CONSTRUCTION AREA AS THEY ARE DEVELOPED. ADDITIONAL SILT FENCING WILL BE ADDED AS CONSTRUCTION TAKES PLACE IF NECESSARY.



STABILIZED CONSTRUCTION ENTRANCE
N.T.S

**ERC LEGEND**

SITE POSTING


CONC. WASHOUT
DETENTION AREA


SILT FENCE

RIP RAP CHECK DAM

CONSTRUCTION ENTRANCE

DISTURBED AREA




	<p style="text-align: right;">129 N. Main Street, Benton, Arkansas 72015 PH. (501) 315-2626 FAX (501) 315-0024 www.hopeconsulting.com</p>
---	---

OUTDOOR STORAGE YARD

I-30 FRONTAGE ROAD, SALINE COUNTY, AR

DRAINAGE REPORT

MAY 2025



Owner & Developer

KNOEDL INVESTMENTS, LLC

By:

HOPE
CONSULTING
ENGINEERS - SURVEYORS

129 N. Main Street
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
www.hopeconsulting.com

Table of Contents-

Drainage Summary

Pre Development Area & Calculation

Post Development Area & Calculation

Ditch & Drainage Pipe Details

Detention Plan

Hydrograph Summary Report

Precipitation Data of NOAA

PROJECT TITLE

OUTDOOR STORAGE YARD

PROJECT PROPERTY OWNER

KNOEDL INVESTMENTS, LLC

PROJECT LOCATION

I-30 FRONTAGE RD in The City of BRYANT, Saline County, Arkansas

PROJECT DESCRIPTION

The proposed development is on side of the I-30 Frontage road. The total development site area is 4.19 acres.

DRAINAGE ANALYSIS

On Site Drainage- Rational method was used to determine the existing and proposed flows from proposed site. There will be one detention ponds to detain water from this development. Detailed drainage calculations considering the future expected development have been conducted to determine the required detention volumes, ditch and culvert dimensions as required. Summary of the calculations are below:

South Detention Pond



- A detention pond has been proposed on the South side of the property.
- Pre-development area 4.49 acres.
- Post-development area 4.70 acres.
- Considering the existing condition, pre-development runoff coefficient 0.47.
- Post-development cumulative runoff coefficient 0.96.
- Bottom elevation of detention facility is 344.00'.
- One 12" RCP with 1.00% slope is proposed for outflow culvert.

Peak flows for Pre and post development phase of onsite area have been tabulated below-


	Pre-development	Dev. Generated	Post-dev. After detention
	Peak Flow (cfs)	Peak Flow (cfs)	Peak Flow (cfs)
2-Year	7.418	23.19	3.044
5-Year	8.844	27.60	3.636
10- Year	9.965	31.05	3.992
25- Year	11.46	35.65	4.423
50- Year	12.53	39.11	4.681
100- Year	13.57	42.34	4.907

CONCLUSION


From the drainage calculation, it is seen that there is decrease in flow for all storm events due to the proposed detention pond.



DETENTION PROPOSED SECTION
NTS



SPILLWAY END VIEW
NTS



OUTLET SECTION
NTS

DETENTION POND MAINTENANCE PLAN

Background
The detention pond is located at the **South** of the subjected property. It is designed to temporarily detain stormwater to meet water quantity criteria before discharging off the property.

Routine Maintenance
Routine maintenance will include but not be limited to:
-Mowing of the bank slopes and area around the pond on a monthly basis during the growing season and as needed during the cooler months.

-The outlet pipe from the pond and other areas will be inspected monthly for debris which could inhibit the proper flow of discharge. Any debris will be removed immediately and disposed of or placed in a location to prevent future maintenance and to not cause impact up or downstream of the structure.

-Trash will be removed from around the pond to prevent entering the pond. Generally, the site should be kept free of loose trash which could be carried off site by wind or rain.

-Inspect the pond and outlet pipe for non-routine maintenance need.

Periodic or Non-Routine Maintenance
The routine inspection of the pond area and discharge pipe will identify needed repairs and non-routine maintenance. These items may include but not be limited to:


-Re-growth of trees on or around the pond bank. These should be cut and removed from the pond area.

-Sediment from the site may accumulate in the pond bottom and reduce the pond to below design volume requirements. The pond should be excavated if the pond bottom elevation reached a level that allows excessive aquatic growth or reduces the pond efficiency such, that the sediments are passing the discharge structure and release off site.


-Stabilization or re-grading of side slopes may be required periodically or after excessive rain events. Any disturbance of slopes should be reseeded or may require installation of erosion control materials until seeding can reestablish adequate grasses to prevent future erosion.

-Any other maintenance or repairs which would minimize other maintenance to the pond or outfall structures.


For questions or concerns about Tract "A", contact at 501-.



DITCH-1 SECTION



DITCH-2 SECTION (TEMPORARY)






HOPE CONSULTING
ENGINEERS - SURVEYORS

129 N. Main Street,
Benton, Arkansas 72015
PH. (501) 315-2626
FAX (501) 315-0024
www.hopeconsulting.com

FOR USE AND BENEFIT OF:
KNOEDL INVESTMENTS, LLC

**OUTDOOR STORAGE YARD
DETENTION PLAN**
I-30 FRONTAGE ROAD, BRYANT, AR

DATE:	05/16/2025	C.A.D. BY:		DRAWING NUMBER:
REVISED:		CHECKED BY:		23-1109
SHEET:	C-3.0	SCALE:	1" = 10'	
500	01S	14W	0 13 420	62 1664





HOPE CONSULTING
ENGINEERS - SURVEYORS

129 N. Main Street,
Benton, Arkansas 72015
PH. (501) 315-2626
FAX (501) 315-0024
www.hopeconsulting.com


FOR USE AND BENEFIT OF: KNOEDL INVESTMENTS, LLC					
OUTDOOR STORAGE YARD PRE DEVELOPMENT DRAINAGE AREA MAP I-30 FRONTAGE ROAD, BRYANT, AR					
DATE:	05/16/2025	C.A.D. BY:		DRAWING NUMBER: 23-1109	
REVISED:		CHECKED BY:			
SHEET:	C-3.1	SCALE:	1" = 30'		
500	01S	14W	0 13 420	62	1664

A:\HOPE CONSULTING\9 PROJECTS\23-1109 EXPANSION ON I-30 DWG\03-0023.SW\23-1109 PARKING EXTENSION_05-15-2025_FINAL.DWG




POST DEVELOPMENT TIME OF CONCENTRATION

		C		
	Area (acer)	100 year		100 year
Area A1 (Storage Yard & Future development)	4.58	0.97		4.45
Area A2 (Undeveloped)	0.12	0.47		0.06
Tot A =	4.70		Corr. C =	0.96



	129 N. Main Street, Benton, Arkansas 72015	
	PH. (501) 315-2626	
	FAX (501) 315-0024	
	www.hopeconsulting.com	



12" RCP PIPE Capacity Check				
Frequency - Duration	Target Discharge		Toal Area, A (ac)	Discharge, Q = CIA (cfs)
	Intensity, I (in/hr)	Runoff Coefficient, C		
100 yr - 5 min	11.20	0.97	0.21	2.29

Pipe Capacity Check														
Pipe Dia (in)		12		Pipe Dimension										
Target Discharge, Q (cfs)		2.29												
Q = V A		Discharge		Velocity, V ft/sec	Pipe Dia, (ft)	Area, A (ft²)	Flow Depth, y (ft)	Length, L (ft)	Elevation, h (ft)	Slope, S (ft/ft)	Mannings, n	Wetted Perimeter, P	Hydraulic Radius, R = A/P	
$V = \frac{1.49}{n} R^{\frac{2}{3}} S^{\frac{1}{2}}$		Capacity, Q (cfs)												
		100%		2.74	3.49	1.00	0.79	1.00	34.0	0.2	0.0059	0.013	3.142	0.250
Adequate size														

Ditch-1 Size Calculation

Existing Ditch Capacity Calculation									
Existing Channel Dimension									
Velocity, V (ft/sec)	Bottom Width, (ft)	Depth, (ft)	Top Width, (ft)	Ch Side Slope 1:2	Area, (ft²)	Slope, S (ft/ft)	Mannings, n	Hydraulic Radius, R	
55.74	3.72	0.00	1.68	17.84	5.31	14.99	0.0100	0.030	0.648
Existing Channel Capacity, Q = 55.74 ft³/s									

Proposed Ditch Capacity Calculation - DITCH 1									
Proposed Channel Dimension									
Target Discharge, Q (ft³/s)	55.7								
Velocity, V (ft/sec)	Bottom Width, (ft)	Depth, (ft)	Top Width, (ft)	Ch Side Slope 1:2	Area, (ft²)	Slope, S (ft/ft)	Mannings, n	Hydraulic Radius, R	
60.98	4.86	2.50	1.67	12.52	3.00	12.54	0.0100	0.030	0.969
Ditch 1 Discharge Capacity, Q = 60.98 ft³/s									
Adequate size									


Ditch-2 Size Calculation

Area (ft2)	102056.0										
Area (Acre)	2.34										
Total Length, L (ft)	630.0										
Change in Elevation (ft)	16.9										
Gross Slope, S (ft/ft)	0.027										
N (Coeff. Of roughness, Table 400-3)	0.600										
L _o (overland/sheet flow, ft)	50.0										
L _u (shallow concentrated, ft)	100.0										
V _{ch} (channel, ft)	480.0										
$t_{ch} = 0.83 \frac{(W L_o)^{0.467}}{S^{0.5}}$, (min)	9.21										
$t_{uvc} = \frac{L_{uvc}}{60 V}$, (min) , unpaired	0.54										
$V = 16.1345(S^{0.5})$											
$t_{cx} = \frac{L_{cx}}{60 V}$, (min)	2.18										
$V = \frac{1.48}{1.49} R^{0.49} S^{0.58}$	Ch1										
Ch2-Ditch	0.80										
Total time of concentration, tc (min)	12.79										

Hydrograph Summary Report
SOUTH DETENTION

Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025



Legend

Hyd.	Origin	Description
1	Rational	Pre Development
2	Rational	Post Development
3	Reservoir	Detention

Multi-Hydrograph Plot

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 7.535 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 8,138 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 3.04 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 11,152 cuft



Multi-Hydrograph Plot

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 8.984 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 9,703 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 3.64 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 13,276 cuft



Multi-Hydrograph Plot

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 10.12 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 10,933 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 3.99 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 14,943 cuft



Multi-Hydrograph Plot

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 11.64 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 12,569 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 4.42 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 17,162 cuft



Multi-Hydrograph Plot

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 12.73 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 13,751 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 4.68 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 18,830 cuft



Multi-Hydrograph Plot

Hyd. No. 1


Pre Development

Hydrograph type = Rational
Peak discharge = 13.78 cfs
Time to peak = 0.30 hrs
Hyd. Volume = 14,883 cuft

Hyd. No. 3

Detention

Hydrograph type = Reservoir
Peak discharge = 4.91 cfs
Time to peak = 0.25 hrs
Hyd. Volume = 20,388 cuft



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	7.535	1	18	8,138	-----	-----	-----	Pre Development
2	Rational	23.30	1	8	11,184	-----	-----	-----	Post Development
3	Reservoir	3.044	1	15	11,152	2	345.28	9,832	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 2 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 7.535 cfs
Storm frequency	= 2 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 8,138 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 3.571 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Lon -92.4569).IDF 1/1		



Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 23.30 cfs
Storm frequency	= 2 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 11,184 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 5.164 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 34.6349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 3.044 cfs
Storm frequency	= 2 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 11,152 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 345.28 ft
Reservoir name	= Pond	Max. Storage	= 9,832 cuft

Storage Indication method used.



Pond No. 1 - Pond

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 344.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	344.00	6,800	0	0
0.50	344.50	7,411	3,551	3,551
1.50	345.50	8,687	8,040	11,591
2.50	346.50	10,035	9,352	20,943
3.50	347.50	11,456	10,737	31,680


Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 12.00	0.00	0.00	0.00
Span (in)	= 12.00	0.00	0.00	0.00
No. Barrels	= 1	0	0	0
Invert El. (ft)	= 344.00	0.00	0.00	0.00
Length (ft)	= 25.00	0.00	0.00	0.00
Slope (%)	= 1.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 5.00	0.00	0.00	0.00
Crest El. (ft)	= 346.50	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= Rect	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.000 (by Contour)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	8.984	1	18	9,703	-----	-----	-----	Pre Development
2	Rational	27.72	1	8	13,308	-----	-----	-----	Post Development
3	Reservoir	3.636	1	15	13,276	2	345.51	11,662	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 5 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 8.984 cfs
Storm frequency	= 5 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 9,703 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 4.257 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 34.6349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 27.72 cfs
Storm frequency	= 5 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 13,308 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 6.145 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, N 3214569).IDF 1/1		




Hydrograph Report

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 3.636 cfs
Storm frequency	= 5 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 13,276 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 345.51 ft
Reservoir name	= Pond	Max. Storage	= 11,662 cuft

Storage Indication method used.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	10.12	1	18	10,933	-----	-----	-----	Pre Development
2	Rational	31.20	1	8	14,974	-----	-----	-----	Post Development
3	Reservoir	3.992	1	15	14,943	2	345.66	13,120	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 10 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 10.12 cfs
Storm frequency	= 10 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 10,933 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 4.797 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 34.6349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 31.20 cfs
Storm frequency	= 10 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 14,974 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 6.914 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Lon -92.4569).IDF 1/1		



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025


Friday, 05 / 16 / 2025

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 3.992 cfs
Storm frequency	= 10 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 14,943 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 345.66 ft
Reservoir name	= Pond	Max. Storage	= 13,120 cuft

Storage Indication method used.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	11.64	1	18	12,569	-----	-----	-----	Pre Development
2	Rational	35.82	1	8	17,193	-----	-----	-----	Post Development
3	Reservoir	4.423	1	15	17,162	2	345.87	15,083	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 25 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 11.64 cfs
Storm frequency	= 25 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 12,569 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 5.515 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 34.6349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 35.82 cfs
Storm frequency	= 25 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 17,193 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 7.939 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Ne 924569).IDF 1/1		




Hydrograph Report

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 4.423 cfs
Storm frequency	= 25 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 17,162 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 345.87 ft
Reservoir name	= Pond	Max. Storage	= 15,083 cuft

Storage Indication method used.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	12.73	1	18	13,751	-----	-----	-----	Pre Development
2	Rational	39.29	1	8	18,861	-----	-----	-----	Post Development
3	Reservoir	4.681	1	15	18,830	2	346.03	16,576	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 50 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 12.73 cfs
Storm frequency	= 50 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 13,751 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 6.034 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 39.29 cfs
Storm frequency	= 50 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 18,861 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 8.709 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Ne 924569).IDF 1/1		




Hydrograph Report

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 4.681 cfs
Storm frequency	= 50 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 18,830 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 346.03 ft
Reservoir name	= Pond	Max. Storage	= 16,576 cuft

Storage Indication method used.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2025

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	13.78	1	18	14,883	-----	-----	-----	Pre Development
2	Rational	42.54	1	8	20,419	-----	-----	-----	Post Development
3	Reservoir	4.907	1	15	20,388	2	346.18	17,991	Detention
23-1109 Pond calculation_05.09.2025.gpw					Return Period: 100 Year			Friday, 05 / 16 / 2025	

Hydrograph Report

Hyd. No. 1

Pre Development

Hydrograph type	= Rational	Peak discharge	= 13.78 cfs
Storm frequency	= 100 yrs	Time to peak	= 18 min
Time interval	= 1 min	Hyd. volume	= 14,883 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.47
Intensity	= 6.530 in/hr	Tc by User	= 18.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Lon -92.4569).IDF 1/1		




Hydrograph Report

Hyd. No. 2

Post Development

Hydrograph type	= Rational	Peak discharge	= 42.54 cfs
Storm frequency	= 100 yrs	Time to peak	= 8 min
Time interval	= 1 min	Hyd. volume	= 20,419 cuft
Drainage area	= 4.700 ac	Runoff coeff.	= 0.96
Intensity	= 9.428 in/hr	Tc by User	= 8.00 min
IDF Curve	= Bryant, Arkansas, USA (La 346349, Ne 924569).IDF 1/1		




Hydrograph Report

Hyd. No. 3

Detention

Hydrograph type	= Reservoir	Peak discharge	= 4.907 cfs
Storm frequency	= 100 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 20,388 cuft
Inflow hyd. No.	= 2 - Post Development	Max. Elevation	= 346.18 ft
Reservoir name	= Pond	Max. Storage	= 17,991 cuft

Storage Indication method used.



Hydraflow Rainfall Report

Return Period (Yrs)	Intensity-Duration-Frequency Equation Coefficients (FHA)			
	B	D	E	(N/A)
1	0.0000	0.0000	0.0000	-----
2	27.5237	5.1000	0.6504	-----
3	0.0000	0.0000	0.0000	-----
5	34.4145	5.5000	0.6620	-----
10	39.6208	5.7000	0.6670	-----
25	45.2262	5.7000	0.6648	-----
50	46.6831	5.2000	0.6507	-----
100	47.7305	4.8000	0.6362	-----

File name: Bryant, Arkansas, USA (La 34.6349 Lo -92.4569).IDF

Intensity = B / (Tc + D)^E

Return Period (Yrs)	Intensity Values (in/hr)											
	5 min	10	15	20	25	30	35	40	45	50	55	60
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	6.12	4.71	3.91	3.38	3.01	2.72	2.49	2.31	2.16	2.03	1.92	1.82
3	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5	7.26	5.61	4.66	4.03	3.58	3.24	2.97	2.75	2.57	2.41	2.28	2.16
10	8.15	6.31	5.25	4.54	4.04	3.65	3.34	3.10	2.89	2.71	2.56	2.43
25	9.36	7.25	6.03	5.23	4.64	4.20	3.85	3.56	3.33	3.12	2.95	2.80
50	10.30	7.94	6.60	5.72	5.08	4.60	4.22	3.91	3.65	3.43	3.24	3.08
100	11.17	8.60	7.14	6.19	5.51	4.99	4.58	4.25	3.97	3.74	3.54	3.36

Tc = time in minutes. Values may exceed 60.

Precip. file name: Sample.pcp

Storm Distribution	Rainfall Precipitation Table (in)							
	1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr
SCS 24-hour	0.00	2.20	0.00	3.30	4.25	5.77	6.80	7.95
SCS 6-Hr	0.00	1.80	0.00	0.00	2.60	0.00	0.00	4.00
Huff-1st	0.00	1.55	0.00	2.75	4.00	5.38	6.50	8.00
Huff-2nd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-3rd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-4th	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-Indy	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Custom	0.00	1.75	0.00	2.80	3.90	5.25	6.00	7.10

Watershed Model Schematic.....	1
Hydrograph Return Period Recap.....	2
2 - Year	
Summary Report.....	3
Hydrograph Reports.....	4
Hydrograph No. 1, Rational, Pre Development.....	4
Hydrograph No. 2, Rational, Post Development.....	5
Hydrograph No. 3, Reservoir, Detention.....	6
Pond Report - Pond.....	7
5 - Year	
Summary Report.....	8
Hydrograph Reports.....	9
Hydrograph No. 1, Rational, Pre Development.....	9
Hydrograph No. 2, Rational, Post Development.....	10
Hydrograph No. 3, Reservoir, Detention.....	11
10 - Year	
Summary Report.....	12
Hydrograph Reports.....	13
Hydrograph No. 1, Rational, Pre Development.....	13
Hydrograph No. 2, Rational, Post Development.....	14
Hydrograph No. 3, Reservoir, Detention.....	15
25 - Year	
Summary Report.....	16
Hydrograph Reports.....	17
Hydrograph No. 1, Rational, Pre Development.....	17
Hydrograph No. 2, Rational, Post Development.....	18
Hydrograph No. 3, Reservoir, Detention.....	19
50 - Year	
Summary Report.....	20
Hydrograph Reports.....	21
Hydrograph No. 1, Rational, Pre Development.....	21
Hydrograph No. 2, Rational, Post Development.....	22
Hydrograph No. 3, Reservoir, Detention.....	23
100 - Year	
Summary Report.....	24
Hydrograph Reports.....	25
Hydrograph No. 1, Rational, Pre Development.....	25
Hydrograph No. 2, Rational, Post Development.....	26
Hydrograph No. 3, Reservoir, Detention.....	27
IDF Report.....	28



NOAA Atlas 14, Volume 9, Version 2
Location name: Bryant, Arkansas, USA*
Latitude: 34.6349°, Longitude: -92.4569°
Elevation: 350 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Deborah Martin, Sandra Pavlovic, Ishani Roy, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Michael Yekta, Geoffrey Bonnin

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerals](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	5.40 (4.36-6.64)	6.12 (4.93-7.52)	7.26 (5.83-8.94)	8.17 (6.53-10.1)	9.38 (7.22-11.9)	10.3 (7.76-13.2)	11.2 (8.15-14.7)	12.0 (8.42-16.2)	13.1 (8.84-18.1)	13.9 (9.17-19.6)
10-min	3.95 (3.19-4.85)	4.48 (3.61-5.50)	5.31 (4.27-6.55)	5.98 (4.78-7.40)	6.87 (5.29-8.69)	7.53 (5.68-9.67)	8.17 (5.96-10.7)	8.79 (6.17-11.9)	9.58 (6.48-13.3)	10.2 (6.71-14.3)
15-min	3.22 (2.59-3.95)	3.64 (2.93-4.48)	4.32 (3.47-5.32)	4.86 (3.88-6.02)	5.59 (4.30-7.07)	6.12 (4.62-7.86)	6.64 (4.85-8.72)	7.15 (5.02-9.64)	7.79 (5.27-10.8)	8.26 (5.46-11.7)
30-min	2.39 (1.93-2.94)	2.72 (2.19-3.34)	3.24 (2.60-3.99)	3.65 (2.92-4.52)	4.20 (3.23-5.31)	4.60 (3.47-5.91)	4.99 (3.64-6.55)	5.37 (3.77-7.23)	5.84 (3.95-8.09)	6.18 (4.09-8.73)
60-min	1.60 (1.29-1.97)	1.82 (1.46-2.23)	2.16 (1.73-2.66)	2.43 (1.94-3.01)	2.80 (2.16-3.55)	3.08 (2.33-3.96)	3.36 (2.45-4.42)	3.63 (2.55-4.90)	3.98 (2.69-5.51)	4.23 (2.80-5.98)
2-hr	1.00 (0.817-1.22)	1.14 (0.922-1.38)	1.35 (1.09-1.65)	1.52 (1.22-1.87)	1.76 (1.37-2.21)	1.93 (1.47-2.47)	2.11 (1.55-2.76)	2.29 (1.62-3.07)	2.52 (1.71-3.47)	2.69 (1.79-3.77)
3-hr	0.753 (0.615-0.913)	0.850 (0.694-1.03)	1.01 (0.822-1.23)	1.14 (0.926-1.40)	1.33 (1.04-1.67)	1.47 (1.13-1.87)	1.61 (1.20-2.10)	1.76 (1.25-2.36)	1.95 (1.34-2.69)	2.10 (1.40-2.94)
6-hr	0.453 (0.373-0.545)	0.514 (0.424-0.620)	0.618 (0.508-0.746)	0.707 (0.577-0.857)	0.834 (0.660-1.04)	0.935 (0.723-1.19)	1.04 (0.776-1.35)	1.15 (0.822-1.53)	1.29 (0.893-1.77)	1.41 (0.946-1.96)
12-hr	0.265 (0.220-0.316)	0.305 (0.253-0.364)	0.374 (0.309-0.447)	0.433 (0.357-0.521)	0.520 (0.416-0.649)	0.590 (0.461-0.746)	0.664 (0.500-0.859)	0.741 (0.536-0.984)	0.848 (0.590-1.16)	0.932 (0.630-1.29)
24-hr	0.155 (0.130-0.184)	0.180 (0.151-0.214)	0.223 (0.186-0.265)	0.261 (0.216-0.311)	0.316 (0.255-0.392)	0.361 (0.284-0.454)	0.409 (0.311-0.526)	0.459 (0.335-0.607)	0.530 (0.371-0.719)	0.586 (0.399-0.803)
2-day	0.091 (0.077-0.107)	0.105 (0.088-0.123)	0.129 (0.109-0.152)	0.150 (0.126-0.178)	0.182 (0.148-0.224)	0.208 (0.165-0.259)	0.235 (0.180-0.300)	0.264 (0.194-0.347)	0.305 (0.215-0.411)	0.337 (0.231-0.459)
3-day	0.066 (0.056-0.077)	0.076 (0.065-0.089)	0.093 (0.079-0.109)	0.108 (0.091-0.128)	0.130 (0.106-0.160)	0.148 (0.118-0.184)	0.167 (0.128-0.212)	0.187 (0.138-0.244)	0.214 (0.152-0.288)	0.236 (0.162-0.321)
4-day	0.053 (0.045-0.062)	0.061 (0.052-0.071)	0.074 (0.063-0.087)	0.086 (0.072-0.101)	0.103 (0.084-0.125)	0.116 (0.093-0.144)	0.131 (0.101-0.165)	0.146 (0.108-0.190)	0.167 (0.118-0.223)	0.183 (0.126-0.248)
7-day	0.035 (0.030-0.040)	0.040 (0.034-0.046)	0.048 (0.041-0.056)	0.055 (0.047-0.064)	0.065 (0.054-0.079)	0.074 (0.059-0.090)	0.082 (0.063-0.103)	0.091 (0.067-0.117)	0.103 (0.073-0.136)	0.112 (0.078-0.151)
10-day	0.028 (0.024-0.032)	0.031 (0.027-0.036)	0.037 (0.032-0.043)	0.042 (0.036-0.049)	0.050 (0.041-0.060)	0.055 (0.045-0.067)	0.061 (0.048-0.076)	0.067 (0.050-0.087)	0.076 (0.054-0.100)	0.082 (0.057-0.110)
20-day	0.018 (0.016-0.021)	0.020 (0.018-0.023)	0.024 (0.020-0.027)	0.026 (0.023-0.030)	0.030 (0.025-0.036)	0.033 (0.027-0.040)	0.036 (0.028-0.044)	0.039 (0.029-0.049)	0.043 (0.031-0.056)	0.046 (0.032-0.061)
30-day	0.015 (0.013-0.017)	0.016 (0.014-0.019)	0.019 (0.016-0.022)	0.021 (0.018-0.024)	0.024 (0.020-0.028)	0.026 (0.021-0.031)	0.028 (0.022-0.034)	0.030 (0.022-0.038)	0.032 (0.023-0.042)	0.034 (0.024-0.046)
45-day	0.012 (0.010-0.014)	0.013 (0.012-0.015)	0.015 (0.013-0.017)	0.017 (0.015-0.019)	0.019 (0.016-0.023)	0.021 (0.017-0.025)	0.022 (0.018-0.027)	0.024 (0.018-0.030)	0.026 (0.019-0.034)	0.027 (0.019-0.036)
60-day	0.010 (0.009-0.011)	0.011 (0.010-0.013)	0.013 (0.012-0.015)	0.015 (0.013-0.017)	0.017 (0.014-0.020)	0.018 (0.015-0.022)	0.020 (0.016-0.024)	0.021 (0.016-0.027)	0.023 (0.017-0.030)	0.024 (0.017-0.032)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

A


B

C

A

B

C



1 FLOOR PLAN
Scale: 3/16" = 1'-0"

CERTIFICATION:

A2.2

ROGUE Architecture PLLC
300 S Spring Street
Suite 720
Little Rock, Arkansas 72201
[p] 501.365.1576
[w] www.roguearch.com

PROPOSED FLOOR PLANS

Issue Date: 2025.05.20

GOOD DAY FARM
DISPENSARY

2320 HURRICANE LAKE ROAD
Bryant, Arkansas

ROGUE
architecture



A


B

C

A

B

C



1 NORTH ELEVATION
Scale: 1/4" = 1'-0"



2 EAST ELEVATION
Scale: 1/4" = 1'-0"

CERTIFICATION:

2025.05.20

Issue Date:

Revisions

A4.4

GOOD DAY FARM
DISPENSARY
2320 HURRICANE LAKE ROAD
Bryant, Arkansas

ROGUE

architecture

ROGUE Architecture PLLC
300 S Spring Street
Suite 720
Little Rock, Arkansas 72201
[p] 501.365.1576
[w] www.roguearch.com

CERTIFICATE OF AUTHORIZATION
FOR THE
ARCHITECTURE
NO. 162
ARKANSAS
NOT FOR CONSTRUCTION

A

A

B

B

C

C

CERTIFICATION:



1 SOUTH ELEVATION
Scale: 1/4" = 1'-0"



2 WEST ELEVATION
Scale: 1/4" = 1'-0"

A4.3

ROGUE Architecture PLLC
300 S Spring Street
Suite 720
Little Rock, Arkansas 72201
[p] 501.365.1576
[w] www.roguearch.com

GOOD DAY FARM DISPENSARY

2320 HURRICANE LAKE ROAD
Bryant, Arkansas


2025.05.20

Issue Date:


Revisions					

EXTERIOR ELEVATIONS


NO CONSTRUCTION




Landscape Plan
SCALE 1"=20'




Spade Cut Bed Edge




Typical Perennial Planting




Typical Shrub Planting



Typical Canopy Tree Planting



Typical Evergreen Planting



Tree Protection Detail

PLANTING SCHEDULE					
ID	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
CANOPY-SHADE TREE					
A	2	Acer saccharum 'Baista'	Fall Fiesta Sugar Maple	3" caliper	B & B

Landscape Summary:

- Minimum landscaping criteria:
 - C-2 zoning = 1 tree per 1/2 acre
 - 41,666 s.f. / 2 = 1.91 half-acre units x 1 tree = 2 trees required
 - C-2 zoning = 1 evergreen per 2,000 s.f.
 - 1,988 s.f. / 2,000 s.f. = 1 evergreen required

PLANTING SCHEDULE					
ID	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
SHRUBS-ORNAMENTAL GRASSES-PERENNIALS-ANNUALS-GROUNDCOVER					
a	4	Ilex x meserveae meserveae 'Heckenstar'	Castle Wall Blue Holly	18" tall	60" o.c.
b	3	Ilex x meserveae 'SMNIFA'	Castle Keep Blue Holly	18" tall	60" o.c.
c	6	Abelia x grandiflora 'Radiance'	Radiance Abelia	18" tall	48" o.c.
d	11	Juniperus horizontalis 'Wiltonii'	Blue Rug Juniper	18" tall	36" o.c.

Landscape Notes:

- Provide lawn in all disturbed areas.
 - All 3:1 or steeper slopes shall be lawn seed and have erosion control blanket.
- Topsoil in all disturbed lawn areas at 6" depth.
- Soil mix in all shrub beds at 8" depth.
- All mulch to be double ground bark mulch.
- Bed edges to be spade cut.

Tree Protection Notes:

- Pre-construction meeting to be held on-site to include a presentation of tree protection measures to operators, construction supervisors, developer's representative, and city zoning inspector.
- Clearing Limits to be rough staked in order to facilitate location for installation of protection fencing. No early maintenance schedule is required.
- No clearing or grading shall begin in areas where the treatment and preservation measures have not been completed, including the installation of tree protection fencing as shown on the plan. Where necessary, Contractor may perform minor tree clearing prior to installing silt fencing and tree protection fencing provided they maintain tree protection area.
- Tree Protection Fencing shall be 4-foot high temporary plastic construction fence. No equipment traffic/parking, concrete washout, material storage or other such construction activity shall be permitted to penetrate the protection fencing except for the removal of dead or invasive plant material. All ground plane in planting areas shall be mulched with hardwood bark mulch. Tree Protection Signage will be placed along the Protection Fencing as shown as the dashed line on the plan.
- Tree protection measures to be maintained throughout construction.



Lee Hess - Landscape Architect
AR License # LA-712056

Consultants:

GOOD DAY FARMS

3205 HIGHWAY 5 N
BRYANT, ARKANSAS 72019

Revisions:

Date	Description	No.

Drawn: RS
Checked: LH



Sheet Title: LANDSCAPE PLAN

Sheet No: L1.01

Date: 5/20/25
Job #: 813.150



Regan Etheridge
Good Day Farm Dispensary
425 W. Capitol Ave., Suite 1400
Little Rock, AR 72201
reetheridge@gooddayfarm.com
(501)551-0502

May 21, 2025

Development and Review Committee
The City of Bryant
210 SW 3rd Street
Bryant, AR 72022

RE: Small Scale Commercial Development Plan - Narrative of Request and Operations

Dear Development and Review Committee of Bryant,

Please accept this letter as our official request for the commercial development of 3205 HWY 5 N Parcel ID: 840-12042-000 & 2320 Hurricane Lake Rd Parcel ID: 840-12038-000 (the “**Property**”) for the ground-up build of a medical marijuana facility. The planned facility will occupy a 1,987 sqft. building with drive-through operations, fully compliant with all applicable regulations, laws, and codes of the City of Bryant, Arkansas.

Both properties are zoned C-2, where commercial uses such as Institutional - Large Scale and Institutional - Small Scale are permitted. A medical marijuana dispensary falls within these categories. Our site comfortably exceeds the required distance from any public or private school, church, daycare center, or center for the developmentally disabled, as documented in the included distance certification.

Thank you for your attention to our application. We appreciate your consideration and look forward to your guidance as we move forward.

Sincerely,

A handwritten signature in black ink that reads "Regan Etheridge".

Regan Etheridge
Senior Project Manager of Store Development

GOOD PEOPLE. GOOD CANNABIS. GOOD DAY.

425 W. Capitol Ave. 14th Floor, Little Rock, AR 72201

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

GarNat Engineering, LLC

P.O. Box 116
Benton, AR 72018

TO WHOM IT MAY CONCERN:


I hereby certify that the property, consisting of four parcels, 840-12042-000 located at 3205 Highway 5 North, 840-12038-000 located at 2320 Hurricane Lake Road, 840-12037-000 located at 2400 Hurricane Lake Road, and 840-12036-000 located at 2410 Hurricane Lake Road, Bryant, Arkansas, as more particularly described on EXHIBIT A hereto (the “**PROPERTY**”) is not within 1,500 feet of a known public or private school, church, daycare center, or center for the developmentally disabled.

The closest church to the Property is: Hurricane Lake Baptist Church located at 2516 Springhill Road which sits approximately 1,828 +/- feet from the Property, as measured in accordance with applicable rules and regulations governing medical marijuana dispensaries.

The closest school to the Property is: Arkansas Christian Academy located at 21815 I-30 Frontage Road which sits approximately 1,737 +/- feet from the Property, as measured in accordance with applicable rules and regulations governing medical marijuana dispensaries.

The closest daycare center to the Property is: Kids Town Academy located at 21941 I-30 South which sits approximately 2,270 +/- feet from the Property, as measured in accordance with applicable rules and regulations governing medical marijuana dispensaries.

The closest center for the developmentally disabled to the Property is: Civitan Services Bryant Campus located at 403 South Reynolds Road which sits approximately 12,328 +/- feet from the Property, as measured in accordance with applicable rules and regulations governing medical marijuana dispensaries.



Sincerely,

A handwritten signature in blue ink that reads "George P. Wooden".

[Surveyor]

12-5-24



**City of Bryant Mayor
Chris Treat**

Thursday, December 12, 2024

To Whom It May Concern,

The property located at 3205 HWY 5 N with parcel number 840-12042-000 is zoned as C-2 Commercial, and the property located at 2320 Hurricane Lake Rd with parcel number 840-12038-000 is also zoned as C-2 Commercial.

The commercial uses of Institutional – Large Scale and Institutional – Small Scale are both permitted uses under the C-2 Zoning.

A medical marijuana dispensary would fall under the commercial use of “Institutional - Small Scale” or “Institutional – Large Scale.”

Additional zoning regulations and permitted uses for this zone can be found at the cityofbryant.com by clicking on “Zoning Code” on the Community Development page under “Codes and Maps”.

If there are any questions or concerns, please feel free to contact me at ctreat@cityofbryant.com or 501-943-0999.

Sincerely,

A handwritten signature in blue ink, appearing to be "C. Treat", is written over a horizontal line.

Chris Treat
Mayor



City of Bryant, Arkansas

Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0488, Comdev@cityofbryant.com

Sign Permit Application

Date: 05/06/2025

Applicant / Owner

Applicant Name: Hope Garcia
Address: 4111 S 74th E Ave
City, State, Zip: Tulsa, OK 74145
Phone: 214-500-3003
Email: hgarcia@lektroninc.com

Owner Name: Little Rock LD, LLC
Address: P.O. Box 10560
City, State, Zip: Fayetteville, AR 72703
Phone: 501-945-0455
Email: hgarcia@lektroninc.com

General Information

Business Name: Lektron LED Technologies
DBA Lektron Branding
Solutions
Site Address: 3021 Midland Rd

Dwelling Type:

Project Description: Midland Road Estates- Two Subdivision Entryway Monuments

I do hereby certify that the information contained herein is true and correct.

Hope Garcia
Name

05/06/2025
Date

Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering in packet.

SIGN	Type (Façade, Pole, Monument, other)	Dimensions (Height, Length, Width)	Sqft (Measurement standards found on Pg.7 of Sign Code)	Façade Width (Linear Ft of building façade where wall sign is being installed)	Height	
					To Top	To Bottom
A	Monument	6'H x 8.5'L x 12"W	26.88 sq. ft.	N/A	6'	22"
B	Monument	6'H x 8.5'L x 12"W	26.88 sq. ft.	N/A	6'	22"
C						
D						
E						
F						

Monument Option 1

A 2-PFO 88" x 47" x 1/2" Thick MDO Sign Panel

- Backer Painted SW 7071 Gray Screen
- 3mm Dibond Overlay, Pantone 2266 C
- Custom 6mm Dibond Logo & Letters, White Satin
- Cut Vinyl Bead

B (2x) 12" x 12" x 18" Stone Masonry Base

- 14" x 14" x 2" Capstone
- (2x) 4" x 4" x 96" Steel Posts
- 54" Visible, 18" in Masonry, 24" Below Grade

C 96" x 55" x 1" Welded Tube Frame

- Black Powdercoat Finish
- Welded to Steel Posts



Project:
Midland Road Estates-Rausch Coleman

Customer Approval:

Via Phone: ☐ Via Email: ☐

Date: 4-21-2025

Sales Rep: Roland W.

Address:

Rev. No.

Designer: Rhonda M.

Proof Disclaimer: An email or fax stating your approval constitutes the total and final approval to produce your job as is on this proof or with changes indicated. While we make every attempt to eliminate mistakes in our proof progression, sometimes overights occur. You have the final responsibility for review to assure there are no errors. Overights that require the job to be reproduced will be done at your expense.

These drawings are the exclusive property of Lektron Branding Solution, and are the result of original work by its employees. They are submitted for the sole purpose of your consideration of whether to purchase these plans. Distribution or exhibition of these plans to others is expressly forbidden. Signs will be built to meet UL specifications if required.



COMPUTED LOCATION
NE CORNER,
S1/2, SE1/4, NE1/4,
PER WILLIAMS (PS 1091)

65.00' 60.00' 60.00' 60.00' 60.00' 72.13' 26.34'

108
0.19 ACRES
8124 Sq. Ft.
MIN FFE 356'

109
0.17 ACRES
7488 Sq. Ft.
MIN FFE 355.5'

110
0.17 ACRES
7476 Sq. Ft.
MIN FFE 355'

111
0.17 ACRES
7465 Sq. Ft.
MIN FFE 355'

112
0.20 ACRES
8720 Sq. Ft.
MIN FFE 354'

124.89' 124.70' 124.51' 124.33' 09.47'

20' B.S.L. 20' B.S.L.

65.00' 60.00' 60.00' 60.00' 45.31'

32' to Center of 'A' Drive

CAK

32' to Center of 'A' Drive

32' to Center of 'A' Drive

**47' to Center
Midland Rd.**

0.65 ACRES
28134 Sq. Ft.

32' to Center of 'A' Drive

RETENTION AREA

MIN FFE 355.5

0.19 ACRES
423 Sq. Ft.

0.20 ACRES
8534 Sq. Ft.

4" W 662.49'

N86°30'24"W 662.49'

S88°16'44"E 818.66'

N1°43'28"E 141.31'

N1°43'28"E 143.17'

S2°32'37"W 333.26'

123.77'

60.00'

60.00'

60.03'

33.1'

4" M

- ROAD RIGHT OF WAY DEDICATION

Rod's.Signs@yahoo.com



City of Bryant, Arkansas
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0943

SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at www.cityofbryant.com under the Community Development tab.

Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.

Date: 5/6/25

Sign Co. or Sign Owner Rodney Barefield

Name Rod's Signs, LLC

Address 111 Dogwood PL DR

City, State, Zip Bryant, AR 72022

Phone 501-351-4077

Alternate Phone Same

Property Owner

Name Melnika Bale

Address 5920 Hwy 5 N # 5

City, State, Zip Bryant, AR 72022

Phone 501-240-8098

Alternate Phone Same

GENERAL INFORMATION

Name of Business LATA DA Learning ~~Center~~ Creative Arts

Address/Location of sign 5920 Hwy 5 N, # 5 CENTER, LLC

Zoning Classification _____

Please use following page to provide details on the signs requesting approval. Along with information provided on this application, a Site Plan showing placement of sign(s) and any existing sign(s) on the property is **required** to be submitted. Renderings of the sign(s) showing the correct dimensions is also **required** to be submitted with the application. A fifty dollar (\$50) per sign payment will be collected at the time of permit issuance. According to the Sign Ordinance a fee for a sign variance or Alternative Signage Plan request shall be two hundred and fifty dollars (\$250). Additional documentation may be required by Sign Administrator.

READ CAREFULLY BEFORE SIGNING

I [Signature], do hereby certify that all information contained within this application is true and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand that no sign may be placed in public right of way. I understand that I must comply with all Building and Electrical Codes and that it is my responsibility to obtain all necessary permits.

Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering in packet.

SIGN	Type (Façade, Pole, Monument, other)	Dimensions (Height, Length, Width)	Sqft (Measurement standards found on Pg.7 of Sign Code)	Façade Width (Linear Ft of building façade where wall sign is being installed)	Height	
					To Top	To Bottom
A	Facade	3'H x 10'W	30 SF	30 Ft		
B	Facade	3'H x 10'W	30 SF	60 Ft		
C						
D						
E						
F						

STE. 5
STE. 6+7

501-351-4077


STE 5 & 6

SIGN A

STE. 5

10'

10'




~~3' x 12'~~
3' x 10'

30'

STE. 6+7

SIGN B



3' x 10'
~~3' x 12'~~