

PLAT CERTIFICATES:

**OWNER:**  
Name: Bryant Realty Company, LLC  
Address: 422 North Main Street, Benton, Arkansas 72015

**DEVELOPER:**  
Name: Bryant Realty Company, LLC  
Address: 422 North Main Street, Benton, Arkansas 72015

**CERTIFICATE OF OWNER:**  
We, the undersigned, owners of the real estate shown and described herein do hereby certify that we have laid off, platted and subdivided, and do hereby lay off, plat and subdivide said real estate in accordance with the within plat.

Date: \_\_\_\_\_ Signed: \_\_\_\_\_  
Name: Fred Briner  
Address: 422 North Main Street, Benton, Arkansas 72015

Source of Title Saline County: Deed Book 2000, Page 27387

**CERTIFICATE OF ENGINEERING ACCURACY:**  
I, Vernon J. Williams, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their locations, size, type, and material are correctly shown; and that all requirements of the City of Bryant Subdivision Rules and Regulations have been fully complied with.

Date: \_\_\_\_\_ Signed: \_\_\_\_\_  
Vernon J. Williams  
Registered Professional Engineer  
No. 9551, Arkansas

**CERTIFICATE OF SURVEYING ACCURACY:**  
I, George P. Wooden, hereby certify that this plat correctly represents a boundary survey made by me or under my supervision; that the boundary lines shown hereon correspond with the description in the deeds cited in the above Source of Title; and that all monuments which were found or placed on the property are correctly described and located.

Date: \_\_\_\_\_ Signed: \_\_\_\_\_  
George P. Wooden  
Registered Land Surveyor  
No. 1573, Arkansas

**CERTIFICATE OF FINAL PLAT APPROVAL:**  
Pursuant to the City of Bryant Subdivision Rules and Regulations, this document was given approval by the Bryant Planning Commission. All of the document is hereby accepted, and this certificate executed under the authority of said rules and regulations.


Date: \_\_\_\_\_ Signed: \_\_\_\_\_  
Lance Penfield, Chairman  
Bryant Planning Commission

**CERTIFICATE OF RECORDING:**


**SUBDIVISION DESCRIPTION:**

LOCATED IN THE EAST HALF OF THE NORTHWEST QUARTER (E1/2 NW1/4), OF SECTION 22, TOWNSHIP 01 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PRECISELY DESCRIBED AS FOLLOWS:

**COMMENCING** AT A FOUND 2" ALUMINUM CAP LOCATED AT THE NORTHEAST CORNER OF THE NORTHWEST QUARTER (NW1/4) OF SECTION 22, TOWNSHIP 01 SOUTH, RANGE 14 WEST, SAID POINT ALSO BEING ON THE EAST LINE OF HUNTER CROSSING SUBDIVISION; THENCE S 2°19'11" W, ALONG THE EAST LINE OF SAID NW1/4 AND SAID SUBDIVISION FOR A DISTANCE OF 740.62 FEET TO A FOUND 5/8" REBAR WITH CAP LOCATED AT THE SOUTHEAST CORNER OF SAID SUBDIVISION FOR THE **POINT OF BEGINNING**; THENCE S 2°16'37" W, LEAVING SAID SUBDIVISION AND CONTINUING ALONG SAID EAST LINE OF THE NW1/4 FOR A DISTANCE OF 109.30 FEET TO A SET 1/2" REBAR WITH CAP #1573 LOCATED ON THE NORTH LINE OF A SEWER EASEMENT; THENCE N 89°34'46" W, LEAVING SAID EAST LINE AND ALONG SAID NORTH LINE OF SEWER EASEMENT, A DISTANCE OF 126.09 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE N 66°21'14" W, CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 278.28 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE N 53°54'43" W, CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 305.25 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE S 82°18'35" W, CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 252.15 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE S 19°51'00" E, LEAVING SAID NORTH LINE OF SEWER EASEMENT, A DISTANCE OF 30.74 FEET TO A FOUND BENT 5/8" REBAR; THENCE S 75°49'54" W FOR A DISTANCE OF 237.67 FEET TO A FOUND 5/8" REBAR WITH CAP #1141 LOCATED ON THE EAST RIGHT OF WAY OF MARKETPLACE AVENUE; THENCE CONTINUING ALONG SAID EAST RIGHT OF WAY AND ALONG A CURVE TO THE LEFT WITH A RADIUS OF 1586.45 FEET AND A LENGTH OF 243.80 FEET, WHOSE CHORD BEARS N 18°29'44" W - 243.56 FEET TO A SET MAG NAIL LOCATED AT THE CENTERLINE OF PROGRESS WAY (PRIVATE STREET); THENCE ALONG SAID CENTERLINE AND LEAVING SAID EAST RIGHT OF WAY THE FOLLOWING COURSES: THENCE N 70°09'00" E - 290.57 FEET, THENCE ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 300.00 FEET AND A LENGTH OF 101.27 FEET, WHOSE CHORD BEARS N 79°41'39" E - 100.79 FEET, THENCE N 89°21'50" E - 207.51 FEET, THENCE ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 300.00 FEET AND A LENGTH OF 252.62 FEET, WHOSE CHORD BEARS S 86°39'47" E - 248.22 FEET, THENCE S 42°23'24" E - 207.21 FEET TO A POINT LOCATED ON THE WEST LINE OF HUNTER CROSSING SUBDIVISION PHASE 2; THENCE S 2°43'50" E, LEAVING SAID CENTERLINE OF SAID AND ALONG THE WEST LINE OF SAID SUBDIVISION, FOR A DISTANCE OF 28.40 FEET TO A FOUND 5/8" REBAR WITH CAP #1148 LOCATED AT THE SOUTHWEST CORNER OF SAID SUBDIVISION; THENCE S 51°47'53" E, ALONG SAID SOUTH LINE OF SAID SUBDIVISION, FOR A DISTANCE OF 52.90 FEET TO A FOUND 1/2" REBAR WITH CAP #1667; THENCE S 52°14'07" E, CONTINUING ALONG SAID SOUTH LINE FOR A DISTANCE OF 236.02 FEET TO THE **POINT OF BEGINNING**, CONTAINING 6.42 ACRES MORE OR LESS.



## FINAL PLAT - MARKETPLACE EAST PHASE 1 CITY OF BRYANT SALINE COUNTY, ARKANSAS



**DOCUMENTS USED:**

- SURVEY BY REAL ESTATE SERVICES OF SALINE COUNTY, INC. DATED 9/11/2015 KERRY LANE PLS #1141
- SURVEY BY REAL ESTATE SERVICES OF SALINE COUNTY, INC. DATED 1/27/2009 KERRY LANE PLS #1141
- SURVEY BY REAL ESTATE SERVICES OF SALINE COUNTY, INC. DATED 4/21/2022 KERRY LANE PLS #1141
- WARRANTY DEED 2020 PAGE 004456 FRED E. BRINER TO FRED BRINER PROPERTIES, LLC
- SPECIAL WARRANTY DEED 2000 PAGE 27387 HIGHWAY 5 INVESTMENTS, LLC TO BRYANT REALTY COMPANY IMPROVEMENT DISTRICT NO. 26
- SPECIAL WARRANTY DEED 2019 PAGE 016136 FERGUSON-BRINER, LLC TO HCII-3412 MARKET PLACE AVENUE, LLC
- WARRANTY DEED 2000 PAGE 27385 HIGHTOWER TO HIGHWAY 5 INVESTMENTS, LLC
- REVISED FINAL PLAT OF HUNTER CROSSING SUBDIVISION PHASE 1
- REVISED FINAL PLAT OF HUNTER CROSSING SUBDIVISION PHASE 2

**BASIS OF BEARINGS:**

BENCHMARK(S) PROVIDED ARE REBAR AND COORDINATES ON BENCHMARKS ARE NORTH AMERICAN DATUM 1983, ARKANSAS SOUTH ZONE, US SURVEY FEET, GRID COORDINATES AND ELEVATIONS ARE NAVD 1988. COORDINATES AND ELEVATIONS WERE ESTABLISHED USING GPS AND WERE PROCESSED USING THE NATIONAL GEODETIC SURVEYS "ONLINE POSITIONING USER SERVICE" (OPUS).

**CERTIFICATIONS:**

BY AFFIXING MY SEAL AND SIGNATURE, I GEORGE P. WOODEN, PS. NO.1573, HEREBY CERTIFY THAT THIS DRAWING CORRECTLY DEPICTS A SURVEY COMPILED UNDER MY SUPERVISION ON JANUARY 10, 2023.

THIS SURVEY WAS BASED ON LEGAL DESCRIPTIONS AND TITLE WORK FURNISHED BY OTHERS AND DOES NOT REPRESENT A TITLE SEARCH.

THIS PROPERTY IS NOT LOCATED IN THE 100 YEAR FLOOD PLAIN. THE PROPERTY SHOWN ON THIS PLAT IS LOCATED IN ZONE "X" OF THE F.E.M.A. MAP PANEL 05125C0240E EFFECTIVE DATE JUNE 05, 2020.

**PROPERTY SPECIFICATIONS:**

ZONING CLASSIFICATION: C-2  
SOURCE OF WATER: CITY OF BRYANT  
SOURCE OF SEWER: CITY OF BRYANT  
BUILDING SETBACKS (SB):  
FRONT - 50'  
REAR - 25'  
SIDE INTERIOR - 15'  
SIDE EXTERIOR - 15'  
EASEMENTS: UTILITY & DRAINAGE (D.E. & U.E.)  
FRONT, SIDE AND REAR - 10' OR AS SHOWN  
INGRESS/EGRESS (I/E)  
LOT CORNERS: SET #4 REBAR WITH CAP


**NOTES:**

- ALL LOTS WILL HAVE SIDEWALKS. THESE WILL BE ADDED WHEN EACH SITE PLAN IS SUBMITTED FOR APPROVAL TO THE CITY OF BRYANT AND MEET BRYANT CONSTRUCTION STANDARDS.
- FINAL PLAT WILL NOT BE APPROVED UNTIL 8" WATER LINE AT SOUTH END OF HUNTER CROSSING IS LOOPEO TO EXISTING 12" IN THIS SUBDIVISION.
- FIRE TRUCK ACCESS TO HUNTER CROSSING HAS NOT BEEN MAINTAINED. FINAL PLAT WILL NOT BE APPROVED UNTIL FIRE TRUCK ACCESS IS RESTORED AND ACCEPTABLE TO BRYANT FIRE MARSHAL.

**SURVEY LEGEND**

- △ - Computed point
- - Found monument
- - Set #4 RB/Plas. Cap or Mag Nail with Shiner
- (M) - Measured
- (R) - Record
- (P) - Platted

**SURVEY PLAT CODE:**  
500-01S-14W-0-22-400-62-1573



Curve Table					
Curve #	Length	Radius	Delta	Chord Direction	Chord Length
C4	101.27'	300.00'	19°20'26"	N79° 41' 39" E	100.79'
C5	252.62'	300.00'	48°14'46"	S66° 30' 47" E	245.22'
C6	243.80'	1596.45'	8°44'59"	N18° 29' 44" W	243.56'

BY: \_\_\_\_\_

REVISION: \_\_\_\_\_

DATE: \_\_\_\_\_

Designing our client's success

**GarNat Engineering, LLC**

3825 Mt Carmel Road  
Bryant, AR 72022  
P.O. Box 116  
Benton, AR 72018  
Ph. (501) 408-4650  
garnateengineering@gmail.com

**MARKETPLACE EAST PHASE 1  
BRYANT REALTY COMPANY, LLC  
CITY OF BRYANT  
SALINE COUNTY, ARKANSAS**

REGISTERED PROFESSIONAL SURVEYOR  
STATE OF ARKANSAS  
NO. 1573  
SIGNATURE: GEORGE P. WOODEN

CONTENTS:

**FINAL PLAT**

PROJECT NO:  
20022

DATE:  
JULY 2, 2025

SHEET NO:

**V1.0**