

Drainage Report

For

Bryant Pharmacy

Bryant, Saline County, Arkansas



September 5, 2025

Prepared by:

RICHARDSON ENGINEERING, PLLC

**325 W. South St.
Benton, AR 72015
501-315-7225**

TABLE OF CONTENTS

Title	Page Number
Project Owner Information	3
Project Location and Description	3
Site Drainage	4
Runoff Summary	4
Recommendations/Summary	6
Appendices:	7
<i>Runoff Coefficient Calculation</i>	8
<i>NRCS Soil Report</i>	9
<i>Site Drainage Basin Maps</i>	10
<i>Storm System Design (SSA)</i>	11
<i>2 Year Design Storm</i>	12
<i>10 Year Design Storm</i>	13
<i>25 Year Design Storm</i>	14
<i>50 Year Design Storm</i>	15
<i>100 Year Design Storm</i>	16
<i>Pre and Post Development Hydrographs (Hydrology Studio)</i>	17

Jon Martin
5501 Lombard Road
Alexander, AR 72002

The project is located on West side of the Bryant Parkway, part of the Southeast Quarter of the Northwest Quarter, Section 14, Township 1-S, Range 14-W, Saline County, Arkansas.



3

Site Drainage

Pre-Development

The pre-developed runoff for the site flows to the East and West. The pre-development runoff condition is undeveloped/woods.

Post-Development

The site drainage starts on the South side of the project and flows to the North. The drainage is sheet flows across the proposed parking lot and intercepted by the proposed storm sewer system and is discharged into a proposed detention basin on the Northwest corner of the project. The proposed detention basin will utilize a culvert/weir discharge structure. Post-Development Basin A is the drainage basin that discharges water into the proposed detention basin and Post-Development Basin B and C are the grass tie back slopes from the proposed pavement to existing grade. These areas are not routed through the detention basin, so it was calculated by itself. The post-development runoff conditions changed from undeveloped/woods to commercial development.

Runoff Summary

Overall Basin Design Point

Development Drainage Study Area = 1.92 Ac

Post-Development Drainage Study Area = 1.97

Existing Condition runoff Coefficient: $C = 0.56$

Proposed runoff Coefficient: $C = 0.95/0.58/0.51$

Tc Undeveloped = 9/12 Minutes (TR55 Method)

Tc Developed = 5/10 Minutes

Detention Basin Required Volume: 7,811 CF

Detention Basin Volume: 12,635 CF

Maximum Storage: 1,163 CF

Discharge Structure: Culvert/Weir

Design Storm	Pre-Development Flow Rate (cfs)	Post-Development Flow Rate (cfs)	Post-Development w/ Detention Flow Rate (cfs)
2-yr	4.39	3.90	9.82
10-yr	5.87	5.25	13.13
25-yr	6.75	5.77	15.08
50-yr	7.38	6.26	16.47
100-yr	8.02	6.79	17.91

Pre- Development Basin "A" Design Point
 Drainage Study Area = 1.17 Ac
 Existing runoff Coefficient: C = 0.56
 Tc Undeveloped = 9 Minutes

Design Storm	Post-Development Flow Rate (cfs)
2-yr	3.08
10-yr	4.13
25-yr	4.75
50-yr	5.19
100-yr	5.64

Pre- Development Basin "B" Design Point
 Drainage Study Area = 0.75 Ac
 Existing runoff Coefficient: C = 0.56
 Tc Undeveloped = 12 Minutes

Design Storm	Post-Development Flow Rate (cfs)
2-yr	1.74
10-yr	2.33
25-yr	2.67
50-yr	2.92
100-yr	3.18

Post- Development Basin "A" Design Point
 Drainage Study Area = 1.50 Ac
 Proposed runoff Coefficient: C = 0.95
 Tc Developed = 5 Minutes

Design Storm	Post-Development Flow Rate (cfs)
2-yr	8.75
10-yr	11.70
25-yr	13.44
50-yr	14.68
100-yr	15.96

Post- Development Basin “B” Design Point
 Drainage Study Area = 0.22 Ac
 Proposed runoff Coefficient: C = 0.58
 Tc Developed = 10 Minutes

Design Storm	Post-Development Flow Rate (cfs)
2-yr	0.57
10-yr	0.77
25-yr	0.88
50-yr	0.96
100-yr	1.05

Post- Development Basin “C” Design Point
 Development Drainage Study Area = 0.25 Ac
 Proposed runoff Coefficient: C = 0.51
 Tc Developed = 5 Minutes

Design Storm	Post-Development Flow Rate (cfs)
2-yr	0.78
10-yr	1.05
25-yr	1.20
50-yr	1.31
100-yr	1.43

Recommendations/Summary

The proposed drainage improvements include a storm sewer system and a detention basin on the Northwest corner of the project. The proposed detention basin releases the post development runoff at a lower rate than the pre-development condition.

Appendices

Runoff Coefficient Calculations
NRCS Soil Report
Site Drainage Map
Pond and Post Development Hydrographs (Hydrology Studio)

Runoff Coefficient Calculations

(1/2)

PROJECT 025-029 DRAINAGE ANALYSIS

DATE 09/04/2025

PRE-DEVELOPMENT

DRAINAGE AREA : 1.92 AC


CLAY SOIL

50% - 2%-7% C = 0.50

50% - > 7% C = 0.62

$$C = \frac{(0.960)(0.5) + (0.960)(0.62)}{1.92}$$

$$= 0.56$$



(2/2)

PROJECT 025-029 DRAINAGE ANALYSIS

DATE 09/04/2025

POST-DEVELOPMENT

BASIN "A"

AREA = 1.5 AC

C = 0.75

BASIN "B"

AREA = 0.22 AC (9661 SF)

PERVIOUS : 8092 SF

C = 0.51

(Grass - Good Condition)
7%

IMPERVIOUS : 1569 SF

C = 0.95

$$C = \frac{(8092)(0.51) + (1569)(0.95)}{9661} = \underline{0.58}$$

BASIN "C"

AREA = 0.25 AC (11,088 SF)

PERVIOUS : 6,792 SF

C = 0.51

IMPERVIOUS : 4,296 SF

C = 0.95

$$C = \frac{(6792)(0.51) + (4296)(0.95)}{11088} = \underline{0.68}$$

NRCS Soil Report

Soil Map—Saline County, Arkansas



MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Saline County, Arkansas

Survey Area Data: Version 21, Sep 10, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.


Date(s) aerial images were photographed: May 1, 2022—May 29, 2022


The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.


Map Unit Legend


Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
29	Tiak silt loam, 3 to 8 percent slopes	2.4	100.0%
Totals for Area of Interest		2.4	100.0%


Site Drainage Basin Maps




PROJECT # 025-029		No.		Revisions		Date	
Scale: 1" = 20'		Date: 09/05/2025					
Sheet: 1 of 3							
PREPARED FOR: JON MARTIN 5501 LOMBARD ROAD ALEXANDER, AR 72002				PRE-DEVELOPMENT DRAINAGE BASIN MAP SHOPPES AT DOGWOOD SPRINGS RETAIL DEVELOPMENT BRYANT PARKWAY BRYANT, ARKANSAS			
 RICHARDSON ENGINEERING Planning • Engineering • Development Consulting							
325 W. SOUTH STREET, BENTON, AR 72015 (501)315-7225							



PROJECT # 025-029		Revisions		Date	
Scale: 1" = 20'	Date: 09/05/2025				
Sheet: 2 of 3					
Prepared For: JON MARTIN 5501 LOMBARD ROAD ALEXANDER, AR 72002					
POST-DEVELOPMENT DRAINAGE BASIN MAP SHOPPES AT DOGWOOD SPRINGS RETAIL DEVELOPMENT BRYANT PARKWAY BRYANT, ARKANSAS					
RICHARDSON ENGINEERING Planning • Engineering • Development Consulting 325 W. SOUTH STREET, BENTON, AR 72015 (501)315-7225 					



PROJECT # 025-029		No.		Revisions		Date	
Scale: 1" = 20'		Date: 09/05/2025					
Sheet: 3 of 3							
Prepared For: JON MARTIN 5501 LOMBARD ROAD ALEXANDER, AR 72002				POST-DEVELOPMENT DRAINAGE BASIN MAP SHOPPES AT DOGWOOD SPRINGS RETAIL DEVELOPMENT BRYANT PARKWAY BRYANT, ARKANSAS			
 RICHARDSON ENGINEERING Planning • Engineering • Development Consulting 325 W. SOUTH STREET, BENTON, AR 72015 (501)315-7225							

Storm System Design (SSA)

2 Year Design Storm

Project Description

File Name Bryant Pharmacy Drainage Analysis 9-5-25.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method User-Defined
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On Sep 05, 2025 00:00:00
End Analysis On Sep 06, 2025 00:00:00
Start Reporting On Sep 05, 2025 00:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	4
<i>Storage Nodes</i>	0
Links.....	5
<i>Channels</i>	0
<i>Pipes</i>	5
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	0
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 2 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.51	0.49	0.17	2.02	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.51	0.49	0.17	2.09	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.51	0.49	0.08	0.91	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.51	0.49	0.15	1.77	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	418.00					6.67	418.53	

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600	0.000	0.0150	0.07	0.00	0.00	0.00	0.00
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	84.31	422.00	418.00	4.7400	18.000	0.0120	6.67	24.79	0.27	11.93	0.53
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500	18.000	0.0120	2.65	28.90	0.09	10.23	0.31
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700	18.000	0.0120	1.69	19.60	0.09	9.23	0.30
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100	18.000	0.0120	1.99	21.31	0.09	8.25	0.31

Inlet Summary

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation	Max (Rim) Elevation	Initial Water Elevation	Ponded Area	Peak Flow	Peak Flow Intercepted	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Allowable Spread	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow
				(ft)	(ft)	(ft)	(ft²)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	2.02	N/A	N/A	N/A	10.00	8.74	432.16
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	2.09	N/A	N/A	N/A	10.00	5.00	432.01
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	0.98	N/A	N/A	N/A	10.00	3.01	432.59
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	1.77	1.72	0.06	96.77	10.00	6.06	433.28

Subbasin Hydrology

Subbasin : Sub-AD-4

Subbasin : Sub-CB-1

Subbasin : Sub-CB-2

Subbasin : Sub-CB-3

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Man Rougl
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy	0.000	0.000	0
2	SL - (14)	84.31	422.00	0.00	418.00	0.00	4.00	4.7400	CIRCULAR	18.000	18.000	0
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR	18.000	18.000	0
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR	18.000	18.000	0
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR	18.000	18.000	0

No. of
Barrels
$$\begin{array}{c} 1 \\ 1 \\ 1 \\ 1 \\ 1 \end{array}$$

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Tota Surc
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (16)	0.07	0 00:05	0.00	0.00	0.00		0.00	0.00	
2 SL - (14)	6.67	0 00:05	24.79	0.27	11.93	0.12	0.53	0.35	
3 SL - (15)	2.65	0 00:05	28.90	0.09	10.23	0.10	0.31	0.20	
4 SL - (16)	1.69	0 00:05	19.60	0.09	9.23	0.18	0.30	0.20	
5 SL - (18)	1.99	0 00:05	21.31	0.09	8.25	0.26	0.31	0.21	

Inlet Input

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50	0.1312	10.00
2	CB-1	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3	CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4	CB-3	0.0200	0.0300	0.0150	0.0200	1.50	0.1312	10.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	1 Max Occu
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days t
1	AD-4	2.02	2.02	N/A	N/A	N/A	8.74	432.16	0.36	(
2	CB-1	2.09	2.09	N/A	N/A	N/A	5.00	432.01	0.40	(
3	CB-2	0.98	0.91	N/A	N/A	N/A	3.01	432.59	0.34	(
4	CB-3	1.77	1.77	1.72	0.06	96.77	6.06	433.28	0.17	(

10 Year Design Storm

Project Description

File Name Bryant Pharmacy Drainage Analysis 9-5-25.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method User-Defined
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On Sep 05, 2025 00:00:00
End Analysis On Sep 06, 2025 00:00:00
Start Reporting On Sep 05, 2025 00:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	4
<i>Storage Nodes</i>	0
Links.....	5
<i>Channels</i>	0
<i>Pipes</i>	5
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	0
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 10 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.68	0.65	0.22	2.70	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.68	0.65	0.23	2.80	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.68	0.65	0.10	1.22	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.68	0.65	0.20	2.37	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	418.00					8.93	418.62	

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600	0.000	0.0150	0.24	0.00	0.00	0.00	0.00
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	84.31	422.00	418.00	4.7400	18.000	0.0120	8.93	24.79	0.36	12.91	0.62
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500	18.000	0.0120	3.54	28.90	0.12	11.11	0.35
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700	18.000	0.0120	2.12	19.60	0.11	9.87	0.33
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100	18.000	0.0120	2.66	21.31	0.12	8.42	0.36

Inlet Summary

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation	Max (Rim) Elevation	Initial Water Elevation	Ponded Area	Peak Flow	Peak Flow Intercepted	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Allowable Spread	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow
				(ft)	(ft)	(ft)	(ft²)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	2.70	N/A	N/A	N/A	10.00	10.40	432.21
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	2.80	N/A	N/A	N/A	10.00	6.07	432.04
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	1.46	N/A	N/A	N/A	10.00	3.92	432.62
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.37	2.14	0.23	90.23	10.00	6.73	433.30

Subbasin Hydrology

Subbasin : Sub-AD-4

Subbasin : Sub-CB-1

Subbasin : Sub-CB-2

Subbasin : Sub-CB-3

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Man Rougl
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy	0.000	0.000	0
2	SL - (14)	84.31	422.00	0.00	418.00	0.00	4.00	4.7400	CIRCULAR	18.000	18.000	0
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR	18.000	18.000	0
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR	18.000	18.000	0
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR	18.000	18.000	0

No. of
Barrels
$$\begin{array}{c} 1 \\ 1 \\ 1 \\ 1 \\ 1 \end{array}$$

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Tota Surc
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (16)	0.24	0 00:05	0.00	0.00	0.00		0.00	0.00	
2 SL - (14)	8.93	0 00:05	24.79	0.36	12.91	0.11	0.62	0.41	
3 SL - (15)	3.54	0 00:05	28.90	0.12	11.11	0.09	0.35	0.24	
4 SL - (16)	2.12	0 00:05	19.60	0.11	9.87	0.17	0.33	0.22	
5 SL - (18)	2.66	0 00:05	21.31	0.12	8.42	0.25	0.36	0.24	

Inlet Input

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50	0.1312	10.00
2	CB-1	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3	CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4	CB-3	0.0200	0.0300	0.0150	0.0200	1.50	0.1312	10.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	1 Max Occu
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days t
1	AD-4	2.70	2.70	N/A	N/A	N/A	10.40	432.21	0.41	(
2	CB-1	2.80	2.80	N/A	N/A	N/A	6.07	432.04	0.43	(
3	CB-2	1.46	1.22	N/A	N/A	N/A	3.92	432.62	0.37	(
4	CB-3	2.37	2.37	2.14	0.23	90.23	6.73	433.30	0.19	(

25 Year Design Storm

Project Description

File Name Bryant Pharmacy Drainage Analysis 9-5-25.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method User-Defined
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On Sep 05, 2025 00:00:00
End Analysis On Sep 06, 2025 00:00:00
Start Reporting On Sep 05, 2025 00:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	4
<i>Storage Nodes</i>	0
Links.....	5
<i>Channels</i>	0
<i>Pipes</i>	5
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	0
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 25 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.79	0.75	0.26	3.10	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.79	0.75	0.27	3.22	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.79	0.75	0.12	1.40	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.79	0.75	0.23	2.72	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	418.00					10.27	418.67	

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600	0.000	0.0150	0.37	0.00	0.00	0.00	0.00
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	84.31	422.00	418.00	4.7400	18.000	0.0120	10.27	24.79	0.41	13.40	0.67
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500	18.000	0.0120	4.07	28.90	0.14	11.57	0.38
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700	18.000	0.0120	2.34	19.60	0.12	10.19	0.35
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100	18.000	0.0120	3.06	21.31	0.14	8.63	0.38

Inlet Summary

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation	Max (Rim) Elevation	Initial Water Elevation	Ponded Area	Peak Flow	Peak Flow Intercepted	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Allowable Spread	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow
				(ft)	(ft)	(ft)	(ft²)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.10	N/A	N/A	N/A	10.00	11.31	432.24
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.22	N/A	N/A	N/A	10.00	6.66	432.06
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	1.77	N/A	N/A	N/A	10.00	4.47	432.64
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.72	2.36	0.37	86.54	10.00	7.08	433.31

Subbasin Hydrology

Subbasin : Sub-AD-4

Subbasin : Sub-CB-1

Subbasin : Sub-CB-2

Subbasin : Sub-CB-3

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Man Rougl
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy	0.000	0.000	0
2	SL - (14)	84.31	422.00	0.00	418.00	0.00	4.00	4.7400	CIRCULAR	18.000	18.000	0
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR	18.000	18.000	0
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR	18.000	18.000	0
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR	18.000	18.000	0

No. of
Barrels
$$\begin{array}{c} 1 \\ 1 \\ 1 \\ 1 \\ 1 \end{array}$$

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Surcharge
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (16)	0.37	0 00:05	0.00	0.00	0.00		0.00	0.00	
2 SL - (14)	10.27	0 00:05	24.79	0.41	13.40	0.10	0.67	0.45	
3 SL - (15)	4.07	0 00:05	28.90	0.14	11.57	0.09	0.38	0.25	
4 SL - (16)	2.34	0 00:05	19.60	0.12	10.19	0.17	0.35	0.23	
5 SL - (18)	3.06	0 00:05	21.31	0.14	8.63	0.25	0.38	0.26	

Inlet Input

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50	0.1312	10.00
2	CB-1	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3	CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4	CB-3	0.0200	0.0300	0.0150	0.0200	1.50	0.1312	10.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	1 Max Occu
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days t
1	AD-4	3.10	3.10	N/A	N/A	N/A	11.31	432.24	0.44	(
2	CB-1	3.22	3.22	N/A	N/A	N/A	6.66	432.06	0.45	(
3	CB-2	1.77	1.40	N/A	N/A	N/A	4.47	432.64	0.38	(
4	CB-3	2.72	2.72	2.36	0.37	86.54	7.08	433.31	0.20	(

50 Year Design Storm

Project Description

File Name Bryant Pharmacy Drainage Analysis 9-5-25.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method User-Defined
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On Sep 05, 2025 00:00:00
End Analysis On Sep 06, 2025 00:00:00
Start Reporting On Sep 05, 2025 00:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	4
<i>Storage Nodes</i>	0
Links.....	5
<i>Channels</i>	0
<i>Pipes</i>	5
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	0
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 50 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.86	0.82	0.28	3.38	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.86	0.82	0.29	3.51	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.86	0.82	0.13	1.53	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.86	0.82	0.25	2.98	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	418.00					11.22	418.71	

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600	0.000	0.0150	0.47	0.00	0.00	0.00	0.00
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	84.31	422.00	418.00	4.7400	18.000	0.0120	11.22	24.79	0.45	13.71	0.71
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500	18.000	0.0120	4.45	28.90	0.15	11.88	0.40
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700	18.000	0.0120	2.48	19.60	0.13	10.41	0.36
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100	18.000	0.0120	3.34	21.31	0.16	8.85	0.40

Inlet Summary

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation	Max (Rim) Elevation	Initial Water Elevation	Ponded Area	Peak Flow	Peak Flow Intercepted	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Allowable Spread	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow
				(ft)	(ft)	(ft)	(ft²)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.38	N/A	N/A	N/A	10.00	11.93	432.26
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.51	N/A	N/A	N/A	10.00	7.06	432.07
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	2.01	N/A	N/A	N/A	10.00	4.86	432.65
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.98	2.50	0.47	84.09	10.00	7.31	433.31

Subbasin Hydrology

Subbasin : Sub-AD-4

Subbasin : Sub-CB-1

Subbasin : Sub-CB-2

Subbasin : Sub-CB-3

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Man Rougl
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy	0.000	0.000	0
2	SL - (14)	84.31	422.00	0.00	418.00	0.00	4.00	4.7400	CIRCULAR	18.000	18.000	0
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR	18.000	18.000	0
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR	18.000	18.000	0
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR	18.000	18.000	0

No. of
Barrels
$$\begin{array}{r} \hline 1 \\ 1 \\ 1 \\ 1 \\ 1 \end{array}$$

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Totl Surcl
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (16)	0.47	0 00:05	0.00	0.00	0.00		0.00	0.00	
2 SL - (14)	11.22	0 00:05	24.79	0.45	13.71	0.10	0.71	0.47	
3 SL - (15)	4.45	0 00:05	28.90	0.15	11.88	0.09	0.40	0.27	
4 SL - (16)	2.48	0 00:05	19.60	0.13	10.41	0.16	0.36	0.24	
5 SL - (18)	3.34	0 00:05	21.31	0.16	8.85	0.24	0.40	0.27	

Inlet Input

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50	0.1312	10.00
2	CB-1	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3	CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4	CB-3	0.0200	0.0300	0.0150	0.0200	1.50	0.1312	10.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	1 Max Occu
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days t
1	AD-4	3.38	3.38	N/A	N/A	N/A	11.93	432.26	0.46	(
2	CB-1	3.51	3.51	N/A	N/A	N/A	7.06	432.07	0.46	(
3	CB-2	2.01	1.53	N/A	N/A	N/A	4.86	432.65	0.40	(
4	CB-3	2.98	2.98	2.50	0.47	84.09	7.31	433.31	0.20	(

100 Year Design Storm

Project Description

File Name Bryant Pharmacy Drainage Analysis 9-5-25.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method Rational
Time of Concentration (TOC) Method User-Defined
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods NO

Analysis Options

Start Analysis On Sep 05, 2025 00:00:00
End Analysis On Sep 06, 2025 00:00:00
Start Reporting On Sep 05, 2025 00:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:05:00 days hh:mm:ss
Routing Time Step 30 seconds

Number of Elements

	Qty
Rain Gages	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	4
<i>Storage Nodes</i>	0
Links.....	5
<i>Channels</i>	0
<i>Pipes</i>	5
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	0
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

Return Period..... 100 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.93	0.89	0.31	3.68	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.93	0.89	0.32	3.82	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.93	0.89	0.14	1.67	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.93	0.89	0.27	3.24	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	418.00					12.20	418.74	

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600	0.000	0.0150	0.60	0.00	0.00	0.00	0.00
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	84.31	422.00	418.00	4.7400	18.000	0.0120	12.20	24.79	0.49	14.00	0.74
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500	18.000	0.0120	4.84	28.90	0.17	12.16	0.41
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700	18.000	0.0120	2.62	19.60	0.13	10.61	0.37
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100	18.000	0.0120	3.64	21.31	0.17	9.06	0.42

Inlet Summary

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation	Max (Rim) Elevation	Initial Water Elevation	Ponded Area	Peak Flow	Peak Flow Intercepted	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Allowable Spread	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow
				(ft)	(ft)	(ft)	(ft²)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.68	N/A	N/A	N/A	10.00	12.56	432.28
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.82	N/A	N/A	N/A	10.00	7.47	432.08
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	2.26	N/A	N/A	N/A	10.00	5.26	432.66
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	3.24	2.64	0.59	81.70	10.00	7.54	433.32

Subbasin Hydrology

Subbasin : Sub-AD-4

Subbasin : Sub-CB-1

Subbasin : Sub-CB-2

Subbasin : Sub-CB-3

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Man Rougl
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy	0.000	0.000	0
2	SL - (14)	84.31	422.00	0.00	418.00	0.00	4.00	4.7400	CIRCULAR	18.000	18.000	0
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR	18.000	18.000	0
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR	18.000	18.000	0
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR	18.000	18.000	0

No. of
Barrels
$$\begin{array}{c} \hline 1 \\ 1 \\ 1 \\ 1 \\ 1 \end{array}$$

Pipe Results

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Tot Surc
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (16)	0.60	0 00:05	0.00	0.00	0.00		0.00	0.00	
2 SL - (14)	12.20	0 00:05	24.79	0.49	14.00	0.10	0.74	0.50	
3 SL - (15)	4.84	0 00:05	28.90	0.17	12.16	0.09	0.41	0.28	
4 SL - (16)	2.62	0 00:05	19.60	0.13	10.61	0.16	0.37	0.25	
5 SL - (18)	3.64	0 00:05	21.31	0.17	9.06	0.24	0.42	0.28	

Inlet Input

SN	Element ID	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50	0.1312	10.00
2	CB-1	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3	CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4	CB-3	0.0200	0.0300	0.0150	0.0200	1.50	0.1312	10.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	1 Max Occu
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days t
1	AD-4	3.68	3.68	N/A	N/A	N/A	12.56	432.28	0.48	(
2	CB-1	3.82	3.82	N/A	N/A	N/A	7.47	432.08	0.47	(
3	CB-2	2.26	1.67	N/A	N/A	N/A	5.26	432.66	0.41	(
4	CB-3	3.24	3.24	2.64	0.59	81.70	7.54	433.32	0.21	(

Pre and Post Development Hydrographs (Hydrology Studio)

Table of Contents

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

Basin Model Schematic	1
Hydrograph by Return Period	2
2 - Year	
Hydrograph Summary	3
Hydrograph Reports	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	4
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	5
Hydrograph No. 3, Junction, Total Pre-Dev	6
Hydrograph No. 4, Mod Rational, Post-Dev Basin A	7
Hydrograph No. 5, Pond Route, Detention Basin	8
Detention Pond Reports - Bryant Pharmacy Detention Pond	9
Hydrograph No. 6, Rational, Post-Dev Basin B	13
Hydrograph No. 7, Rational, Post-Dev Basin "C"	14
Hydrograph No. 8, Junction, Total Post-Dev	15
10 - Year	
Hydrograph Summary	16
Hydrograph Reports	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	17
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	18
Hydrograph No. 3, Junction, Total Pre-Dev	19
Hydrograph No. 4, Mod Rational, Post-Dev Basin A	20
Hydrograph No. 5, Pond Route, Detention Basin	21
Hydrograph No. 6, Rational, Post-Dev Basin B	22
Hydrograph No. 7, Rational, Post-Dev Basin "C"	23
Hydrograph No. 8, Junction, Total Post-Dev	24
25 - Year	
Hydrograph Summary	25
Hydrograph Reports	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	26
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	27
Hydrograph No. 3, Junction, Total Pre-Dev	28
Hydrograph No. 4, Mod Rational, Post-Dev Basin A	29
Hydrograph No. 5, Pond Route, Detention Basin	30
Hydrograph No. 6, Rational, Post-Dev Basin B	31
Hydrograph No. 7, Rational, Post-Dev Basin "C"	32
Hydrograph No. 8, Junction, Total Post-Dev	33

Contents continued...

50 - Year

Hydrograph Summary	34
Hydrograph Reports	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	35
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	36
Hydrograph No. 3, Junction, Total Pre-Dev	37
Hydrograph No. 4, Mod Rational, Post-Dev Basin A	38
Hydrograph No. 5, Pond Route, Detention Basin	39
Hydrograph No. 6, Rational, Post-Dev Basin B	40
Hydrograph No. 7, Rational, Post-Dev Basin "C"	41
Hydrograph No. 8, Junction, Total Post-Dev	42

100 - Year


Hydrograph Summary	43
Hydrograph Reports	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	44
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	45
Hydrograph No. 3, Junction, Total Pre-Dev	46
Hydrograph No. 4, Mod Rational, Post-Dev Basin A	47
Hydrograph No. 5, Pond Route, Detention Basin	48
Hydrograph No. 6, Rational, Post-Dev Basin B	49
Hydrograph No. 7, Rational, Post-Dev Basin "C"	50
Hydrograph No. 8, Junction, Total Post-Dev	51

Basin Model

Hydrology Studio v 3.0.0.27

Project Name: Bryant Pharmacy

09-05-2025



Hydrograph by Return Period

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

[illegible]

Hydrograph 2-yr Summary

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27


09-05-2025

[illegible]

Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 3.084 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,223 cuft
Drainage Area	= 1.17 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.71 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Pre-Dev Basin "B"

Hyd. No. 2


Hydrograph Type	= Rational	Peak Flow	= 1.736 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 1,668 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.13 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Pre-Dev

Hyd. No. 3

Hydrograph Type	= Junction	Peak Flow	= 4.385 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Hydrograph Volume	= 3,886 cuft
Inflow Hydrographs	= 1, 2	Total Contrib. Area	= 1.92 ac



Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Post-Dev Basin A

Hyd. No. 4


Hydrograph Type	= Mod Rational	Peak Flow	= 3.206 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 8,946 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 2.25 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 9.3 x Tc
Target Q	= 3.080 cfs	Required Storage	= 4,233 cuft



Detention Basin

Hyd. No. 5

Hydrograph Type	= Pond Route	Peak Flow	= 3.206 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.63 hrs
Time Interval	= 1 min	Hydrograph Volume	= 8,847 cuft
Inflow Hydrograph	= 4 - Post-Dev Basin A	Max. Elevation	= 418.73 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 558 cuft



Pond Report


Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

Bryant Pharmacy Detention Pond

Stage-Storage


[illegible]

Bryant Pharmacy Detention Pond

Stage-Discharge

Culvert / Orifices	Culvert	Orifices			Perforated Riser
		1	2	3	
Rise, in	15				Hole Diameter, in
Span, in	15				No. holes
No. Barrels	1				Invert Elevation, ft
Invert Elevation, ft	417.80				Height, ft
Orifice Coefficient, Co	0.60				Orifice Coefficient, Co
Length, ft	30				
Barrel Slope, %	1.32				
N-Value, n	0.012				
Weirs	Riser*	Weirs			Ancillary
		1	2	3	
Shape / Type	Circular	Broad Crested			Exfiltration, in/hr
Crest Elevation, ft		424			
Crest Length, ft		6			
Angle, deg		45 (1:1)			
Weir Coefficient, Cw		3.3			

*Routes through Culvert.



Pond Report

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

Bryant Pharmacy Detention Pond


Stage-Storage-Discharge Summary

Stage (ft)	Elev. (ft)	Storage (cuft)	Culvert (cfs)	Orifices, cfs			Riser (cfs)	Weirs, cfs			Pf Riser (cfs)	Exfil (cfs)	User (cfs)	Total (cfs)
				1	2	3		1	2	3				
0.00	417.80	0.000	0.000					0.000						0.000
0.20	418.00	55.2	0.193 ic					0.000						0.193
1.20	419.00	746	4.324 oc					0.000						4.324
2.20	420.00	1,740	7.415 ic					0.000						7.415
3.20	421.00	3,075	9.481 ic					0.000						9.481
4.20	422.00	4,791	11.17 ic					0.000						11.17
5.20	423.00	6,927	12.64 ic					0.000						12.64
6.20	424.00	9,523	13.95 ic					0.000						13.95
7.20	425.00	12,635	15.15 ic					22.44						37.59

Suffix key: ic = inlet control, oc = outlet control, s = submerged weir

Bryant Pharmacy Detention Pond


Pond Drawdown



Post-Dev Basin B

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.573 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 459 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.49 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Post-Dev Basin "C"

Hyd. No. 7


Hydrograph Type	= Rational	Peak Flow	= 0.532 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 213 cuft
Drainage Area	= 0.17 ac	Runoff Coeff.	= 0.51
Tc Method	= TR55	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.14 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Post-Dev

Hyd. No. 8

Hydrograph Type	= Junction	Peak Flow	= 3.810 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Hydrograph Volume	= 9,501 cuft
Inflow Hydrographs	= 5, 6, 7	Total Contrib. Area	= 0.39 ac



Hydrograph 10-yr Summary

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

[illegible]

Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Pre-Dev Basin "A"

Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 4.131 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,978 cuft
Drainage Area	= 1.17 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Pre-Dev Basin "B"


Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 2.327 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 2,236 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 5.54 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Pre-Dev


Hyd. No. 3



Post-Dev Basin A

Hyd. No. 4

Hydrograph Type	= Mod Rational	Peak Flow	= 4.316 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 12,041 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 3.03 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 9.3 x Tc
Target Q	= 4.130 cfs	Required Storage	= 5,722 cuft




Detention Basin

Hyd. No. 5

Hydrograph Type	= Pond Route	Peak Flow	= 4.316 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.77 hrs
Time Interval	= 1 min	Hydrograph Volume	= 11,909 cuft
Inflow Hydrograph	= 4 - Post-Dev Basin A	Max. Elevation	= 419.00 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 743 cuft

Pond Routing by Storage Indication Method


Center of mass detention time = 3 min



Post-Dev Basin B

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.767 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 615 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.01 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Post-Dev Basin "C"

Hyd. No. 7


Hydrograph Type	= Rational	Peak Flow	= 0.712 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 285 cuft
Drainage Area	= 0.17 ac	Runoff Coeff.	= 0.51
Tc Method	= TR55	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.21 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Post-Dev

Hyd. No. 8

Hydrograph Type	= Junction	Peak Flow	= 5.127 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Hydrograph Volume	= 12,785 cuft
Inflow Hydrographs	= 5, 6, 7	Total Contrib. Area	= 0.39 ac



Hydrograph 25-yr Summary

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

[illegible]

Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 4.746 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 3,421 cuft
Drainage Area	= 1.17 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.24 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Pre-Dev Basin "B"


Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 2.674 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 2,570 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.37 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Pre-Dev


Hyd. No. 3



Post-Dev Basin A

Hyd. No. 4


Hydrograph Type	= Mod Rational	Peak Flow	= 4.964 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 13,849 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 3.48 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 9.3 x Tc
Target Q	= 4.750 cfs	Required Storage	= 6,582 cuft



Detention Basin

Hyd. No. 5


Hydrograph Type	= Pond Route	Peak Flow	= 4.964 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.77 hrs
Time Interval	= 1 min	Hydrograph Volume	= 13,698 cuft
Inflow Hydrograph	= 4 - Post-Dev Basin A	Max. Elevation	= 419.19 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 930 cuft



Post-Dev Basin B

Hyd. No. 6


Hydrograph Type	= Rational	Peak Flow	= 0.882 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 706 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.91 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Post-Dev Basin "C"

Hyd. No. 7


Hydrograph Type	= Rational	Peak Flow	= 0.818 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 327 cuft
Drainage Area	= 0.17 ac	Runoff Coeff.	= 0.51
Tc Method	= TR55	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 9.43 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Post-Dev

Hyd. No. 8

Hydrograph Type	= Junction	Peak Flow	= 5.623 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Hydrograph Volume	= 14,704 cuft
Inflow Hydrographs	= 5, 6, 7	Total Contrib. Area	= 0.39 ac



Hydrograph 50-yr Summary

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27


09-05-2025

[illegible]

Pre-Dev Basin "A"

Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 5.188 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 3,740 cuft
Drainage Area	= 1.17 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.92 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Pre-Dev Basin "B"


Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 2.924 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 2,810 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.96 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Pre-Dev


Hyd. No. 3



Post-Dev Basin A

Hyd. No. 4

Hydrograph Type	= Mod Rational	Peak Flow	= 5.437 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 15,170 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 3.82 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 9.3 x Tc
Target Q	= 5.190 cfs	Required Storage	= 7,230 cuft




Detention Basin

Hyd. No. 5

Hydrograph Type	= Pond Route	Peak Flow	= 5.437 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.77 hrs
Time Interval	= 1 min	Hydrograph Volume	= 15,005 cuft
Inflow Hydrograph	= 4 - Post-Dev Basin A	Max. Elevation	= 419.29 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 1,035 cuft

Pond Routing by Storage Indication Method


Center of mass detention time = 3 min



Post-Dev Basin B

Hyd. No. 6


Hydrograph Type	= Rational	Peak Flow	= 0.964 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 772 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.55 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Post-Dev Basin "C"

Hyd. No. 7


Hydrograph Type	= Rational	Peak Flow	= 0.893 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 358 cuft
Drainage Area	= 0.17 ac	Runoff Coeff.	= 0.51
Tc Method	= TR55	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 10.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Post-Dev

Hyd. No. 8

Hydrograph Type	= Junction	Peak Flow	= 6.097 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Hydrograph Volume	= 16,105 cuft
Inflow Hydrographs	= 5, 6, 7	Total Contrib. Area	= 0.39 ac



Hydrograph 100-yr Summary

Project Name: Bryant Pharmacy

Hydrology Studio v 3.0.0.27

09-05-2025

[illegible]

Hydrograph Report

Project Name: Bryant Pharmacy


Hydrology Studio v 3.0.0.27

09-05-2025

Pre-Dev Basin "A"

Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 5.636 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 4,063 cuft
Drainage Area	= 1.17 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.60 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Pre-Dev Basin "B"


Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 3.175 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 3,052 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.56 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Pre-Dev


Hyd. No. 3



Post-Dev Basin A

Hyd. No. 4

Hydrograph Type	= Mod Rational	Peak Flow	= 5.893 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 16,440 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.14 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 9.3 x Tc
Target Q	= 5.640 cfs	Required Storage	= 7,811 cuft




Detention Basin

Hyd. No. 5

Hydrograph Type	= Pond Route	Peak Flow	= 5.892 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.77 hrs
Time Interval	= 1 min	Hydrograph Volume	= 16,261 cuft
Inflow Hydrograph	= 4 - Post-Dev Basin A	Max. Elevation	= 419.42 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 1,163 cuft

Pond Routing by Storage Indication Method


Center of mass detention time = 3 min



Post-Dev Basin B

Hyd. No. 6


Hydrograph Type	= Rational	Peak Flow	= 1.047 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 839 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Post-Dev Basin "C"

Hyd. No. 7

Hydrograph Type	= Rational	Peak Flow	= 0.971 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 389 cuft
Drainage Area	= 0.17 ac	Runoff Coeff.	= 0.51
Tc Method	= TR55	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 11.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



Total Post-Dev

Hyd. No. 8

Hydrograph Type	= Junction	Peak Flow	= 6.620 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Hydrograph Volume	= 17,456 cuft
Inflow Hydrographs	= 5, 6, 7	Total Contrib. Area	= 0.39 ac

