

**Drainage Report**  
**For**  
**Bryant Pharmacy**  
**Bryant, Saline County, Arkansas**



**November 7, 2025**

**Prepared by:**

**RICHARDSON ENGINEERING, PLLC**

**325 W. South St.  
Benton, AR 72015  
501-315-7225**

## TABLE OF CONTENTS

Title	Page Number
Project Owner Information	3
Project Location and Description	3
Site Drainage	4
Runoff Summary's	5
<i>Pre- Development Drainage Basin Information</i>	5
<i>Overall Site Post- Development Drainage Basin Information</i>	6
<i>On-Site Drainage Inlet Basin Information</i>	6
<i>Site Discharge to the West</i>	7
<i>Site Discharge to the East</i>	7
<i>Site Discharge to the South</i>	8
Recommendations/Summary	8
Appendices:	9
<i>Runoff Coefficient Calculation</i>	10
<i>NRCS Soil Report</i>	11
<i>Site Drainage Basin Maps</i>	12
<i>Trickle Channel Velocity Calculation</i>	13
<i>Overflow Wier Blockage Calculation</i>	14
<i>SSA Design Layout</i>	15
<i>Storm System Design (SSA)</i>	16
<i>2 Year Design Storm</i>	17
<i>10 Year Design Storm</i>	18
<i>25 Year Design Storm</i>	19
<i>50 Year Design Storm</i>	20
<i>100 Year Design Storm</i>	21
<i>Pre and Post Development Hydrographs (Hydrology Studio)</i>	22

Jon Martin  
5501 Lombard Road  
Alexander, AR 72002

The project is located on West side of the Bryant Parkway, part of the Southeast Quarter of the Northwest Quarter, Section 14, Township 1-S, Range 14-W, Saline County, Arkansas.



3

## **Site Drainage**

### *Pre-Development*

The pre-developed runoff for the site flows to the East, West, and South. The on-site drainage basins have been broken down into five separate basins that discharge water off-site. Drainage Basins A and B discharge water to the West, Basin C discharges water to the South, and Basins D and E discharge water to the East. The pre-development drainage basin delineation can be found in the appendix of this report.

The pre-development runoff condition is undeveloped/woods.

### *Post-Development*

The site drainage starts on the South side of the project and flows to the North. The drainage is sheet flows across the proposed parking lot and intercepted by the proposed storm sewer system and is discharged into a proposed detention basin on the Northwest corner of the project. There are also some small areas that discharge to the East and South from the site.

The City of Bryant Drainage Manual utilized different C values for each storm event. The C value for the 100-year design storm was utilized for all storm events for the drainage analysis for this site.

The time of concentration values for the storm inlets on this site were manually inputted into the Storm and Sanitary Analysis program to be 5 minutes. The drainage basins for CB-1, CB-2, CB-3 and AD-4 primarily consist of impervious areas. Drainage basins in this case typically produce time of concentration values that are less than 5 minutes. Per the City of Bryant Drainage manual, the minimum time of concentration value is 5 minutes; therefore, a time of concentration value of 5 minutes was utilized to analyze the on-site storm system.

The minimum required volume of the detention basin was found by comparing the pre-development rational method hydrograph for the area that the detention pond is being discharged, to the post-development modified rational method hydrograph for the area that the detention basin is receiving using the Hydrology Studio program. The minimum required volume was found to be 4,974 CF for the 100-year storm event. In order to meet the City of Bryant's Stormwater Manual detention requirements, the detention pond has to be sized with at least a 25% factor of safety; therefore, the minimum size of the detention pond is 6,218 CF.

The proposed detention basin will utilize an orifice/riser/culvert discharge structure. Post-Development Basin "A" is the drainage basin that discharges water into the proposed detention basin. Post-development drainage basin "A" consists of all of the individual drainage basins for CB-1, CB-2, CB-3, AD-4, the proposed building areas for phase 2 (i.e. roof drains), and the detention pond area. Post-Development Basin B, C, and D



consist of the grass tie back slopes from the proposed pavement to existing grade and a small portion of the entrance drives that tie down to the existing grade on the Bryant Parkway. These areas are not routed through the detention basin, so they were calculated by themselves. The detention basin and post-development basin “B” will be discharged to the West, post-development basin “C” will be discharged to the East, and post-development basin “D” will be discharged to the South. A delineation for the drainage basins that were used in Hydrology Studio (for the overall site drainage basins), as well as a delineation of the basins that were used in Storm and Sanitary Analysis (on-site storm inlets) can be seen in the appendix of this report.

The post-development runoff conditions changed from undeveloped/woods to commercial development.

### **Runoff Summary's**

#### *Pre- Development Drainage Basin Information*

Overall Site Area: 1.92 Acres

Drainage Basins	Drainage Area (Ac)	C Value	Time of Concentration (min)
Basin A	0.86	0.56	9
Basin B	0.31	0.56	7
Basin C	0.20	0.56	16
Basin D	0.34	0.56	12
Basin E	0.21	0.56	10

Design Storm	Basin A (cfs)	Basin B (cfs)	Basin C (cfs)	Basin D (cfs)	Basin E (cfs)
2-yr	2.27	2.21	0.41	0.79	0.53
10-yr	3.04	2.96	0.55	1.06	0.71
25-yr	3.49	3.41	0.63	1.21	0.81
50-yr	3.81	3.72	0.69	1.33	0.89
100-yr	4.14	4.04	0.74	1.44	0.97

Overall Post-Development Drainage Study Area: 1.97 Acres

*Overall Site Post- Development Drainage Basin Information*

Drainage Basins	Drainage Area (Ac)	C Value	Time of Concentration (min)
Basin A	1.50	0.95	5
Basin B	0.22	0.58	10
Basin C	0.237	0.68	5
Basin D	0.017	0.75	5

Design Storm	Basin A (cfs)	Basin B (cfs)	Basin C (cfs)	Basin D (cfs)
2-yr	8.75	0.57	0.99	0.08
10-yr	11.70	0.77	1.32	0.11
25-yr	13.44	0.88	1.52	0.12
50-yr	14.68	0.96	1.66	0.13
100-yr	15.96	1.05	1.81	0.14

*On-Site Drainage Inlet Basin Information*

Drainage Basins	Drainage Area (Ac)	C Value	Time of Concentration (min)
CB-1	0.36	0.95	5
CB-2	0.16	0.95	5
CB-3	0.30	0.95	5
AD-4	0.35	0.95	5

Design Storm	CB-1 (cfs)	CB-2 (cfs)	CB-3 (cfs)	AD-4 (cfs)
2-yr	2.09	0.91	1.77	2.02
10-yr	2.80	1.22	2.37	2.70
25-yr	3.22	1.40	2.72	3.10
50-yr	3.51	1.53	2.98	3.83
100-yr	3.82	1.67	3.24	3.68

*Site Discharge to the West to Include Detention Basin*

Overall Development Area = 1.92 Ac  
Pre-Development Drainage Study Area = 1.17  
Post-Development Drainage Study Area = 1.72  
Existing Condition runoff Coefficient: C = 0.56  
Proposed runoff Coefficient: C = 0.95/0.58  
Tc Undeveloped = 9/7 Minutes (TR55 Method)  
Tc Developed = 5/10 Minutes (TR55 Method)  
Detention Basin Required Volume: 6,218 CF  
Detention Basin Volume: 9,802 CF  
Maximum Storage: 3,842 CF  
Discharge Structure: Orifice/Riser/Culvert

Design Storm	Pre-Development Flow Rate (cfs)	Post- Development Flow Rate (cfs)	Post- Development w/ Detention Flow Rate (cfs)	Maximum Water Elevation in Pond (ft)
2-yr	4.08	9.04	4.00	420.71
10-yr	5.46	12.08	5.03	421.46
25-yr	6.28	13.88	5.52	421.94
50-yr	6.86	15.16	5.87	422.24
100-yr	7.45	16.48	6.15	422.55

*Site Discharge to the East*

Pre-Development Drainage Study Area = 0.55  
Post-Development Drainage Study Area = 0.237  
Existing Condition runoff Coefficient: C = 0.56  
Proposed runoff Coefficient: C = 0.68  
Tc Undeveloped = 12/10 Minutes (TR55 Method)  
Tc Developed = 5 Minutes (TR55 Method)

Design Storm	Pre-Development Flow Rate (cfs)	Post- Development Flow Rate (cfs)
2-yr	1.25	0.99
10-yr	1.67	1.32
25-yr	1.92	1.52
50-yr	2.10	1.66
100-yr	2.28	1.81

*Site Discharge to the South*

Pre-Development Drainage Study Area = 0.20

Post-Development Drainage Study Area = 0.017

Existing Condition runoff Coefficient:  $C = 0.56$

Proposed runoff Coefficient:  $C = 0.75$

Tc Undeveloped = 16 Minutes (TR55 Method)

Tc Developed = 5 Minutes (TR55 Method)

Design Storm	Pre-Development Flow Rate (cfs)	Post- Development Flow Rate (cfs)
2-yr	0.41	0.078
10-yr	0.55	0.11
25-yr	0.63	0.12
50-yr	0.69	0.13
100-yr	0.74	0.14

**Recommendations/Summary**

The proposed drainage improvements include a storm sewer system and a detention basin on the Northwest corner of the project. The proposed detention basin releases the post development runoff at a lower rate than the pre-development condition.

# Appendices

Runoff Coefficient Calculations  
NRCS Soil Report  
Site Drainage Map  
Trickle Channel Velocity Calculation  
Overflow Wier Blockage Calculation  
SSA Design Layout  
Storm System Design  
Pond and Post Development Hydrographs (Hydrology Studio)

# **Runoff Coefficient Calculations**



# RICHARDSON ENGINEERING

Planning • Engineering • Development Consulting

325 West South Street  
Benton, AR 72015  
(501) 315-7225

(1/1)

PROJECT 02S-029 DRAINAGE ANALYSIS

DATE 09/04/2025

PRE-DEVELOPMENT

DRAINAGE AREA : 1.92 AC

CLAY SOIL

50% - 2%-7% C = 0.50

50% - > 7% C = 0.62

$$C = \frac{(0.960)(0.5) + (0.960)(0.62)}{1.92}$$

$$= 0.56$$



PROJECT 025-029 DRAINAGE ANALYSIS

DATE 11/05/2025

## POST-DEVELOPMENT

### BASIN "A"

AREA = 1.5 ACRE

C = 0.95

### BASIN "B"

AREA = 0.22 ACRE (9661 SF)

PERVIOUS: 8092 SF C = 0.51 (GRASS - GOOD CONDITION)  
IMPERVIOUS: 1569 SF C = 0.95 > 7%

$$C = \frac{(8092)(0.51) + (1569)(0.95)}{9661} = \underline{0.58}$$

### BASIN "C"

AREA = 0.237 AC (10348 SF)

PERVIOUS: 6452 SF C = 0.51

IMPERVIOUS: 3896 SF C = 0.95

$$C = \frac{(6452)(0.51) + (3896)(0.95)}{10348} = \underline{0.68}$$

### BASIN "D"

AREA = 0.017 ACRE (722 SF)

PERVIOUS: C = 0.51

IMPERVIOUS: C = 0.95

$$C = \frac{(322)(0.51) + (400)(0.95)}{722} = \underline{0.75}$$



# **NRCS Soil Report**

Soil Map—Saline County, Arkansas




## MAP LEGEND

### Area of Interest (AOI)

 Area of Interest (AOI)

### Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

### Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

### Water Features



Streams and Canals

### Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

### Background



Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Saline County, Arkansas

Survey Area Data: Version 21, Sep 10, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 1, 2022—May 29, 2022



The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
29	Tiak silt loam, 3 to 8 percent slopes	2.4	100.0%
<b>Totals for Area of Interest</b>		<b>2.4</b>	<b>100.0%</b>

# **Site Drainage Basin Maps**







PROJECT # 025-029		No.		Revisions		Date	
Scale: 1" = 20'		Date: 11/07/2025					
Sheet: 1 of 3							
PRE-DEVELOPMENT DRAINAGE BASIN MAP SHOPPES AT DOGWOOD SPRINGS RETAIL DEVELOPMENT BRYANT PARKWAY BRYANT, ARKANSAS				Prepared For: JON MARTIN 5501 LOMBARD ROAD ALEXANDER, AR 72002			
 <b>RICHARDSON ENGINEERING</b> Planning • Engineering • Development Consulting							
				325 W. SOUTH STREET, BENTON, AR 72015 (501)315-7225			




PEAK FLOW FROM  
SITE TO WEST  
Q25 = 5.52 CFS  
Q100 = 6.15 CFS



No.	Revisions	Date

PROJECT # 025-029	DATE: 11/07/2025	Sheet: 2 of 3
Scale: 1" = 20'		







# **Trickle Channel Velocity Calculation**



# RICHARDSON ENGINEERING


Planning • Engineering • Development Consulting

325 West South Street  
Benton, AR 72015  
(501) 315-7225

(1/1)

PROJECT 025-029 TRUCK CHANNEL VELOCITY

DATE 11/05/2025



$$A = 0.045 \text{ FT}^2$$

$$S = \frac{0.2}{10} = 0.02 \text{ FT/FT}$$


$$W_p = 0.16 \text{ FT}$$

$$Q = \left( \frac{1.49}{0.013} \right) (0.045) \left( \frac{0.045}{0.16} \right)^{2/3} (0.02)^{1/2}$$
$$= 0.313 \text{ CFS}$$

$$V = \frac{Q}{A} = \frac{0.313}{0.045} = 6.95 \text{ FT/S} > 2 \text{ FT/S} \checkmark$$

# **Overflow Wier Blockage Calculation**






(1/1)

PROJECT 02S-029 OVER FLOW RISER WEIR CALCULATION DATE 11/05/2025

RISER IS 4' I.D. ROUND BARREL



$$Q = C L H^{3/2}$$

$$C = 2.6$$

$$L = 2\pi R = (2)(\pi)(2) = 12.56'$$

$$H = 1.0'$$

$$Q = (2.6)(12.56)(1.0)^{3/2} = 32.65 \text{ CFS}$$

∴ ASSUMING THAT 50% OF THE WEIR IS BLOCKED


$$Q = \frac{32.65}{2} = 16.33 \text{ CFS} > Q_{100} \text{ WITH ROAD} = 15.96 \text{ CFS} \checkmark$$

# **SSA Design Layout**



PROJECT 025-029 SSA DESIGN LAYOUT

DATE 11/05/2025



# **Storm System Design (SSA)**

## **2 Year Design Storm**



Project Description

File Name ..... Bryant Pharmacy Drainage Analysis 11-7-25.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... Rational  
Time of Concentration (TOC) Method ..... User-Defined  
Link Routing Method ..... Kinematic Wave  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

	Qty
Rain Gages .....	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i> .....	0
<i>Outfalls</i> .....	1
<i>Flow Diversions</i> .....	0
<i>Inlets</i> .....	4
<i>Storage Nodes</i> .....	0
Links.....	5
<i>Channels</i> .....	0
<i>Pipes</i> .....	5
<i>Pumps</i> .....	0
<i>Orifices</i> .....	0
<i>Weirs</i> .....	0
<i>Outlets</i> .....	0
Pollutants .....	0
Land Uses .....	0

Rainfall Details

Return Period ..... 2 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.51	0.49	0.17	2.02	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.51	0.49	0.17	2.09	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.51	0.49	0.08	0.91	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.51	0.49	0.15	1.77	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation  (ft)	Ground/Rim (Max) Elevation (ft)	Initial Water Elevation (ft)	Surcharge Elevation (ft)	Ponded Area (ft²)	Peak Inflow (cfs)	Max HGL Elevation Attained (ft)	Max Surcharge Depth Attained (ft)	Min Freeboard Attained (ft)
1	Out-1SL - (14)	Outfall	419.00					6.66	419.58		

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/ Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Total Depth Ratio	To
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600			0.07	0.00	0.00	0.00	0.00	0.00	
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	85.23	422.00	419.00	3.5200			6.66	21.35	0.31	10.71	0.58	0.38	
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500			2.65	28.90	0.09	10.23	0.31	0.20	
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700			1.69	19.60	0.09	9.23	0.30	0.20	
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100			1.99	21.31	0.09	8.25	0.31	0.21	

Inlet Summary

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
	ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
				Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
				(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	2.02	N/A	N/A	N/A	10.00	8.74	432.16
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	2.09	N/A	N/A	N/A	10.00	5.00	432.01
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	0.98	N/A	N/A	N/A	10.00	3.01	432.59
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	1.77	1.72	0.06	96.75	10.00	6.07	433.28

Subbasin Hydrology

Subbasin : Sub-AD-4

Input Data

Area (ac) ..... 0.35  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-1**

**Input Data**

Area (ac) ..... 0.36  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-2**

**Input Data**

Area (ac) ..... 0.16  
Weighted Runoff Coefficient ..... 0.95



**Subbasin : Sub-CB-3**

**Input Data**

Area (ac) ..... 0.3  
Weighted Runoff Coefficient ..... 0.95

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entr Lc
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)		
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy				
2	SL - (14)	85.23	422.00	0.00	419.00	0.00	3.00	3.5200	CIRCULAR				
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR				
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR				
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR				

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Froude Number
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)
1	L-SL - (16)	0.07	0 00:05	0.00	0.00	0.00		0.00	0.00	0.00
2	SL - (14)	6.66	0 00:05	21.35	0.31	10.71	0.13	0.58	0.38	0.00
3	SL - (15)	2.65	0 00:05	28.90	0.09	10.23	0.10	0.31	0.20	0.00
4	SL - (16)	1.69	0 00:05	19.60	0.09	9.23	0.18	0.30	0.20	0.00
5	SL - (18)	1.99	0 00:05	21.31	0.09	8.25	0.26	0.31	0.21	0.00

Inlet Input

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
ID		Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
				(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)	(%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50		

Inlet Results

SN	Element	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet (cfs)	Peak Flow Bypassing Inlet (cfs)	Inlet Efficiency during Peak Flow (%)	Max Gutter Spread during Peak Flow (ft)	Max Gutter Water Elev. during Peak Flow (ft)	Max Gutter Water Depth during Peak Flow (ft)	Time of Max Depth Occurrence (days hh:mm)	T Flood Volume (ac)
1	AD-4	2.02	2.02	N/A	N/A	N/A	8.74	432.16	0.36	0 00:05	0
2	CB-1	2.09	2.09	N/A	N/A	N/A	5.00	432.01	0.40	0 00:05	0
3	CB-2	0.98	0.91	N/A	N/A	N/A	3.01	432.59	0.34	0 00:05	0
4	CB-3	1.77	1.77	1.72	0.06	96.75	6.07	433.28	0.17	0 00:05	0

# **10 Year Design Storm**

Project Description

File Name ..... Bryant Pharmacy Drainage Analysis 11-7-25.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... Rational  
Time of Concentration (TOC) Method ..... User-Defined  
Link Routing Method ..... Kinematic Wave  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

	Qty
Rain Gages .....	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i> .....	0
<i>Outfalls</i> .....	1
<i>Flow Diversions</i> .....	0
<i>Inlets</i> .....	4
<i>Storage Nodes</i> .....	0
Links.....	5
<i>Channels</i> .....	0
<i>Pipes</i> .....	5
<i>Pumps</i> .....	0
<i>Orifices</i> .....	0
<i>Weirs</i> .....	0
<i>Outlets</i> .....	0
Pollutants .....	0
Land Uses .....	0

Rainfall Details

Return Period ..... 10 year(s)



Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.68	0.65	0.22	2.70	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.68	0.65	0.23	2.80	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.68	0.65	0.10	1.22	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.68	0.65	0.20	2.37	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation  (ft)	Ground/Rim (Max) Elevation (ft)	Initial Water Elevation (ft)	Surcharge Elevation (ft)	Ponded Area (ft²)	Peak Inflow (cfs)	Max HGL Elevation Attained (ft)	Max Surcharge Depth Attained (ft)	Min Freeboard Attained (ft)
1	Out-1SL - (14)	Outfall	419.00					8.93	419.68		

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/ Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Total Depth/ Ratio	To
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600			0.24	0.00	0.00	0.00	0.00	0.00	
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	85.23	422.00	419.00	3.5200			8.93	21.35	0.42	11.58	0.68	0.45	
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500			3.54	28.90	0.12	11.11	0.35	0.24	
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700			2.12	19.60	0.11	9.87	0.33	0.22	
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100			2.66	21.31	0.12	8.42	0.36	0.24	

Inlet Summary

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
	ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
				Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
				(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	2.70	N/A	N/A	N/A	10.00	10.40	432.21
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	2.80	N/A	N/A	N/A	10.00	6.07	432.04
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	1.46	N/A	N/A	N/A	10.00	3.92	432.62
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.37	2.14	0.23	90.25	10.00	6.72	433.30

Subbasin Hydrology

Subbasin : Sub-AD-4

Input Data

Area (ac) ..... 0.35  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-1**

**Input Data**

Area (ac) ..... 0.36  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-2**

**Input Data**

Area (ac) ..... 0.16  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-3**

**Input Data**

Area (ac) ..... 0.3  
Weighted Runoff Coefficient ..... 0.95



Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entr Lc
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)		
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy				
2	SL - (14)	85.23	422.00	0.00	419.00	0.00	3.00	3.5200	CIRCULAR				
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR				
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR				
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR				

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Froude Number
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)	
1	L-SL - (16)	0.24	0 00:05	0.00	0.00	0.00		0.00	0.00	0.00	
2	SL - (14)	8.93	0 00:05	21.35	0.42	11.58	0.12	0.68	0.45	0.00	
3	SL - (15)	3.54	0 00:05	28.90	0.12	11.11	0.09	0.35	0.24	0.00	
4	SL - (16)	2.12	0 00:05	19.60	0.11	9.87	0.17	0.33	0.22	0.00	
5	SL - (18)	2.66	0 00:05	21.31	0.12	8.42	0.25	0.36	0.24	0.00	

Inlet Input

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging	
			Elevation			Elevation	Depth			Factor
			(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)		(%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50		

Inlet Results

SN	Element	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet (cfs)	Peak Flow Bypassing Inlet (cfs)	Inlet Efficiency during Peak Flow (%)	Max Gutter Spread during Peak Flow (ft)	Max Gutter Water Elev. during Peak Flow (ft)	Max Gutter Water Depth during Peak Flow (ft)	Time of Max Depth Occurrence (days hh:mm)	T Flood Volume (ac)
1	AD-4	2.70	2.70	N/A	N/A	N/A	10.40	432.21	0.41	0 00:05	0
2	CB-1	2.80	2.80	N/A	N/A	N/A	6.07	432.04	0.43	0 00:05	0
3	CB-2	1.46	1.22	N/A	N/A	N/A	3.92	432.62	0.37	0 00:05	0
4	CB-3	2.37	2.37	2.14	0.23	90.25	6.72	433.30	0.19	0 00:05	0

# **25 Year Design Storm**

Project Description

File Name ..... Bryant Pharmacy Drainage Analysis 11-7-25.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... Rational  
Time of Concentration (TOC) Method ..... User-Defined  
Link Routing Method ..... Kinematic Wave  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

	Qty
Rain Gages .....	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i> .....	0
<i>Outfalls</i> .....	1
<i>Flow Diversions</i> .....	0
<i>Inlets</i> .....	4
<i>Storage Nodes</i> .....	0
Links.....	5
<i>Channels</i> .....	0
<i>Pipes</i> .....	5
<i>Pumps</i> .....	0
<i>Orifices</i> .....	0
<i>Weirs</i> .....	0
<i>Outlets</i> .....	0
Pollutants .....	0
Land Uses .....	0

Rainfall Details

Return Period ..... 25 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.79	0.75	0.26	3.10	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.79	0.75	0.27	3.22	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.79	0.75	0.12	1.40	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.79	0.75	0.23	2.72	0 00:05:00



Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	419.00					10.24	419.73		

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/ Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Depth/ Total Depth Ratio	T Su
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600			0.37	0.00	0.00	0.00	0.00	0.00	
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	85.23	422.00	419.00	3.5200			10.24	21.35	0.48	11.99	0.73	0.49	
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500			4.07	28.90	0.14	11.57	0.38	0.25	
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700			2.34	19.60	0.12	10.19	0.35	0.23	
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100			3.06	21.31	0.14	8.63	0.38	0.26	

Inlet Summary

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
	ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
				Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
				(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.10	N/A	N/A	N/A	10.00	11.31	432.24
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.22	N/A	N/A	N/A	10.00	6.66	432.06
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	1.77	N/A	N/A	N/A	10.00	4.47	432.64
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.72	2.36	0.37	86.54	10.00	7.08	433.31

Subbasin Hydrology

Subbasin : Sub-AD-4

Input Data

Area (ac) ..... 0.35  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-1**

**Input Data**

Area (ac) ..... 0.36  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-2**

**Input Data**

Area (ac) ..... 0.16  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-3**

**Input Data**

Area (ac) ..... 0.3  
Weighted Runoff Coefficient ..... 0.95

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entr Lc
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)		
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy				
2	SL - (14)	85.23	422.00	0.00	419.00	0.00	3.00	3.5200	CIRCULAR				
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR				
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR				
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR				



Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Fro Num
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)	
1	L-SL - (16)	0.37	0 00:05	0.00	0.00	0.00		0.00	0.00	0.00	
2	SL - (14)	10.24	0 00:05	21.35	0.48	11.99	0.12	0.73	0.49	0.00	
3	SL - (15)	4.07	0 00:05	28.90	0.14	11.57	0.09	0.38	0.25	0.00	
4	SL - (16)	2.34	0 00:05	19.60	0.12	10.19	0.17	0.35	0.23	0.00	
5	SL - (18)	3.06	0 00:05	21.31	0.14	8.63	0.25	0.38	0.26	0.00	

Inlet Input

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging	
			Elevation			Elevation	Depth			Factor
			(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)		(%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50		

Inlet Results

SN	Element	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet (cfs)	Peak Flow Bypassing Inlet (cfs)	Inlet Efficiency during Peak Flow (%)	Max Gutter Spread during Peak Flow (ft)	Max Gutter Water Elev. during Peak Flow (ft)	Max Gutter Water Depth during Peak Flow (ft)	Time of Max Depth Occurrence (days hh:mm)	T Flood Volume (ac)
1	AD-4	3.10	3.10	N/A	N/A	N/A	11.31	432.24	0.44	0 00:05	C
2	CB-1	3.22	3.22	N/A	N/A	N/A	6.66	432.06	0.45	0 00:05	C
3	CB-2	1.77	1.40	N/A	N/A	N/A	4.47	432.64	0.38	0 00:05	C
4	CB-3	2.72	2.72	2.36	0.37	86.54	7.08	433.31	0.20	0 00:05	C

# **50 Year Design Storm**

Project Description

File Name ..... Bryant Pharmacy Drainage Analysis 11-7-25.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... Rational  
Time of Concentration (TOC) Method ..... User-Defined  
Link Routing Method ..... Kinematic Wave  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

	Qty
Rain Gages .....	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i> .....	0
<i>Outfalls</i> .....	1
<i>Flow Diversions</i> .....	0
<i>Inlets</i> .....	4
<i>Storage Nodes</i> .....	0
Links.....	5
<i>Channels</i> .....	0
<i>Pipes</i> .....	5
<i>Pumps</i> .....	0
<i>Orifices</i> .....	0
<i>Weirs</i> .....	0
<i>Outlets</i> .....	0
Pollutants .....	0
Land Uses .....	0

Rainfall Details

Return Period ..... 50 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.86	0.82	0.28	3.38	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.86	0.82	0.29	3.51	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.86	0.82	0.13	1.53	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.86	0.82	0.25	2.98	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation  (ft)	Ground/Rim (Max) Elevation (ft)	Initial Water Elevation (ft)	Surcharge Elevation (ft)	Ponded Area (ft²)	Peak Inflow (cfs)	Max HGL Elevation Attained (ft)	Max Surcharge Depth Attained (ft)	Min Freeboard Attained (ft)
1	Out-1SL - (14)	Outfall	419.00					11.21	419.77		



Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/ Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Depth/ Total Depth Ratio	T Su
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600			0.47	0.00	0.00	0.00	0.00	0.00	
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	85.23	422.00	419.00	3.5200			11.21	21.35	0.53	12.26	0.77	0.51	
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500			4.45	28.90	0.15	11.88	0.40	0.27	
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700			2.48	19.60	0.13	10.41	0.36	0.24	
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100			3.34	21.31	0.16	8.85	0.40	0.27	

Inlet Summary

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
	ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
				Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
				(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.38	N/A	N/A	N/A	10.00	11.93	432.26
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.51	N/A	N/A	N/A	10.00	7.06	432.07
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	2.01	N/A	N/A	N/A	10.00	4.86	432.65
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	2.98	2.50	0.47	84.09	10.00	7.31	433.31

Subbasin Hydrology

Subbasin : Sub-AD-4

Input Data

Area (ac) ..... 0.35  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-1**

**Input Data**

Area (ac) ..... 0.36  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-2**

**Input Data**

Area (ac) ..... 0.16  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-3**

**Input Data**

Area (ac) ..... 0.3  
Weighted Runoff Coefficient ..... 0.95

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entr Lc
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)		
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy				
2	SL - (14)	85.23	422.00	0.00	419.00	0.00	3.00	3.5200	CIRCULAR				
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR				
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR				
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR				

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Fro Num
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)	
1	L-SL - (16)	0.47	0 00:05	0.00	0.00	0.00		0.00	0.00	0.00	
2	SL - (14)	11.21	0 00:05	21.35	0.53	12.26	0.12	0.77	0.51	0.00	
3	SL - (15)	4.45	0 00:05	28.90	0.15	11.88	0.09	0.40	0.27	0.00	
4	SL - (16)	2.48	0 00:05	19.60	0.13	10.41	0.16	0.36	0.24	0.00	
5	SL - (18)	3.34	0 00:05	21.31	0.16	8.85	0.24	0.40	0.27	0.00	



Inlet Input

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging	
			Elevation			Elevation	Depth			Factor
			(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)		(%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50		

Inlet Results

SN	Element	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet (cfs)	Peak Flow Bypassing Inlet (cfs)	Inlet Efficiency during Peak Flow (%)	Max Gutter Spread during Peak Flow (ft)	Max Gutter Water Elev. during Peak Flow (ft)	Max Gutter Water Depth during Peak Flow (ft)	Time of Max Depth Occurrence (days hh:mm)	T Flood Volume (ac)
1	AD-4	3.38	3.38	N/A	N/A	N/A	11.93	432.26	0.46	0 00:05	0
2	CB-1	3.51	3.51	N/A	N/A	N/A	7.06	432.07	0.46	0 00:05	0
3	CB-2	2.01	1.53	N/A	N/A	N/A	4.86	432.65	0.40	0 00:05	0
4	CB-3	2.98	2.98	2.50	0.47	84.09	7.31	433.31	0.20	0 00:05	0

# **100 Year Design Storm**

Project Description

File Name ..... Bryant Pharmacy Drainage Analysis 11-7-25.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... Rational  
Time of Concentration (TOC) Method ..... User-Defined  
Link Routing Method ..... Kinematic Wave  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

	Qty
Rain Gages .....	0
Subbasins.....	4
Nodes.....	5
<i>Junctions</i> .....	0
<i>Outfalls</i> .....	1
<i>Flow Diversions</i> .....	0
<i>Inlets</i> .....	4
<i>Storage Nodes</i> .....	0
Links.....	5
<i>Channels</i> .....	0
<i>Pipes</i> .....	5
<i>Pumps</i> .....	0
<i>Orifices</i> .....	0
<i>Weirs</i> .....	0
<i>Outlets</i> .....	0
Pollutants .....	0
Land Uses .....	0

Rainfall Details

Return Period ..... 100 year(s)

Subbasin Summary

SN	Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-AD-4	0.35	0.9500	0.93	0.89	0.31	3.68	0 00:05:00
2	Sub-CB-1	0.36	0.9500	0.93	0.89	0.32	3.82	0 00:05:00
3	Sub-CB-2	0.16	0.9500	0.93	0.89	0.14	1.67	0 00:05:00
4	Sub-CB-3	0.30	0.9500	0.93	0.89	0.27	3.24	0 00:05:00

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)
1	Out-1SL - (14)	Outfall	419.00					12.19	419.81		

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length (ft)	Inlet Invert Elevation (ft)	Outlet Invert Elevation (ft)	Average Slope (%)	Diameter or Height (in)	Manning's Roughness	Peak Flow (cfs)	Design Flow Capacity (cfs)	Peak Flow/ Design Flow Ratio	Peak Flow Velocity (ft/sec)	Peak Flow Depth (ft)	Peak Flow Depth/ Total Depth Ratio	T Su
1	L-SL - (16)	Pipe	CB-3	CB-2	112.54	433.11	432.25	0.7600			0.60	0.00	0.00	0.00	0.00	0.00	
2	SL - (14)	Pipe	CB-1	Out-1SL - (14)	85.23	422.00	419.00	3.5200			12.19	21.35	0.57	12.52	0.81	0.54	
3	SL - (15)	Pipe	CB-2	CB-1	62.02	426.00	422.00	6.4500			4.84	28.90	0.17	12.16	0.41	0.28	
4	SL - (16)	Pipe	CB-3	CB-2	101.17	429.00	426.00	2.9700			2.62	19.60	0.13	10.61	0.37	0.25	
5	SL - (18)	Pipe	AD-4	CB-1	128.37	427.50	423.00	3.5100			3.64	21.31	0.17	9.06	0.42	0.28	



Inlet Summary

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
	ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
				Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
				(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
1	AD-4	On Sag	1	427.50	431.80	427.50	10.00	3.68	N/A	N/A	N/A	10.00	12.56	432.28
2	CB-1	On Sag	1	422.00	431.61	422.00	10.00	3.82	N/A	N/A	N/A	10.00	7.47	432.08
3	CB-2	On Sag	1	426.00	432.25	426.00	10.00	2.26	N/A	N/A	N/A	10.00	5.26	432.66
4	CB-3	On Grade	1	429.00	433.11	429.00	N/A	3.24	2.64	0.59	81.70	10.00	7.54	433.32

Subbasin Hydrology

Subbasin : Sub-AD-4

Input Data

Area (ac) ..... 0.35  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-1**

**Input Data**

Area (ac) ..... 0.36  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-2**

**Input Data**

Area (ac) ..... 0.16  
Weighted Runoff Coefficient ..... 0.95

**Subbasin : Sub-CB-3**

**Input Data**

Area (ac) ..... 0.3  
Weighted Runoff Coefficient ..... 0.95

Pipe Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entr Lc
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)		
1	L-SL - (16)	112.54	433.11	4.11	432.25	6.25	0.86	0.7600	Dummy				
2	SL - (14)	85.23	422.00	0.00	419.00	0.00	3.00	3.5200	CIRCULAR				
3	SL - (15)	62.02	426.00	0.00	422.00	0.00	4.00	6.4500	CIRCULAR				
4	SL - (16)	101.17	429.00	0.00	426.00	0.00	3.00	2.9700	CIRCULAR				
5	SL - (18)	128.37	427.50	0.00	423.00	1.00	4.50	3.5100	CIRCULAR				

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Fro Num
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)	
1	L-SL - (16)	0.60	0 00:05	0.00	0.00	0.00		0.00	0.00	0.00	
2	SL - (14)	12.19	0 00:05	21.35	0.57	12.52	0.11	0.81	0.54	0.00	
3	SL - (15)	4.84	0 00:05	28.90	0.17	12.16	0.09	0.41	0.28	0.00	
4	SL - (16)	2.62	0 00:05	19.60	0.13	10.61	0.16	0.37	0.25	0.00	
5	SL - (18)	3.64	0 00:05	21.31	0.17	9.06	0.24	0.42	0.28	0.00	

Inlet Input

SN	Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
ID		Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
				(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)	(%)
1	AD-4	On Sag	1	427.50	431.80	4.30	427.50	0.00	10.00	0.00
2	CB-1	On Sag	1	422.00	431.61	9.61	422.00	0.00	10.00	0.00
3	CB-2	On Sag	1	426.00	432.25	6.25	426.00	0.00	10.00	0.00
4	CB-3	On Grade	1	429.00	433.11	4.11	429.00	0.00	N/A	0.00



Roadway & Gutter Input

SN	Element	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	AD-4	N/A	0.0300	0.0150	0.0300	1.50		

Inlet Results

SN	Element	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet (cfs)	Peak Flow Bypassing Inlet (cfs)	Inlet Efficiency during Peak Flow (%)	Max Gutter Spread during Peak Flow (ft)	Max Gutter Water Elev. during Peak Flow (ft)	Max Gutter Water Depth during Peak Flow (ft)	Time of Max Depth Occurrence (days hh:mm)	T Flood Volume (ac)
1	AD-4	3.68	3.68	N/A	N/A	N/A	12.56	432.28	0.48	0 00:05	0
2	CB-1	3.82	3.82	N/A	N/A	N/A	7.47	432.08	0.47	0 00:05	0
3	CB-2	2.26	1.67	N/A	N/A	N/A	5.26	432.66	0.41	0 00:05	0
4	CB-3	3.24	3.24	2.64	0.59	81.70	7.54	433.32	0.21	0 00:05	0

## **Pre and Post Development Hydrographs (Hydrology Studio)**



Report



Help

Estimate Storage\* > Create Pond > Add Outlet Structures


Post-dev Hyd = 8 - Mod Rational - Post-Dev Basin A  
Pre-dev Hyd = 3 - Junction - Total Pre-Dev West

Freq (Yr)	Vol Pre (cuft)	Vol Post (cuft)	Qp Post (cfs)	Q Targ (cfs)	Req Stor (cuft)
1					
2	2,828	6,610	4.08	4.08	2,693
3					
5					
10	3,787	8,883	5.48	5.46	3,641
25	4,351	10,214	6.30	6.27	4,194
50	4,755	11,180	6.90	6.86	4,595
100	5,167	12,126	7.49	7.45	4,974

Clear Estimate Storage

Extended Detention Storage (optional)		
Zone	Description	Volume (cuft)
1	WQv	
2	CPv	
3	Custom	
4	Custom	

1-Yr 2-Yr 3-Yr 5-Yr 10-Yr 25-Yr 50-Yr 100-Yr



# Table of Contents

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

<b>Basin Model Schematic</b>	<b>1</b>
<b>Hydrograph by Return Period</b>	<b>2</b>
<b>2 - Year</b>	
<b>Hydrograph Summary</b>	<b>3</b>
<b>Hydrograph Reports</b>	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	4
Tc by TR55 Worksheet	5
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	6
Tc by TR55 Worksheet	7
Hydrograph No. 3, Junction, Total Pre-Dev West	8
Hydrograph No. 4, Rational, Pre-Dev Basin "C"	9
Tc by TR55 Worksheet	10
Hydrograph No. 5, Rational, Pre-Dev Basin "D"	11
Tc by TR55 Worksheet	12
Hydrograph No. 6, Rational, Pre-Dev Basin "E"	13
Tc by TR55 Worksheet	14
Hydrograph No. 7, Junction, Total Pre-Dev East	15
Hydrograph No. 8, Mod Rational, Post-Dev Basin A	16
Hydrograph No. 9, Pond Route, Detention Basin	17
Detention Pond Reports - Bryant Pharmacy Detention Pond	18
Hydrograph No. 10, Rational, Post-Dev Basin B	22
Tc by TR55 Worksheet	23
Hydrograph No. 11, Rational, Post-Dev Basin "C"	24
Tc by TR55 Worksheet	25
Hydrograph No. 12, Junction, Total Post-Dev West	26
Hydrograph No. 13, Rational, Post-Dev Basin "D"	27
Tc by TR55 Worksheet	28
<b>10 - Year</b>	
<b>Hydrograph Summary</b>	<b>29</b>
<b>Hydrograph Reports</b>	
Hydrograph No. 1, Rational, Pre-Dev Basin "A"	30
Hydrograph No. 2, Rational, Pre-Dev Basin "B"	31
Hydrograph No. 3, Junction, Total Pre-Dev West	32
Hydrograph No. 4, Rational, Pre-Dev Basin "C"	33
Hydrograph No. 5, Rational, Pre-Dev Basin "D"	34
Hydrograph No. 6, Rational, Pre-Dev Basin "E"	35

## Contents continued...

---

Hydrograph No. 7, Junction, Total Pre-Dev East .....	36
Hydrograph No. 8, Mod Rational, Post-Dev Basin A .....	37
Hydrograph No. 9, Pond Route, Detention Basin .....	38
Hydrograph No. 10, Rational, Post-Dev Basin B .....	39
Hydrograph No. 11, Rational, Post-Dev Basin "C" .....	40
Hydrograph No. 12, Junction, Total Post-Dev West .....	41
Hydrograph No. 13, Rational, Post-Dev Basin "D" .....	42

### 25 - Year

<b>Hydrograph Summary .....</b>	<b>43</b>
---------------------------------	-----------

#### **Hydrograph Reports**

Hydrograph No. 1, Rational, Pre-Dev Basin "A" .....	44
Hydrograph No. 2, Rational, Pre-Dev Basin "B" .....	45
Hydrograph No. 3, Junction, Total Pre-Dev West .....	46
Hydrograph No. 4, Rational, Pre-Dev Basin "C" .....	47
Hydrograph No. 5, Rational, Pre-Dev Basin "D" .....	48
Hydrograph No. 6, Rational, Pre-Dev Basin "E" .....	49
Hydrograph No. 7, Junction, Total Pre-Dev East .....	50
Hydrograph No. 8, Mod Rational, Post-Dev Basin A .....	51
Hydrograph No. 9, Pond Route, Detention Basin .....	52
Hydrograph No. 10, Rational, Post-Dev Basin B .....	53
Hydrograph No. 11, Rational, Post-Dev Basin "C" .....	54
Hydrograph No. 12, Junction, Total Post-Dev West .....	55
Hydrograph No. 13, Rational, Post-Dev Basin "D" .....	56

### 50 - Year

<b>Hydrograph Summary .....</b>	<b>57</b>
---------------------------------	-----------

#### **Hydrograph Reports**

Hydrograph No. 1, Rational, Pre-Dev Basin "A" .....	58
Hydrograph No. 2, Rational, Pre-Dev Basin "B" .....	59
Hydrograph No. 3, Junction, Total Pre-Dev West .....	60
Hydrograph No. 4, Rational, Pre-Dev Basin "C" .....	61
Hydrograph No. 5, Rational, Pre-Dev Basin "D" .....	62
Hydrograph No. 6, Rational, Pre-Dev Basin "E" .....	63
Hydrograph No. 7, Junction, Total Pre-Dev East .....	64
Hydrograph No. 8, Mod Rational, Post-Dev Basin A .....	65
Hydrograph No. 9, Pond Route, Detention Basin .....	66
Hydrograph No. 10, Rational, Post-Dev Basin B .....	67

# Contents continued...

---

Hydrograph No. 11, Rational, Post-Dev Basin "C" .....	68
Hydrograph No. 12, Junction, Total Post-Dev West .....	69
Hydrograph No. 13, Rational, Post-Dev Basin "D" .....	70

**100 - Year**

<b>Hydrograph Summary</b> .....	<b>71</b>
---------------------------------	-----------


**Hydrograph Reports**

Hydrograph No. 1, Rational, Pre-Dev Basin "A" .....	72
Hydrograph No. 2, Rational, Pre-Dev Basin "B" .....	73
Hydrograph No. 3, Junction, Total Pre-Dev West .....	74
Hydrograph No. 4, Rational, Pre-Dev Basin "C" .....	75
Hydrograph No. 5, Rational, Pre-Dev Basin "D" .....	76
Hydrograph No. 6, Rational, Pre-Dev Basin "E" .....	77
Hydrograph No. 7, Junction, Total Pre-Dev East .....	78
Hydrograph No. 8, Mod Rational, Post-Dev Basin A .....	79
Hydrograph No. 9, Pond Route, Detention Basin .....	80
Hydrograph No. 10, Rational, Post-Dev Basin B .....	81
Hydrograph No. 11, Rational, Post-Dev Basin "C" .....	82
Hydrograph No. 12, Junction, Total Post-Dev West .....	83
Hydrograph No. 13, Rational, Post-Dev Basin "D" .....	84

# Basin Model

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025





# Hydrograph by Return Period

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Outflow (cfs)							
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr
1	Rational	Pre-Dev Basin "A"		2.267			3.036	3.489	3.813	4.143
2	Rational	Pre-Dev Basin "B"		2.215			2.964	3.406	3.721	4.044
3	Junction	Total Pre-Dev West		4.079			5.461	6.275	6.858	7.452
4	Rational	Pre-Dev Basin "C"		0.406			0.545	0.627	0.686	0.744
5	Rational	Pre-Dev Basin "D"		0.787			1.055	1.212	1.325	1.439
6	Rational	Pre-Dev Basin "E"		0.528			0.707	0.813	0.888	0.965
7	Junction	Total Pre-Dev East		1.249			1.673	1.923	2.103	2.284
8	Mod Rational	Post-Dev Basin A		4.080			5.483	6.305	6.901	7.485
9	Pond Route	Detention Basin		3.938			4.978	5.521	5.825	6.052
10	Rational	Post-Dev Basin B		0.573			0.767	0.882	0.964	1.047
11	Rational	Post-Dev Basin "C"		0.990			1.323	1.520	1.660	1.805
12	Junction	Total Post-Dev West		4.000			5.026	5.521	5.867	6.147
13	Rational	Post-Dev Basin "D"		0.078			0.105	0.120	0.131	0.143

# Hydrograph 2-yr Summary

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin "A"	2.267	0.15	1,634	---		
2	Rational	Pre-Dev Basin "B"	2.215	0.12	1,242	---		
3	Junction	Total Pre-Dev West	4.079	0.15	2,828	1, 2		
4	Rational	Pre-Dev Basin "C"	0.406	0.27	521	---		
5	Rational	Pre-Dev Basin "D"	0.787	0.20	756	---		
6	Rational	Pre-Dev Basin "E"	0.528	0.17	423	---		
7	Junction	Total Pre-Dev East	1.249	0.20	1,167	5, 6		
8	Mod Rational	Post-Dev Basin A	4.080	0.08	6,610	---		
9	Pond Route	Detention Basin	3.938	0.45	6,608	8	420.72	1,272
10	Rational	Post-Dev Basin B	0.573	0.17	459	---		
11	Rational	Post-Dev Basin "C"	0.990	0.08	396	---		
12	Junction	Total Post-Dev West	4.000	0.32	7,055	9, 10		
13	Rational	Post-Dev Basin "D"	0.078	0.03	12.5	---		

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 2.267 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 1,634 cuft
Drainage Area	= 0.86 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.71 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Pre-Dev Basin "A" Rational

**Hyd. No. 1**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	100			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	7			
<b>Travel Time (min)</b>	<b>8.85</b>	<b>0.00</b>	<b>0.00</b>	<b>8.85</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)	107			
Watercourse Slope (%)	7.47	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)	4.41			
<b>Travel Time (min)</b>	<b>0.40</b>	<b>0.00</b>	<b>0.00</b>	<b>0.40</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>9 min</b>

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "B"

Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 2.215 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.12 hrs
Time Interval	= 1 min	Runoff Volume	= 1,242 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 7.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 5.27 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Pre-Dev Basin "B" Rational

**Hyd. No. 2**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	100			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	11.75			
<b>Travel Time (min)</b>	<b>7.20</b>	<b>0.00</b>	<b>0.00</b>	<b>7.20</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)	55			
Watercourse Slope (%)	14.25	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)	6.09			
<b>Travel Time (min)</b>	<b>0.15</b>	<b>0.00</b>	<b>0.00</b>	<b>0.15</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>7 min</b>


# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev West

Hyd. No. 3



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "C"

Hyd. No. 4

Hydrograph Type	= Rational	Peak Flow	= 0.406 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.27 hrs
Time Interval	= 1 min	Runoff Volume	= 521 cuft
Drainage Area	= 0.2 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 16.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 3.63 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67





# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Pre-Dev Basin "C" Rational

**Hyd. No. 4**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	68			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	.7			
<b>Travel Time (min)</b>	<b>16.34</b>	<b>0.00</b>	<b>0.00</b>	<b>16.34</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)				
Watercourse Slope (%)	0.00	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>16 min</b>

# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy


File: Detention Calculation 11-7-25.hys

11-07-2025

## Pre-Dev Basin "D"

Hyd. No. 5

Hydrograph Type	= Rational	Peak Flow	= 0.787 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 756 cuft
Drainage Area	= 0.34 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.13 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Pre-Dev Basin "D" Rational

**Hyd. No. 5**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	100			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	3			
<b>Travel Time (min)</b>	<b>12.43</b>	<b>0.00</b>	<b>0.00</b>	<b>12.43</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)	14			
Watercourse Slope (%)	7.00	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)	4.27			
<b>Travel Time (min)</b>	<b>0.05</b>	<b>0.00</b>	<b>0.00</b>	<b>0.05</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>12 min</b>

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "E"

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.528 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 423 cuft
Drainage Area	= 0.21 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.49 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Pre-Dev Basin "E" Rational

**Hyd. No. 6**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	100			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	5			
<b>Travel Time (min)</b>	<b>10.13</b>	<b>0.00</b>	<b>0.00</b>	<b>10.13</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)	16			
Watercourse Slope (%)	8.00	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)	4.56			
<b>Travel Time (min)</b>	<b>0.06</b>	<b>0.00</b>	<b>0.00</b>	<b>0.06</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>10 min</b>

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev East

Hyd. No. 7

Hydrograph Type	= Junction	Peak Flow	= 1.249 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Hydrograph Volume	= 1,167 cuft
Inflow Hydrographs	= 5, 6	Total Contrib. Area	= 0.55 ac



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin A

Hyd. No. 8

Hydrograph Type	= Mod Rational	Peak Flow	= 4.080 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 6,610 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 2.86 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 5.4 x Tc
Target Q	= 0.000 cfs	Required Storage	= 0.000 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Detention Basin

Hyd. No. 9

Hydrograph Type	= Pond Route	Peak Flow	= 3.938 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.45 hrs
Time Interval	= 1 min	Hydrograph Volume	= 6,608 cuft
Inflow Hydrograph	= 8 - Post-Dev Basin A	Max. Elevation	= 420.72 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 1,272 cuft





# Pond Report


Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Bryant Pharmacy Detention Pond

## Stage-Storage

[illegible]

# Pond Report

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025


## Bryant Pharmacy Detention Pond

## Stage-Discharge

Culvert / Orifices	Cir Culvert	Orifice			Orifice Plate
		1 (m)	2	3	
Rise, in	18	15			Orifice Dia, in
Span, in	18	8			No. Orifices
No. Barrels	1	1			Invert Elevation, ft
Invert Elevation, ft	418.80	418.80			Height, ft
Orifice Coefficient, Co	0.60	0.60			Orifice Coefficient, Co
Length, ft	39				
Barrel Slope, %	1				
N-Value, n	0.013				
Weirs	Riser	Weir			Ancillary
		1	2	3	
Shape / Type	Circular				Exfiltration, in/hr
Crest Elevation, ft	423				
Crest Length, ft	12.56				
Angle, deg					
Weir Coefficient, Cw	3.3				

*m = Flows through Culvert, i = Independent*

### Stage-Discharge



# Pond Report

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Bryant Pharmacy Detention Pond


## Stage-Storage-Discharge Summary

[illegible]

*Suffix key: ic = inlet control, oc = outlet control, s = submerged weir*

Bryant Pharmacy Detention Pond

Pond Drawdown



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin B

Hyd. No. 10

Hydrograph Type	= Rational	Peak Flow	= 0.573 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 459 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.49 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Post-Dev Basin B Rational

**Hyd. No. 10**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	100			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	5.17			
<b>Travel Time (min)</b>	<b>10.00</b>	<b>0.00</b>	<b>0.00</b>	<b>10.00</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)	37			
Watercourse Slope (%)	3.29	0.00	0.00	
Surface Description	Unpaved	Paved	Paved	
Average Velocity (ft/s)	2.93			
<b>Travel Time (min)</b>	<b>0.21</b>	<b>0.00</b>	<b>0.00</b>	<b>0.21</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>10 min</b>

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "C"

Hyd. No. 11

Hydrograph Type	= Rational	Peak Flow	= 0.990 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 396 cuft
Drainage Area	= 0.237 ac	Runoff Coeff.	= 0.68
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.14 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Post-Dev Basin "C" Rational

**Hyd. No. 11**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	52			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	8			
<b>Travel Time (min)</b>	<b>4.97</b>	<b>0.00</b>	<b>0.00</b>	<b>4.97</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)				
Watercourse Slope (%)	0.00	0.00	0.00	
Surface Description	Paved	Paved	Paved	
Average Velocity (ft/s)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>5 min</b>



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Post-Dev West

Hyd. No. 12

Hydrograph Type	= Junction	Peak Flow	= 4.000 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.32 hrs
Time Interval	= 1 min	Hydrograph Volume	= 7,055 cuft
Inflow Hydrographs	= 10	Total Contrib. Area	= 0.22 ac



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "D"

Hyd. No. 13

Hydrograph Type	= Rational	Peak Flow	= 0.078 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.03 hrs
Time Interval	= 1 min	Runoff Volume	= 12.5 cuft
Drainage Area	= 0.017 ac	Runoff Coeff.	= 0.75
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 2.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.14 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Tc by TR55 Worksheet

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys

Hydrology Studio v 3.0.0.39

11-07-2025

## Post-Dev Basin "D" Rational

**Hyd. No. 13**

Description	Segments			Tc (min)
	A	B	C	
<b>Sheet Flow</b>				
Description				
Manning's n	0.300	0.013	0.013	
Flow Length (ft)	11			
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28	
Land Slope (%)	2			
<b>Travel Time (min)</b>	<b>2.50</b>	<b>0.00</b>	<b>0.00</b>	<b>2.50</b>
<b>Shallow Concentrated Flow</b>				
Flow Length (ft)				
Watercourse Slope (%)	0.00	0.00	0.00	
Surface Description	Paved	Paved	Paved	
Average Velocity (ft/s)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Channel Flow</b>				
X-sectional Flow Area (sqft)				
Wetted Perimeter (ft)				
Channel Slope (%)				
Manning's n	0.013	0.013	0.013	
Velocity (ft/s)				
Flow Length (ft)				
<b>Travel Time (min)</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
<b>Total Travel Time</b>				<b>2 min</b>

# Hydrograph 10-yr Summary

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin "A"	3.036	0.15	2,189	---		
2	Rational	Pre-Dev Basin "B"	2.964	0.12	1,662	---		
3	Junction	Total Pre-Dev West	5.461	0.15	3,787	1, 2		
4	Rational	Pre-Dev Basin "C"	0.545	0.27	699	---		
5	Rational	Pre-Dev Basin "D"	1.055	0.20	1,014	---		
6	Rational	Pre-Dev Basin "E"	0.707	0.17	566	---		
7	Junction	Total Pre-Dev East	1.673	0.20	1,564	5, 6		
8	Mod Rational	Post-Dev Basin A	5.483	0.08	8,883	---		
9	Pond Route	Detention Basin	4.978	0.45	8,881	8	421.47	2,141
10	Rational	Post-Dev Basin B	0.767	0.17	615	---		
11	Rational	Post-Dev Basin "C"	1.323	0.08	530	---		
12	Junction	Total Post-Dev West	5.026	0.32	9,480	9, 10		
13	Rational	Post-Dev Basin "D"	0.105	0.03	16.8	---		

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 3.036 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,189 cuft
Drainage Area	= 0.86 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "B"

Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 2.964 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.12 hrs
Time Interval	= 1 min	Runoff Volume	= 1,662 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 7.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.06 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev West

Hyd. No. 3



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "C"

Hyd. No. 4

Hydrograph Type	= Rational	Peak Flow	= 0.545 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.27 hrs
Time Interval	= 1 min	Runoff Volume	= 699 cuft
Drainage Area	= 0.2 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 16.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.87 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67





# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "D"

Hyd. No. 5

Hydrograph Type	= Rational	Peak Flow	= 1.055 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 1,014 cuft
Drainage Area	= 0.34 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 5.54 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "E"

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.707 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 566 cuft
Drainage Area	= 0.21 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.01 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev East

Hyd. No. 7



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin A

Hyd. No. 8

Hydrograph Type	= Mod Rational	Peak Flow	= 5.483 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 8,883 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 3.85 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 5.4 x Tc
Target Q	= 0.000 cfs	Required Storage	= 0.000 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Detention Basin

Hyd. No. 9

Hydrograph Type	= Pond Route	Peak Flow	= 4.978 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.45 hrs
Time Interval	= 1 min	Hydrograph Volume	= 8,881 cuft
Inflow Hydrograph	= 8 - Post-Dev Basin A	Max. Elevation	= 421.47 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 2,141 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin B

Hyd. No. 10

Hydrograph Type	= Rational	Peak Flow	= 0.767 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 615 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.01 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "C"

Hyd. No. 11

Hydrograph Type	= Rational	Peak Flow	= 1.323 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 530 cuft
Drainage Area	= 0.237 ac	Runoff Coeff.	= 0.68
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.21 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Post-Dev West

Hyd. No. 12





# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "D"

Hyd. No. 13

Hydrograph Type	= Rational	Peak Flow	= 0.105 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.03 hrs
Time Interval	= 1 min	Runoff Volume	= 16.8 cuft
Drainage Area	= 0.017 ac	Runoff Coeff.	= 0.75
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 2.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.21 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph 25-yr Summary

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin "A"	3.489	0.15	2,515	---		
2	Rational	Pre-Dev Basin "B"	3.406	0.12	1,909	---		
3	Junction	Total Pre-Dev West	6.275	0.15	4,351	1, 2		
4	Rational	Pre-Dev Basin "C"	0.627	0.27	803	---		
5	Rational	Pre-Dev Basin "D"	1.212	0.20	1,165	---		
6	Rational	Pre-Dev Basin "E"	0.813	0.17	651	---		
7	Junction	Total Pre-Dev East	1.923	0.20	1,797	5, 6		
8	Mod Rational	Post-Dev Basin A	6.305	0.08	10,214	---		
9	Pond Route	Detention Basin	5.521	0.47	10,212	8	421.95	2,780
10	Rational	Post-Dev Basin B	0.882	0.17	706	---		
11	Rational	Post-Dev Basin "C"	1.520	0.08	609	---		
12	Junction	Total Post-Dev West	5.521	0.47	10,899	9, 10		
13	Rational	Post-Dev Basin "D"	0.120	0.03	19.3	---		

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 3.489 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,515 cuft
Drainage Area	= 0.86 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.24 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "B"

## Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 3.406 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.12 hrs
Time Interval	= 1 min	Runoff Volume	= 1,909 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 7.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.11 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev West

Hyd. No. 3



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "C"

Hyd. No. 4

Hydrograph Type	= Rational	Peak Flow	= 0.627 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.27 hrs
Time Interval	= 1 min	Runoff Volume	= 803 cuft
Drainage Area	= 0.2 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 16.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 5.60 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "D"

Hyd. No. 5

Hydrograph Type	= Rational	Peak Flow	= 1.212 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 1,165 cuft
Drainage Area	= 0.34 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.37 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "E"

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.813 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 651 cuft
Drainage Area	= 0.21 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.91 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67






# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev East

Hyd. No. 7



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin A

Hyd. No. 8

Hydrograph Type	= Mod Rational	Peak Flow	= 6.305 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 10,214 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.42 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 5.4 x Tc
Target Q	= 0.000 cfs	Required Storage	= 0.000 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Detention Basin

Hyd. No. 9

Hydrograph Type	= Pond Route	Peak Flow	= 5.521 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.47 hrs
Time Interval	= 1 min	Hydrograph Volume	= 10,212 cuft
Inflow Hydrograph	= 8 - Post-Dev Basin A	Max. Elevation	= 421.95 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 2,780 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin B

Hyd. No. 10

Hydrograph Type	= Rational	Peak Flow	= 0.882 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 706 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.91 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "C"

Hyd. No. 11

Hydrograph Type	= Rational	Peak Flow	= 1.520 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 609 cuft
Drainage Area	= 0.237 ac	Runoff Coeff.	= 0.68
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 9.43 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Post-Dev West

Hyd. No. 12

Hydrograph Type	= Junction	Peak Flow	= 5.521 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.47 hrs
Time Interval	= 1 min	Hydrograph Volume	= 10,899 cuft
Inflow Hydrographs	= 10	Total Contrib. Area	= 0.22 ac



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "D"

Hyd. No. 13

Hydrograph Type	= Rational	Peak Flow	= 0.120 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.03 hrs
Time Interval	= 1 min	Runoff Volume	= 19.3 cuft
Drainage Area	= 0.017 ac	Runoff Coeff.	= 0.75
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 2.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 9.43 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph 50-yr Summary

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin "A"	3.813	0.15	2,749	---		
2	Rational	Pre-Dev Basin "B"	3.721	0.12	2,087	---		
3	Junction	Total Pre-Dev West	6.858	0.15	4,755	1, 2		
4	Rational	Pre-Dev Basin "C"	0.686	0.27	879	---		
5	Rational	Pre-Dev Basin "D"	1.325	0.20	1,274	---		
6	Rational	Pre-Dev Basin "E"	0.888	0.17	712	---		
7	Junction	Total Pre-Dev East	2.103	0.20	1,965	5, 6		
8	Mod Rational	Post-Dev Basin A	6.901	0.08	11,180	---		
9	Pond Route	Detention Basin	5.825	0.47	11,178	8	422.25	3,292
10	Rational	Post-Dev Basin B	0.964	0.17	772	---		
11	Rational	Post-Dev Basin "C"	1.660	0.08	665	---		
12	Junction	Total Post-Dev West	5.867	0.35	11,930	9, 10		
13	Rational	Post-Dev Basin "D"	0.131	0.03	21.0	---		



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 3.813 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,749 cuft
Drainage Area	= 0.86 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.92 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "B"

Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 3.721 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.12 hrs
Time Interval	= 1 min	Runoff Volume	= 2,087 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 7.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.86 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev West

Hyd. No. 3



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "C"

Hyd. No. 4

Hydrograph Type	= Rational	Peak Flow	= 0.686 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.27 hrs
Time Interval	= 1 min	Runoff Volume	= 879 cuft
Drainage Area	= 0.2 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 16.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.12 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "D"

Hyd. No. 5

Hydrograph Type	= Rational	Peak Flow	= 1.325 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 1,274 cuft
Drainage Area	= 0.34 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.96 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "E"

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.888 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 712 cuft
Drainage Area	= 0.21 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.55 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev East

Hyd. No. 7



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin A

Hyd. No. 8

Hydrograph Type	= Mod Rational	Peak Flow	= 6.901 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 11,180 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.84 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 5.4 x Tc
Target Q	= 0.000 cfs	Required Storage	= 0.000 cuft





# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Detention Basin

Hyd. No. 9

Hydrograph Type	= Pond Route	Peak Flow	= 5.825 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.47 hrs
Time Interval	= 1 min	Hydrograph Volume	= 11,178 cuft
Inflow Hydrograph	= 8 - Post-Dev Basin A	Max. Elevation	= 422.25 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 3,292 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin B

Hyd. No. 10

Hydrograph Type	= Rational	Peak Flow	= 0.964 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 772 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.55 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "C"

Hyd. No. 11

Hydrograph Type	= Rational	Peak Flow	= 1.660 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 665 cuft
Drainage Area	= 0.237 ac	Runoff Coeff.	= 0.68
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 10.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Post-Dev West

Hyd. No. 12



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "D"

Hyd. No. 13

Hydrograph Type	= Rational	Peak Flow	= 0.131 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.03 hrs
Time Interval	= 1 min	Runoff Volume	= 21.0 cuft
Drainage Area	= 0.017 ac	Runoff Coeff.	= 0.75
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 2.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 10.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph 100-yr Summary

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin "A"	4.143	0.15	2,987	---		
2	Rational	Pre-Dev Basin "B"	4.044	0.12	2,268	---		
3	Junction	Total Pre-Dev West	7.452	0.15	5,167	1, 2		
4	Rational	Pre-Dev Basin "C"	0.744	0.27	954	---		
5	Rational	Pre-Dev Basin "D"	1.439	0.20	1,384	---		
6	Rational	Pre-Dev Basin "E"	0.965	0.17	773	---		
7	Junction	Total Pre-Dev East	2.284	0.20	2,134	5, 6		
8	Mod Rational	Post-Dev Basin A	7.485	0.08	12,126	---		
9	Pond Route	Detention Basin	6.052	0.47	12,124	8	422.55	3,842
10	Rational	Post-Dev Basin B	1.047	0.17	839	---		
11	Rational	Post-Dev Basin "C"	1.805	0.08	723	---		
12	Junction	Total Post-Dev West	6.147	0.30	12,941	9, 10		
13	Rational	Post-Dev Basin "D"	0.143	0.03	22.9	---		

# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "A"

Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 4.143 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.15 hrs
Time Interval	= 1 min	Runoff Volume	= 2,987 cuft
Drainage Area	= 0.86 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 9.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.60 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "B"

Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 4.044 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.12 hrs
Time Interval	= 1 min	Runoff Volume	= 2,268 cuft
Drainage Area	= 0.75 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 7.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 9.63 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67






# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev West

Hyd. No. 3



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Pre-Dev Basin "C"

Hyd. No. 4

Hydrograph Type	= Rational	Peak Flow	= 0.744 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.27 hrs
Time Interval	= 1 min	Runoff Volume	= 954 cuft
Drainage Area	= 0.2 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 16.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.64 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy


File: Detention Calculation 11-7-25.hys

11-07-2025

## Pre-Dev Basin "D"

Hyd. No. 5

Hydrograph Type	= Rational	Peak Flow	= 1.439 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.20 hrs
Time Interval	= 1 min	Runoff Volume	= 1,384 cuft
Drainage Area	= 0.34 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 12.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.56 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67



# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy


File: Detention Calculation 11-7-25.hys

11-07-2025

## Pre-Dev Basin "E"

Hyd. No. 6

Hydrograph Type	= Rational	Peak Flow	= 0.965 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 773 cuft
Drainage Area	= 0.21 ac	Runoff Coeff.	= 0.56
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Pre-Dev East

Hyd. No. 7



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin A

Hyd. No. 8

Hydrograph Type	= Mod Rational	Peak Flow	= 7.485 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 12,126 cuft
Drainage Area	= 1.5 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 5.25 in/hr
Freq. Corr. Factor	= 1.00	Storm Duration	= 5.4 x Tc
Target Q	= 0.000 cfs	Required Storage	= 0.000 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Detention Basin

Hyd. No. 9

Hydrograph Type	= Pond Route	Peak Flow	= 6.052 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.47 hrs
Time Interval	= 1 min	Hydrograph Volume	= 12,124 cuft
Inflow Hydrograph	= 8 - Post-Dev Basin A	Max. Elevation	= 422.55 ft
Pond Name	= Bryant Pharmacy Detention Pond	Max. Storage	= 3,842 cuft



# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin B

Hyd. No. 10

Hydrograph Type	= Rational	Peak Flow	= 1.047 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 839 cuft
Drainage Area	= 0.22 ac	Runoff Coeff.	= 0.58
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67





# Hydrograph Report


Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "C"

Hyd. No. 11

Hydrograph Type	= Rational	Peak Flow	= 1.805 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 723 cuft
Drainage Area	= 0.237 ac	Runoff Coeff.	= 0.68
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 11.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67




# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Total Post-Dev West

Hyd. No. 12



# Hydrograph Report

Hydrology Studio v 3.0.0.39

Project Name: Bryant Pharmacy  
File: Detention Calculation 11-7-25.hys  
11-07-2025

## Post-Dev Basin "D"

Hyd. No. 13

Hydrograph Type	= Rational	Peak Flow	= 0.143 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.03 hrs
Time Interval	= 1 min	Runoff Volume	= 22.9 cuft
Drainage Area	= 0.017 ac	Runoff Coeff.	= 0.75
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 2.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 11.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	= 1/1.67

