

#### **Bryant Planning Commission Meeting**

Boswell Municipal Complex - City Hall Court Room

210 SW 3rd Street

YouTube: <a href="https://www.youtube.com/c/bryantarkansas">https://www.youtube.com/c/bryantarkansas</a>

**Date:** May 12, 2025 - **Time:** 6:00 PM

#### Call to Order

#### **Approval of Minutes**

#### 1. Planning Commission Meeting Minutes 4/14/2025

· 2025-04-14 Planning Commission Minutes.pdf

#### **Announcements**

#### **DRC Report**

2. Collective Church - Marketplace East Subdivision - Lot 4

Richardson Engineering - Requesting Recommendation for Site Plan Approval - Ward 2 - RECOMMENDED APPROVAL, Contingent upon remaining items being met

3. Central Arkansas Truck Outfitters - 25633 I-30 - Alternative Signage Plan

Ace Sign Company - Requesting Recommendation for Approval of Alternative Signage Plan - RECOMMENDED APPROVAL

4. State Farm - 515 N Reynolds Road - Non-standard Building

Richardson Engineering - Requesting Approval for Non-standard Building - RECOMMENDED APPROVAL

5. Fleming Electric - 320 McClanahan Dr - Site Addition

Charlie Best - Requesting Approval for a New Driveway Connection - Ward 3 - APPROVED

- 0954-PLN-01.pdf
- 0954-PLN-02.pdf

#### **6. Serenity Vapes - 6221 Hwy 5 Ste 2 -** Sign Permit

Neonics Sign - Requesting Sign Permit Approval - STAFF APPROVED

• 93580-SGNAPP-01.pdf

#### 7. Sparklight - 3519 Market Place Ave - Sign Permit

Teamwork Inc - Requesting Sign Permit Approval - STAFF APPROVED

• 93652-SGNAPP-01.pdf

#### 8. Coldwell Banker RPM Group - 2531 Market Place Ste 400 - Sign Permit

 $L\ Graphics-Requesting\ Sign\ Permit\ Approval-STAFF\ APPROVED$ 

• 93694-SGNAPP-01.pdf

#### **Old Business**

#### **New Business**

#### 9. Collective Church - Marketplace East Subdivision - Lot 4

Richardson Engineering - Requesting Site Plan Approval - Ward 2

- · 0949-PLN-02.pdf
- 0949-ELV-01.PNG
- 0949-ELV-02.PNG
- 0949-DRN-01.pdf
- · 0949-LTR-01.pdf

#### 10. State Farm - 515 N Reynolds Road - Non-standard Building

Richardson Engineering - Requesting Approval for Non-standard Building

• 0956-PLN-01.pdf

#### 11. Central Arkansas Truck Outfitters - 25633 I-30 - Alternative Signage Plan

 $\ Ace\ Sign\ Company\ -\ Requesting\ Approval\ for\ Alternative\ Signage\ Plan$ 

· 0955-PLN-01.pdf

#### **Adjournments**



#### **Bryant Planning Commission Meeting Minutes**

Monday, April 14, 2025 Boswell Municipal Complex – City Hall Courtroom 6:00 PM

#### **Agenda**

#### **CALL TO ORDER**

- Chairman Lance Penfield calls the meeting to order.
- Commissioners Present: Statton, Hooten, Penfield, Johnson, Thompson, Edwards, Erwin, Speed
- Commissioners Absent: None

#### **APPROVAL OF MINUTES**

- 1. Planning Commission Meeting Minutes 3/10/2025
- 2. Special Planning Commission Meeting Minutes 3/24/2025

Motion to Approve both sets of Minutes made by Commissioner Edwards, Seconded by Commissioner Hooten. Voice Vote, 8 Yays, 0 Nays.

#### **ANNOUNCEMENTS**

Item #7 under New Business has been Removed from the Agenda due to items still needing completion.

Vice-Chairman Hooten read the DRC Report.

#### **DRC REPORT**

#### 3. David's Burgers - 23140 I-30- Site Plan Additions

Ryan Rooney - Requesting Approval for New Site Plan Additions - APPROVED, Contingent upon life safety plan being approved by permitting.

#### 4. Grant Plaza - 5401 Hwy 5, Ste 2-4- Site Addition

BJ Grant - Requesting Approval for Site Addition for Daycare Playground - APPROVED, Contingent upon showing 20ft access esmt from North to the manhole and exit gate on playground.

#### 5. 5095 Hwy 5 - Site Plan Addition- New Driveway

Brian Dale - Requesting Site Plan Approval for New Driveway onto Sunset Meadows Dr - APPROVED, Contingent upon remaining comments being addressed including specifications on driveway.

#### 6. Midland Estates Phase 1- Final Plat

Hope Consulting - Requesting Recommendation for Final Plat Approval - RECOMMENDED APPROVAL, Contingent upon addressing remaining comments, submitting updated plans, and on site items being finished by end of day Friday 4/11.

#### **NEW BUSINESS**


#### 7. Midland Estates Phase 1- Final Plat - ITEM REMOVED FROM AGENDA

Hope Consulting Requesting Final Plat Approval

#### **ADJOURNMENT**

Motion to Adjourn made by Commissioner Edwards, Seconded by Vice-Chairman Hooten. Voice Vote, 8 Yays, 0 nays. Meeting was adjourned.


Chairman, Lance Penfield	Date	
Secretary, Colton Leonard	Date	
(Acting Secretary for This Meeting)		



## Vicinity Map

HURRICANE	HURRICANE VALLEY INC.		Fleming Electric Inc.
Professional Engineering Consultants	ring Consultants		West Entrance Drive
P.O. Box 118 Bryant, Arkansas	501-231-5136		212 McClanahan Bryant, Arkansas
HVI Job No. 16141	SCALE: N.T.S.	Date:	<b>Date:</b> 4-10-25

1/2





## City of Bryant, Arkansas

Community Development 210 SW 3<sup>rd</sup> Street Bryant, AR 72022 501-943-0943

# SIGN PERMIT APPLICATION


Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at www.cityofbryant.com under the Planning and Community Development tab.

Date: 3-16-25	Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.
Sign Co. or Sign Owner	Property Owner
Name ULCONICS Sign. Address 2201 Guster Rol	Name Long Truong Address 7914 Worth Avenue Kast
City, State, Zip <i>1405/cy Ar 72065</i> Phone <i>501-425-9965</i>	City, State, Zip <i>1990000 Nr. 12019</i> Phone 501-860-8526
Email Address NEONICS Sign 2001 Con	Email Address longtoung 24 Quahoo, com
GENERAL INFORMATION	
Name of Business Serenty Vapos	10 COR
Address/Location of sign 622/ / Kury 5	Surte of Sryan 111)
Zoning Classification	

property is required to be submitted. Renderings of the sign(s) showing the correct dimensions is also Please use following page to provide details on the signs requesting approval. Along with information collected at the time of permit issuance. According to the Sign Ordinance a fee for and sign variance or provided on this application, a Site Plan showing placement of sign(s) and any existing sign(s) on the special sign permit request shall be one hundred dollars (\$100). Additional documentation may be required to be submitted with the application. A thirty-five dollar (\$35) per sign payment will be required by Sign Administrator.

## READ CAREFULLY BEFORE SIGNING

authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand , do hereby certify that all information contained within this application is true signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all





## Certificate of Persons Conducting Business Under an Assumed Name


known to me (or satisfactorily executed the same in the capacity subscribed and sworn to before me this l (We) do hereby certify that I am (we are) or intend to operate a business under the following assumed as besignaged I And I (we) certify that the true and full name(s) of the person(s) with an interest in the conduction or transaction of , 2004, before me, the undersigned officer, personally appeared, This certificate being executed in compliance with the provisions of Act 11 of 1943 (A.C.A. 4-70-203 et. Seq.) therein stated and for purposes therein contained. Subscribed and sworn to before me this\_ ACKNOWLEDGEMENT Mailing Address: Mailing Address: Date: Date: business under this name is (are) as follows: ALC A DO , 203M. day of County of Grant Business Address: Name of Business: State of Arkansas Signature \_ Signature On this Name: Name: name:

COMM. #12722237 EXP. FEBRUARY 10, 2033 HEATHER CLARK NOTAR PUBLIC - STATE OF ARKANSAS GRANT COUNTY









#### SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at <a href="https://www.cityofbryant.com">www.cityofbryant.com</a> under the Planning and Community Development tab.

Date: 4/9/2025	Required, Please contact the Community Development Office for more information.
Sign Co. or Sign Owner -Installer	Property Owner
Name_Teamwork, Inc	Name Bryant Realty Company LLC
Address 23 Norfolk Ave	Address 422 N Main St
City, State, Zip South Easton, MA 02375	City, State, Zip Benton, AR 72015
Phone 774-568-5438	Phone
Alternate Phone Adam- applicant 608-407-9084 adam@permit.com GENERAL INFORMATION	Alternate Phone
Name of Business Sparklight	
Address/Location of sign 3519 Market Place Av	ve space #600 Bryant, AR 72022
Zoning Classification C-2	

Please use following page to provide details on the signs requesting approval. Along with information provided on this application, a Site Plan showing placement of sign(s) and any existing sign(s) on the property is required to be submitted. Renderings of the sign(s) showing the correct dimensions is also required to be submitted with the application. A thirty-five dollar (\$35) per sign payment will be collected at the time of permit issuance. According to the Sign Ordinance a fee for and sign variance or special sign permit request shall be one hundred dollars (\$100). Additional documentation may be required by Sign Administrator.


#### **READ CAREFULLY BEFORE SIGNING**

Adam Kerian , do hereby certify that all information contained within this application is true and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand

that no sign may be placed in public right of way. I understand that I must comply with all Building and Electrical Codes and that it is my responsibility to obtain all necessary permits.

#### Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering.

SIGN	<b>Type</b> (Façade, Pole, Monument, other)	<b>Dimensions</b> (Height, Length, Width)	Sqft (Measured in whole as rectangle)	Height of Sign (Measured from lot surface)		Column for Admin Certifying Approval
				Top of Sign	Bottom of Sign	
Α	Facade	37.3"x144"x4"	37.2	16'	12'7"	
В						
С						
E						
F						
G						



#### **EXISTING**



#### **EXISTING**



#### 1 Color white Sparklight sign Sign size of 144" X 37.3" Backlight Pan Channel

#### **PROPOSED**





3519 Market Place Ave #600, Bryant, AR 72022

Mike Kahler 602-579-3454

MKahler@americanbus.com

### **Existing Window/Door Measurments**





PRINT | PROMOTIONAL | FULFILLMENT

3519 Market Place Ave #600, Bryant, AR 72022

Mike Kahler 602-579-3454

MKahler@americanbus.com

## ORDER NEEDS APPROVAL

Please reply with Approval or Changes. Order will not be Produced until Approval is received.

**HR14** 



\*Dash insert: 2447 Trans. White insert with vinyl to match PMS 7675C

\*Sparklight insert: Perforated insert painted PMS Cool Gray 11C backed with 2447 Trans. White insert

**RETURN DEPTH & MATERIAL: 4"d FabSTL/FaceLit** 

**FACE FINISH: 5687 White SATIN Painted** 

**RETURN FINISH: Same** 

**BACKS: RECESS Removable Ptnd Stl Bk INSIDE CANS: Inside Cans NOT Painted** 

**SPACERS: None** 

**MOUNTING: RC2-Remov Can w/Studs** 

**PATTERN: Yes** 

**CUSTOM CUTOUT: Cutout Face Flat (No returns)** 

**OUTLINE: Stnd 1/2"Outline** 

**INSERT: See notes INSERT GLUED: Yes** 

Lead Wire Hole - Middle of Ltrs LED CABLE Leads - 120" long

**COLOR: White LEDs** 

**Exterior-WEEP Holes Required UL LISTED: Outside cans on TOP POWER SUPPLY: Standard Class 2** 

#### Sparklight-Face Lit


FRONT VIEW - lights on



Lights off



Backside view




**Lights On** 




**VERSION 2** 

8-14-2024




FASTENER DETAIL - STUDDED WALL SYSTEM
SCALE: NTS




FASTENER DETAIL - STUDDED WALL SYSTEM
SCALE: NTS

INSTALLATION DIAGRAMS SHOWN ARE CHANNEL LETTER SPECIFIC ONLY


HARDWARE INSTALLATION TO FOLLOW MANUFACTURERS SPECIFIC GUIDELINES



FASTENER DETAIL - CONCRETE/BRICK/CMU SCALE: NTS




FASTENER DETAIL - CONCRETE
SCALE: NTS



FASTENER DETAIL - CONCRETE/BRICK/CMU

SCALE: NTS



#### FASTENER DETAIL - WOOD FASCIA/WOOD BLOCKING SCALE: NTS

**Engineers Connection Note:** 

- All fasteners must be installed per/manufacturer's Tech Guide.
- Contact Murdoch Engineering for revision if field conditions vary.

**Prepared For:** 

/Sparklight<sup>®</sup>

Sign Type:

Reverse Pan Channel

**Sales Rep:** 

Mike Kahler American Solutions for Business

Note: This sign is intended to be installed in accordance with the requirements of Article 600 of the NFPA 2017 National Electrical Code and/or other applicable local codes. This includes proper grounding and bonding of



#### WIRING INSTRUCTIONS

#### Fabricated Metal - Lit with LEDs - 60 WATT

Warnings in English & French for Canada

**F10-ULAB-A2 Rev.** 11/21/22
S. Carnesi

#### Customer Installation/Tips/Troubleshooting Guide

Enclosed is your Fabricated lit letter/logo order.

Each individual letter/logo has been custom designed and manufactured to provide a consistent Lumen output.





#### **Components Used**

All letters/logos have been manufactured using only UL Listed and/or Recognized components. Gemini's UL EFILE #E319118 - UL & CSA approved.

#### **LEDs (letters) to Power Supply Connections**

It is recommended that all electrical connections be performed by a licensed electrical contractor. Each letter/logo is equipped with LEDs and a 2 or 3-conductor cable. If 3 conductor is supplied it is not necessary to connect the 3rd wire to the letter (white wire).

Maximum 5.0 amps, at 12VDC, to LEDs.

#### Standard wire connections from letter cable wires to power supply:

Power Supply (to LEDS)	<u>Letters</u>
------------------------	----------------

White (+) RED coated 18AWG wire (+) NOTE: this may be WHITE for 2-conductor supplied cable

Black (-) BLACK coated 18AWG wire (-)

WHITE Coated 18 AWG wire - Ground (not required)

When Class 2 wiring circuits pass through any wall, NEC code requires use of a conduit, or a UL Certified Class 2 cable.

When these circuits run through concealed spaces, such as a drop ceilings, many codes require use of Plenum rated cable.

Grounding of the letter on the Class 2 side is not necessary.

#### Power Supply (PS) to Power Source Connection

Power Supplies provided are Class 2, 12VDC output, wet location rated, max. 277VAC input.

Do NOT mount power supply directly into letters. Amperage ratings are listed on the power supply labels.

It is recommended that lead cables not exceed 10 feet long, for proper LED performance.

Each 60 watt power supply has 3 wires for input from power source.

Black is the LINE, White is NEUTRAL, and green is the GROUND.

Connect power supply to appropriate sized breaker or power cord, in accordance with National Electric Code (NEC),

Article 600, UL 48 and all local electric codes. All field wiring shall be 14 AWG stranded wire.

All orders will be supplied with a wiring diagram that details letter groupings to Power Supply channels.

#### **Power Supply Wiring - Example**


"MAIL" are powered by power supply #1.

"ROOM" are powered by power supply #2.

Caution: Plugging LEDs direct into

110VAC will destroy them.

Use ONLY Class 2,12VDC power supplies



#### Notes:

#### **LED Modules**

LED modules have been secured to letter backs with double faced tape. Every other module has been further secured with a plastic support blocks. Should you need to reposition any LED modules, break off the support block with pliers, reposition module and re-tape module. Then secure with silicone on sides and wires.

Grounding on the Class 2 side (Letter side) is not required

#### Backs

All LED lit components are supplied with required weep (drain) holes in the drops of each letter back, per UL requirements.

Weep holes are supplied to allow moisture or water to escape, as these units are not sealed.

Some install situations may require installers to further seal lit components, or field install additional weep holes - as needed. Letter Stand-Off

Halo lit letters are designed to stand-off the mounting surface by using studs and spacers.

Adjusting the spacer length or stand-off from the wall will effect the halo lighting effect.

Typical stand-offs for optimal halo lighting is around 1-1/2" from the mounting surface.

#### Mounting Surface

When Halo (back) lighting, it is best to install on a non-glossy, lighter colored mounting surfaces.

Dark, Glossy backgrounds will absorb the LED light and will not produce a desirable halo effect.

#### **LED Troubleshooting Guide**

#### Blinking LEDs:

Blinking LEDs: Too many LEDs connected to a given power supply.

Reduce the number of letters or modules attached to your power supply.

LEDs in one or more letters will not light:

LEDs will not light: Too many LED modules are connected to a given power supply.

Reduce the number of letters or modules attached to your power supply.

Check letter connections. Make sure lead cables are properly wired to power supply line.

Make sure all wires are connected per wiring diagram.

Reduce length of lead cables to 10ft. Maximum lengths.

Check AC input connection and/or check circuit breaker.

#### One LED module is Dark (not lit):

You may have a bad module. Check lighting of letter with face covered to determine impact of one dark LED.

If the face is too dark or visible shadows exist, additional LEDs may have to be added to the letter.

#### I see light shadows:

Insure that all modules are secured to the Lexan backs.

If a module has come loose, press it back down and secure with additional DF tape and/or silicone.

#### Some LEDs appear dim:

Ensure that the overall length of the LED system does not exceed the maximum load.

Ensure that the length of supply wire is equal to or below the recommended remote distance.

Ensure that only 50 modules are connected to any one power supply channel.

#### **Electrical Contractor Required**



#### **WARNINGS!**

It is recommended that all electrical connections be performed by a licensed electrical contractor.

Always follow proper OSHA LOTO (Lockout/Tagout) and NEC practices and procedures.

#### RISK OF ELECTRIC SHOCK:

Turn power **OFF** before inspection, installation or removal.

- Properly ground any Power Supply enclosures.
- Shut off power at fuse box or circuit breaker before install.

#### Prepare Electrical Wiring (Electrical Requirements)

#### **RISK OF FIRE:**

- Use only UL approved supply wires.
- Field wiring must be min.14 AWG stranded wire.

Caution: Plugging LEDs direct

Use ONLY Class 2 Power Supplies

into 110V will destroy them.

- Follow all NEC and Local Electrical Codes.
- Use only UL approved wire for input connection. Minimum size 1.02mm

• The grounding and bonding of the LED Driver shall be done in accordance with NEC Article 600.

Always understand and follow all National Electric Codes (NEC) and local electrical codes.

#### Entrepreneur en électricité AVERTISSEMENTS obligatoires!

Il est recommandé que toutes les connexions électriques doivent être faites par un maître électricien.

. Toujours suivre OSHA LOTO (verrouillage/étiquetage) et NEC pratiques et procédures appropriées.

#### RISQUE DE CHOC ÉLECTRIQUE : RISQUES D'INCENDIE :

Coupez l'alimentation avant l'inspection, l'installation ou la suppression.

- Utilisez uniquement UL approuvé fils d'alimentation,
- Terre correctement tous les boîtiers alimentation minimum de 18 AWG.
- · Coupez l'alimentation de la boîte à fusible ou le disjoncteur avant d'installer.
- Suivez toutes NEC et les codes électriques locaux.
- Utilisez uniquement UL fil pour l'entrée approuvé

Préparer le câblage électrique (Spécifications électriques) de connexion. Taille minimale 1,02 mm

• La mise à la terre et la liaison du conducteur de LED doivent être

effectués en conformité avec l'article NEC 600.

Toujours comprendre et suivre toutes les codes NEC (National Electric) et les codes électriques locaux.

Toutes les alimentations doivent être classé endroit humide, classe 2 avec UL lettres.




### Reversed channel letter (white LED halo)


Coldwell Banker Blue CMYK: 100/85/5/22

RGB: 1/33/105

#012169 PMS 280 C







## DETAILED PLANS: COLLECTIVE CHURCH

PROPOSED BUILDING & PARKING BRYANT, ARKANSAS

> LEGAL DESCRIPTION LOT 4, MARKETPLACE EAST SUBDIVISION TO THE CITY OF BRYANT, ARKANSAS

> > 4/3/2025 REV: 4/21/2025

#### PREPARED FOR:

COLLECTIVE CHURCH 3230 MARKET PLACE AVE, SUITE 2 BRYANT, AR 72022




### PRE-CONSTRUCTION COPY -

PLANS FOR BIDDING PURPOSES. QUANTITIES TO BE VERIFIED PRIOR TO CONSTRUCTION. CONTRACTOR TO VERIFY GRADES WITH ENGINEER PRIOR TO CONSTRUCTION.

INDEX OF SHEETS





		COVER SHEET	1
		SWPPP	2
		DEMOLITION PLAN	3
		SITE PLAN	4
Revisions  1 PER CITY OF BRYANT DRC COMMENTS	Date 4/21/2025	SITE DIMENSION PLANS	5-6
		GRADING PLANS	7-8
		UTILITY PLAN	9
		DETAILS	10-12
		LANDSCAPE PLAN	13



Prepared By:







#### GENERAL CONSTRUCTION NOTES

A. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGES OCCURRING TO ANY PROPERTY DURING THE CONSTRUCTION OF THIS PROJECT. SAID CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT PROPERTY DAMAGE.

B. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL SOLELY AND COMPLETELY BE RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, oxine INCLUDING SAFETY WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE

C. ALL SITE AND UTILITY IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION TO THE CITY OF BRYANT STANDARD SPECIFICATIONS.

D. CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH, AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE, AND/OR FEDERAL REGULATIONS

E. PRIOR TO INSTALLATION OF ANY UTILITIES, THE CONTRACTOR IS TO EXCAVATE, VERIFY, AND CALCULATE ALL CROSSINGS AND INFORM ANY IMPACTED UTILITY OWNERS OF ANY

F. CONSTRUCTION SHALL NOT START ON ANY WATER UTILITY TIE-INS UNTIL APPROVAL IS GIVEN BY CITY OF BRYANT. CONTRACTOR SHALL NOT OPERATE ANY VALVE, HYDRANT, OR WATER UTILITY APPURTENANCE NOR SHALL HE ATTACH TO OR TAP ANY WATER UTILITY MAIN WITHOUT APPROVAL FROM BRYANT. THE CONTRACTOR SHALL BEAR THE COST AND CONSEQUENCE OF ANY DISRUPTION OF UTILITY OPERATION CAUSED BY CONSTRUCTION.

G. FIBER OPTIC CABLE ON AND/OR ADJACENT TO THIS SITE WERE NOT LOCATED BY THE SURVEY AND ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ANY FIBER OPTIC CABLES AT TO NEAR THIS SITE AND TAKE ALL NECESSARY AND REQUIRED PRECAUTIONS TO PROTECT ANY EXISTING FIBER OPTIC CABLES. CONTRACTORS SHALL COORDINATE ALL EFFORTS WITH OWNER OF FIBER OPTIC CABLES OR THEIR DESIGNATED

H. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING "ONECALL" SERVICE TO MARK ALL UTILITIES PRIOR TO ANY DEMOLITION, EARTHWORK, OR UTILITY WORK ON THIS SITE.

I. ANY LAND CLEARING, CONSTRUCTION, OR DEVELOPMENT INVOLVING THE MOVEMENT OF MATERIALS, UTILITIES OR GROUND EXCAVATION SHALL BE IN ACCORDANCE WITH THE

J. THE APPROXIMATE LOCATION OF KNOWN SURFACE AND SUBSURFACE STRUCTURES, PIPES, POWER, GAS, PHONE, ETC. ARE SHOWN ON THE DESIGN DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF THE


K. CONTRACTOR TO ADHERE TO CURRENT OSHA REGULATIONS, INCLUDING EXCAVATION &

L. CONTRACTOR SHALL CONTACT THE CITY OF BRYANT STREET DEPARTMENT IN REGARD TO MAINTENANCE OF TRAFFIC PRIOR TO COMMENCEMENT OF WORK WITHIN STREET RIGHT OF


M. CONTRACTOR SHALL CONTACT CITY OF BRYANT PRIOR TO COMMENCEMENT OF UTILITY




1) QUANTITATIVE AREAS ARE APPROXIMATE, TO BE VERIFIED BY THE DEMOLITION CONTRACTOR.



EXISTING CONTOUR





PROPERTY DESCRIPTION

LOT 4 OF THE MARKETPLACE EAST SUBDIVISION, PHASE 2 TO THE CITY OF BRYANT, SALINE COUNTY, ARKANSAS.

#### **GENERAL NOTES:**

1.) SURVEYING PROVIDED BY RASBURRY SURVEYING LLC.

2.) PAVEMENT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THIS PLAN

AND BASED ON GEOTECHNICAL ANALYSIS OF THE SOIL CONDITIONS. 3.) ATTENTION IS CALLED TO CONSTRUCTION DETAILS FOR ADDITIONAL INFORMATION. 4.) CONSTRUCTION SITE SHALL ADHERE TO BRYANT STORMWATER REQUIREMENTS. AND

SHALL MEET ALL APPLICABLE ADEQ STANDARDS FOR EROSION CONTROL MEASURES. 5.) ALL UTILITIES TO BE LOCATED PRIOR TO CONSTRUCTION (ONE CALL, CITY, ETC.) 6.) CONTRACTOR TO ADHERE TO CURRENT OSHA REGULATIONS INCLUDING EXCAVATION &

7.) THE APPROXIMATE LOCATION OF KNOWN SURFACE AND SUBSURFACE STRUCTURES, PIPES, POWER, GAS, PHONE, ETC. ARE SHOWN ON THE DESIGN DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF THE AFOREMENTIONED ITEMS, SHOWN AND NOT SHOWN.

#### **UTILITIES:**

SANITARY SEWER: BRYANT SEWER DEPARTMENT 1019 S.W. 2ND RRYANT. AR 72022

BRYANT WATER DEPARTMENT 210 S.W. 3RD ST

501-943-0441 *ELECTRIC:* ENTERGY 425 W. CAPITAL AVE.

LITTLE ROCK. AR 72201 1-800-368-3749 NATURAL GAS: 400 WEST CAPITOL #600


**ENGINEER** RICHARDSON ENGINEERING. PLLC ADDRESS: 325 W.SOUTH ST. BENTON, AR. 72015 PHONE NO. (501) 315-7225 PROJECT REPRESENTATIVE: TRISTIN PHILLIPS, P.E.


RASBURRY SURVEYING LLC 308 W. SOUTH STREET BENTON, AR 72015 (501)860-6893

**DEVELOPERS** COLLECTIVE CHURCH 3230 MARKET PLACE AVE, SUITE 2 BRYANT, AR 72022

> ARKANSAS  $\star$   $\star$   $\star$ LICENSED **PROFESSIONAL ENGINEER** \* \* \* No. 21954


VICINITY MAP 1" = 2000'





REFER TO NOTES.

ZAT 104



A. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGES OCCURRING TO ANY PROPERTY DURING THE CONSTRUCTION OF THIS PROJECT. SAID CONTRACTOR SHALL

B. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES. THE CONTRACTOR WILL SOLELY AND COMPLETELY BE RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE

C. ALL SITE AND UTILITY IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE

D. CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS. RUBBISH. AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE, AND/OR FEDERAL REGULATIONS

E. PRIOR TO INSTALLATION OF ANY UTILITIES, THE CONTRACTOR IS TO EXCAVATE, VERIFY, AND CALCULATE ALL CROSSINGS AND INFORM ANY IMPACTED UTILITY OWNERS OF ANY

F. CONSTRUCTION SHALL NOT START ON ANY WATER UTILITY TIE-INS UNTIL APPROVAL IS GIVEN BY CITY OF BRYANT. CONTRACTOR SHALL NOT OPERATE ANY VALVE, HYDRANT, OR WATER UTILITY APPURTENANCE NOR SHALL HE ATTACH TO OR TAP ANY WATER UTILITY MAIN WITHOUT APPROVAL FROM BRYANT. THE CONTRACTOR SHALL BEAR THE COST AND

G. FIBER OPTIC CABLE ON AND/OR ADJACENT TO THIS SITE WERE NOT LOCATED BY THE SURVEY AND ARE NOT SHOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE ANY FIBER OPTIC CABLES AT TO NEAR THIS SITE AND TAKE ALL NECESSARY AND REQUIRED PRECAUTIONS TO PROTECT ANY EXISTING FIBER OPTIC CABLES. CONTRACTORS SHALL COORDINATE ALL EFFORTS WITH OWNER OF FIBER OPTIC CABLES OR THEIR DESIGNATED

H. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING "ONECALL" SERVICE TO MARK ALL

I. ANY LAND CLEARING, CONSTRUCTION, OR DEVELOPMENT INVOLVING THE MOVEMENT OF MATERIALS, UTILITIES OR GROUND EXCAVATION SHALL BE IN ACCORDANCE WITH THE

J. THE APPROXIMATE LOCATION OF KNOWN SURFACE AND SUBSURFACE STRUCTURES, PIPES, POWER, GAS, PHONE, ETC. ARE SHOWN ON THE DESIGN DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF THE

K. CONTRACTOR TO ADHERE TO CURRENT OSHA REGULATIONS, INCLUDING EXCAVATION &

L. CONTRACTOR SHALL CONTACT THE CITY OF BRYANT STREET DEPARTMENT IN REGARD TO MAINTENANCE OF TRAFFIC PRIOR TO COMMENCEMENT OF WORK WITHIN STREET RIGHT OF

M. CONTRACTOR SHALL CONTACT CITY OF BRYANT PRIOR TO COMMENCEMENT OF UTILITY

RICHARDSON ENGINEERING, PLLC ADDRESS: 325 W.SOUTH ST. BENTON, AR. 72015 PHONE NO. (501) 315-7225 PROJECT REPRESENTATIVE: TRISTIN PHILLIPS, P.E.

<u>SURVEYOR</u> RASBURRY SURVEYING LLC 308 W. SOUTH STREET BENTON, AR 72015 (501)860-6893


<u>DEVELOPERS</u> COLLECTIVE CHURCH 3230 MARKET PLACE AVE, SUITE 2 BRYANT, AR 72022


<u>OWNER OF RECORD</u> COLLECTIVE CHURCH 3230 MARKET PLACE AVE. SUITE 2 BRYANT, AR 72022 SOURCE OF TITLE: 2023-008570


ZATION


Sonsulting Consulting


2















### TYPICAL SECTION 4-4" UTILITY DUCTS


NOT TO SCALE

- 1.) ALL STOP SIGNS SHALL BE 30" X 30" 2.) PROPOSED LOCATIONS OF TRAFFIC CONTROL MARKERS ARE APPROXIMATE. ACTUAL LOCATION AND INSTALLATION MUST MEET
- MUTCD AND CITY OF BRYANT SPECS. 3.) PAVEMENT SHALL BE CONSTRUCTED IN ACCORDANCE WITH ENGINEER'S
- SPECIFICATIONS, AND BASED ON GEOTECHNICAL ANALYSIS OF THE SOIL CONDITIONS.
- 4.) CONTRACTOR SHALL INCLUDE IN BID THE COST FOR COMPACTION TESTS ON SUBGRADE & BASE. TEST TO BE CONDUCTED AS PER CITY OF BRYANT STREET DEPARTMENT SPECIFICATIONS.
- 5.) CURB INLETS CONSTRUCTED SO THAT POOLING OF WATER DOES
- NOT OCCUR AT INTERSECTIONS.
- 6.) ALL STORM BOX LIDS SHALL BE PER CITY OF BRYANT
- 7.) ALL SIDEWALKS AND CURB/GUTTER TO BE CONSTRUCTED PER CITY OF
- BRYANT SPECIFICATIONS. 8.) ALL SIDEWALKS TO MEET ADA REQUIREMENTS. 9.) \* - INDICATES ADA APPROVED HANDICAP RAMP.
- 10.) DEVELOPMENT SHALL ADHERE TO CITY OF BRYANT STORMWATER REQUIREMENTS.
- 11.) THE APPROXIMATE LOCATION OF KNOWN SURFACE AND SUBSURFACE STRUCTURES, PIPES, POWER, GAS, PHONE, ETC. ARE SHOWN ON THE DESIGN DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF THE AFOREMENTIONED ITEMS, SHOWN AND NOT SHOWN. ALL REPAIRS OR RELOCATIONS NECESSARY SHALL BE MADE AS REQUIRED BY THE UTILITY OR OWNER OF THE STRUCTURE. THE COST OF SAID REPAIRS OR RELOCATIONS SHALL BE

REFER TO CITY OF BRYANT, ARKANSAS PUBLIC WORKS STREET AND DRAINAGE STANDARD DETAILS FOR ADDITIONAL DETAILS AND INFORMATION.





## STORM DRAINAGE PIPE TRENCH (UNDER ASPHALT





STORM DRAINAGE PIPE TRENCH (UNPAVED AREA

HANDICAP SIGN DETAIL










#### SEWER NOTES:


- 1.) ALL CONSTRUCTION AND MATERIALS TO MEET OR EXCEED CITY OF BRYANT' SPECIFICATIONS.
- 2.) ALL SERVICE LINES SHALL BE 4" SDR-21 OR SCH 40 PVC OR AS SPECIFIED ON THE DESIGN DRAWINGS.
  3.) CONTRACTOR TO VERIFY METHOD OF CONNECTION WITH THE UTILITY OWNER PRIOR TO CONSTRUCTION.
  4) ATTENTION IS CALLED TO CONSTRUCTION DETAILS FOR ADDITIONAL INFORMATION.
- 5) CONTRACTOR TO ADHERE TO CURRENT OSHA REGULATIONS INCLUDING EXCAVATION & TRENCH SAFETY.
  6) BACKFILL FOR ALL DISTURBED (EXCAVATED) AREAS SHALL BE IN ACCORDANCE WITH
- CITY OF BRYANT STANDARD SPECS.


  7) A 2-WAY CLEANOUT WITH BACKFLOW PREVENTER SHALL BE INSTALLED WITHIN 5 FEET OF THE BUILDING.

  DIRECTIONALY, THE CLEANOUT MUST SWEEP AWAY FROM THE VALVE TO PREVENT DAMAGE TO THE

GUARDRAIL DETAIL












COLLECTIVE CHURCH

Prepared For:				3230 MARKET PLACE AVE.	( )	SOUE Z		BRYANT AR 72022	
Date	4/21/2025								
Revisions	PER CITY OF BRYANT DRC COMMENTS								
Š.	1								
590-200 :# IJ31088	CAO	Scale: Date: 4/3/2025	NTS ŘEV:	4/21/2025		Sheet:	11 0 13		







1.) ALL CONSTRUCTION AND MATERIALS TO MEET OR EXCEED CITY OF BRYANT SPECIFICATIONS.
2.) ALL SERVICE LINES AND METER SETTINGS SHALL BE AS PER CITY OF BRYANT SPECS.


5.) ATTENTION IS CALLED TO CONSTRUCTION DETAILS FOR ADDITIONAL INFORMATION.
6.) MINIMUM SEPARATION BETWEEN WATERLINES & SEWERLINES SHALL BE 10'.


4.) ALL FITTINGS SHALL BE DUCTILE IRON M.J. (WHERE AVAILABLE).


9.) STREET CROSSINGS TO MEET BRYANT STREET DEPT SPECIFICATIONS.


3.) 12ga BLUE COATED COPPER TRACING WIRE TO BE INSTALLED WITH ALL WATERLINES (MAINS & SERVICES).


7.) MINIMUM VERTICAL SEPARATION BETWEEN WATERLINE & SEWERLINE CROSSINGS SHALL BE 18" (WATER ON TOP).
8.) CONTRACTOR SHALL ADHERE TO CURRENT OSHA REGULATIONS INCLUDING EXCAVATION & TRENCH SAFETY.













DRAWN BY: CHECKED BY: FILE: W17-Vertical Tie-Down Blocking.dwg



OZ

 $\tilde{\mathbf{Q}}_{-}^{\mathbf{Z}}$ 



# **Drainage Report**

For

**Collective Church** 

**Bryant, Saline County, Arkansas** 



**April 23, 2025** 

Prepared by:

RICHARDSON ENGINEERING, PLLC

325 W. South St. Benton, AR 72015 501-315-7225

# **TABLE OF CONTENTS**


Title	Page Number
Project Owner Information	3
Project Location and Description	3
Site Drainage	4
Runoff Summary	4
Recommendations/Summary	4
Appendices:	5
Site Drainage Basin Maps	6
Storm System Design (SSA)	7
2 Year Design Storm	8
10 Year Design Storm	9
25 Year Design Storm	10
50 Year Design Storm	11
100 Year Design Storm	12
Pre and Post Development Hydrographs (Hydrology	13
Studio	

### **Project Owner Information**

Collective Church 3230 Markey Place Ave Bryant, AR 72022

# **Project Location and Description**

The project is located on Progress Way, part of the East Half of the Northwest Quarter, Section 22, Township 1-S, Range 14-W, Saline County, Arkansas.



Vicinity Map – N.T.S

This project is a Commercial Development for a Church, located in the City of Bryant, Saline County.

### Site Drainage

### Pre-Development

The pre-developed runoff for the site flows to the South to a regional detention basin for the overall commercial development. The pre-development runoff condition is undeveloped/woods.

#### Post-Development

The site drainage starts on the North side of the project and flows to the East and West. The drainage is intercepted into a storm sewer system and is discharged into the existing regional detention basin to the South of the proposed project. The post-development runoff conditions changed from undeveloped/woods to commercial development.

### **Runoff Summary**

Basin Design Point

Development Drainage Study Area = 3.48 Ac Existing Condition runoff Coefficient: C = 0.47

Proposed runoff Coefficient: C = 0.95


Tc Undeveloped = 10 Minutes (TR55 Method)


Tc Developed = 5 Minutes

Design Storm	Pre-Development Flow Rate (cfs)	Post-Development Flow Rate (cfs)
2-yr	7.34	20.30
10-yr	9.83	27.14
25-yr	11.30	31.18
50-yr	12.35	34.05
100-yr	13.42	37.03


#### **Recommendations/Summary**


The proposed drainage improvements include a storm sewer system for the commercial development that will be discharged into the existing regional detention basin. The proposed storm system also catches water from the commercial lot to the North and Hunters Crossing subdivision and routes it to the existing regional detention basin.














# **Project Description**

File Name ...... Collective Church Drainage 4-23-25.SPF

# **Project Options**

Flow Units	CFS
Elevation Type	Elevation
Hydrology Method	Rational
Time of Concentration (TOC) Method	SCS TR-55
Link Routing Method	Kinematic Wave
Enable Overflow Ponding at Nodes	YES
Skip Steady State Analysis Time Periods	NO

# **Analysis Options**

Start Analysis On	Apr 23, 2025	00:00:00
End Analysis On	Apr 24, 2025	00:00:00
Start Reporting On	Apr 23, 2025	00:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

### **Number of Elements**

	Qty
Rain Gages	0
Subbasins	12
Nodes	16
Junctions	6
Outfalls	4
Flow Diversions	0
Inlets	6
Storage Nodes	0
Links	15
Channels	1
Pipes	14
Pumps	0
Orifices	0
Weirs	0
Outlets	0
Pollutants	0
Land Uses	0

### **Rainfall Details**

# **Subbasin Summary**

SN Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
	(ac)		(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 Sub-AD- (24)	0.10	0.9500	0.51	0.49	0.05	0.58	0 00:05:00
2 Sub-AD- (25)	0.10	0.9500	0.51	0.49	0.05	0.58	0 00:05:00
3 Sub-AD- (29)	0.10	0.9500	0.51	0.49	0.05	0.58	0 00:05:00
4 Sub-AD- (30)	0.10	0.9500	0.51	0.49	0.05	0.58	0 00:05:00
5 Sub-CB-1	1.20	0.9500	0.51	0.49	0.58	6.99	0 00:05:00
6 Sub-CB-2	0.92	0.9500	0.51	0.49	0.45	5.35	0 00:05:00
7 Sub-CB-3	0.39	0.9500	0.51	0.49	0.19	2.26	0 00:05:00
8 Sub-CB-4	0.14	0.9500	0.51	0.49	0.07	0.82	0 00:05:00
9 Sub-CB-5	0.11	0.9500	0.51	0.49	0.06	0.67	0 00:05:00
10 Sub-CB-6	0.87	0.9500	0.51	0.49	0.42	5.10	0 00:05:00
11 Sub-FES-5	3.78	0.9500	0.51	0.49	1.84	22.04	0 00:05:00
12 Sub-FES-6	3.03	0.7000	1.02	0.71	2.16	7.14	0 00:18:13

# **Node Summary**

SN Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Water	Surcharge Elevation			Max HGL Elevation Attained	Ma Surcharg Dept Attaine
		(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(ft)	(f
1 AD- (24)	Junction	429.05	432.47	429.05	432.47	10.00	0.58	429.32	0.0
2 AD- (25)	Junction	428.00	432.46	428.00	432.46	10.00	1.13	428.26	0.0
3 AD- (29)	Junction	429.06	432.45	429.06	432.45	10.00	0.58	429.32	0.0
4 AD- (30)	Junction	428.00	432.46	428.00	432.46	10.00	1.12	428.29	0.0
5 FES-5	Junction	425.10	427.00	425.10	427.50	0.00	22.04	426.14	0.0
6 FES-6	Junction	424.75	426.99	424.75	426.99	0.00	7.14	425.49	0.0
7 Out-1SL - (15)	Outfall	421.25					35.50	422.94	
8 Out-1SL - (17)	Outfall	423.50					1.12	423.72	
9 Out-1SL - (18) (1)	Outfall	424.50					2.52	424.90	
10 Out-1SL - (21)	Outfall	422.50					7.11	423.15	

# **Link Summary**

SN Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Invert	Average Slope	Diameter or Height	Manning's Roughness		Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	F
				(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	
1 L-SL - (24)	Pipe	CB-3	CB-2	201.23	430.66	426.94	1.8500	0.000	0.0320	0.36	0.00	0.00	0.00	_
2 L-SL-14	Pipe	CB-1	CB-2	251.73	423.42	422.50	0.3700	0.000	0.0150	2.77	0.00	0.00	0.00	
3 SL - (14)	Pipe	CB-1	CB-2	127.64	423.42	422.72	0.5500	24.000	0.0130	4.16	16.75	0.25	7.71	
4 SL - (15)	Pipe	CB-2	Out-1SL - (15)	106.78	422.32	421.25	1.0000	30.000	0.0120	35.50	44.48	0.80	10.14	
5 SL - (16)	Pipe	AD- (24)	AD- (25)	105.49	429.05	428.00	1.0000	12.000	0.0120	0.57	3.86	0.15	5.59	
6 SL - (17)	Pipe	AD- (25)	Out-1SL - (17)	60.96	428.00	423.50	7.3800	12.000	0.0120	1.12	10.49	0.11	8.73	
7 SL - (18)	Pipe	CB-5	CB-4	141.40	427.00	424.90	1.4900	18.000	0.0120	1.76	13.88	0.13	5.45	
8 SL - (18) (1)	Pipe	CB-4	Out-1SL - (18) (1)	20.22	424.90	424.50	1.9700	18.000	0.0120	2.52	15.96	0.16	6.59	
9 SL - (19)	Pipe	AD- (29)	AD- (30)	106.07	429.06	428.00	1.0000	12.000	0.0120	0.57	3.86	0.15	5.60	
10 SL - (20)	Pipe	AD- (30)	CB-5	19.89	428.00	427.50	2.5100	12.000	0.0120	1.12	6.12	0.18	5.94	
11 SL - (21)	Pipe	CB-6	Out-1SL - (21)	63.64	423.50	422.50	1.5700	24.000	0.0120	7.11	30.72	0.23	7.96	
12 SL - (24)	Pipe	CB-3	CB-2	177.82	424.10	422.32	1.0000	30.000	0.0120	23.44	44.46	0.53	9.28	
13 SL - (25)	Pipe	FES-5	CB-3	52.99	425.10	424.10	1.8900	30.000	0.0120	21.93	61.04	0.36	11.83	
14 SL - (26)	Pipe	FES-6	CB-6	123.36	424.75	423.50	1.0100	24.000	0.0120	7.11	24.67	0.29	7.20	
15 L-SL - (18) (1)	Channel	CB-4	CB-6	272.73	431.93	427.30	1.7000	6.000	0.0150	0.00	7.95	0.00	0.00	

# **Inlet Summary**

SN Element	Inlet		Catchbasin	( )		Ponded					Allowable	Max Gutter	Max Gutter
ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
			Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
								Inlet		Flow		Flow	Flow
			(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1 CB-1	On Grade	1	423.42	429.56	423.42	N/A	6.99	4.21	2.77	60.33	10.00	14.61	429.85
2 CB-2	On Sag	1	422.32	426.95	422.32	10.00	8.48	N/A	N/A	N/A	10.00	9.70	427.49
3 CB-3	On Grade	1	424.10	430.66	424.10	N/A	2.26	1.90	0.36	84.14	10.00	5.89	430.82
4 CB-4	On Grade	1	424.90	431.93	424.90	N/A	0.82	0.82	0.00	100.00	10.00	5.89	432.05
5 CB-5	On Sag	1	427.00	432.00	427.00	10.00	0.67	N/A	N/A	N/A	10.00	2.33	432.32
6 CB-6	On Sag	1	423.50	427.34	423.50	10.00	5.10	N/A	N/A	N/A	10.00	7.76	427.86

### **Subbasin Hydrology**

```
Subbasin: Sub-AD- (24)
      Time of Concentration
              TOC Method: SCS TR-55
              Sheet Flow Equation :
                  Tc = (0.007 * ((n * Lf)^0.8)) / ((P^0.5) * (Sf^0.4))
              Where:
                  Tc = Time of Concentration (hr)
                  n = Manning's roughness
                  Lf = Flow Length (ft)
                  P = 2 yr, 24 hr Rainfall (inches)
Sf = Slope (ft/ft)
              Shallow Concentrated Flow Equation:
                 V = 16.1345 * (Sf^0.5) (unpaved surface)
V = 20.3282 * (Sf^0.5) (paved surface)
V = 15.0 * (Sf^0.5) (grassed waterway surface)
V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
V = 7.0 * (Sf^0.5) (short grass pasture surface)
V = 5.0 * (Sf^0.5) (woodland surface)
V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
                  Tc = (Lf / V) / (3600 sec/hr)
                          Where:
                  Tc = Time of Concentration (hr)
                  Lf = Flow Length (ft)
                  V = Velocity (ft/sec)
                  Sf = Slope (ft/ft)
              Channel Flow Equation :
                  V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n
                  R = Aq / Wp
Tc = (Lf / V) / (3600 sec/hr)
              Where:
                  Tc = Time of Concentration (hr)
                  Lf = Flow Length (ft)
R = Hydraulic Radius (ft)
                  Aq = Flow Area (ft²)
                  Wp = Wetted Perimeter (ft)
                  V = Velocity (ft/sec)
                  Sf = Slope (ft/ft)
n = Manning's roughness
```

Subbasin: Sub-AD- (25)

**Time of Concentration** 

Subbasin: Sub-AD- (29)

**Time of Concentration** 

Subbasin: Sub-AD- (30)

**Time of Concentration** 

#### **Time of Concentration**

#### **Time of Concentration**

#### **Time of Concentration**

#### **Time of Concentration**

#### **Time of Concentration**

#### **Time of Concentration**

Subbasin : Sub-FES-5

**Time of Concentration** 

# Subbasin : Sub-FES-6

#### **Time of Concentration**

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0.00	0.00
Flow Length (ft):	85.71195638	0.00	0.00
Slope (%):	2.4	0.00	0.00
2 yr, 24 hr Rainfall (in):	4.36	0.00	0.00
Velocity (ft/sec):	0.12	0.00	0.00
Computed Flow Time (min) :	12.01	0.00	0.00
	Subarea	Subarea	Subarea
Shallow Concentrated Flow Computations	Α	В	С
Flow Length (ft):	253.76684919	31.2339863	0.93388558
Slope (%):	1.8	0.4	1.25
Surface Type :	Paved	Paved	Unpaved
Velocity (ft/sec):	2.73	1.29	1.80
Computed Flow Time (min) :	1.55	4.29	0.38
Total TOC (min)18.23			

## **Junction Input**

SN Eleme	nt Invert	Ground/Rim	Ground/Rim	Initial	Initial	Surcharge	Surcharge	Ponded	Minimum
ID	Elevation	(Max)	(Max)	Water	Water	Elevation	Depth	Area	Pipe
		Elevation	Offset	Elevation	Depth				Cover
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(in)
1 AD- (2	4) 429.05	432.47	3.41	429.05	0.00	432.47	0.00	10.00	28.92
2 AD- (2	5) 428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.57
3 AD- (2	9) 429.06	432.45	3.39	429.06	0.00	432.45	0.00	10.00	28.73
4 AD- (3	0) 428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.55
5 FES-5	425.10	427.00	1.90	425.10	0.00	427.50	0.50	0.00	0.00
6 FES-6	424.75	426.99	2.24	424.75	0.00	426.99	0.00	0.00	2.85

### **Junction Results**

SN Element	Peak	Peak	Max HGL	Max HGL	Max	Min	Average HGL	Average HGL	Time
ID	Inflow	Lateral	Elevation	Depth	Surcharge	Freeboard	Elevation	Depth	Max H
		Inflow	Attained	Attained	Depth	Attained	Attained	Attained	Occurren
					Attained				
	(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:m
1 AD- (24)	0.58	0.58	429.32	0.27	0.00	3.15	429.06	0.01	0 00:
2 AD- (25)	1.13	0.58	428.26	0.26	0.00	4.21	428.00	0.00	0 00:
3 AD- (29)	0.58	0.58	429.32	0.26	0.00	3.13	429.06	0.00	0 00:
4 AD- (30)	1.12	0.58	428.29	0.29	0.00	4.17	428.00	0.00	0 00:
5 FES-5	22.04	22.04	426.14	1.04	0.00	1.46	425.10	0.00	0 00:
6 FES-6	7.14	7.14	425.49	0.74	0.00	1.50	424.76	0.01	0 00:

# **Channel Input**

SN Element	Length	Inlet	Inlet	Outlet	Outlet	Total	Average	Shape	Height	Width	Manı
ID		Invert	Invert	Invert	Invert	Drop	Slope				Rough
		Elevation	Offset	Elevation	Offset						
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)	
1 L-SL - (18) (1)	272.73	431.93	7.03	427.30	3.80	4.63	1.7000	User-Defined	0.500	17.000	0

## **Channel Results**

SN Element	Peak	Time of	Design Flow	Peak Flow/	Peak Flow	Travel	Peak Flow	Peak Flow T
ID	Flow	Peak Flow	Capacity	Design Flow	Velocity	Time	Depth	Depth/ Si
		Occurrence		Ratio				Total Depth
								Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (18) (1)	0.00	0 00:00	7.95	0.00	0.00		0.00	0.00

# Pipe Input

SN Element	Length	Inlet	Inlet				Average		Pipe	Pipe	Ma
ID		Invert			Invert	Drop	Slope	Shape	Diameter or	Width	Rou
		Elevation	Offset	Elevation	Offset				Height		
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1 L-SL - (24)	201.23	430.66	6.56	426.94	4.62	3.72	1.8500	Dummy	0.000	0.000	
2 L-SL-14	251.73	423.42	0.00	422.50	0.18	0.92	0.3700	Dummy	0.000	0.000	
3 SL - (14)	127.64	423.42	0.00	422.72	0.40	0.70	0.5500	CIRCULAR	24.000	24.000	
4 SL - (15)	106.78	422.32	0.00	421.25	0.00	1.07	1.0000	CIRCULAR	30.000	30.000	
5 SL - (16)	105.49	429.05	0.00	428.00	0.00	1.05	1.0000	CIRCULAR	12.000	12.000	
6 SL - (17)	60.96	428.00	0.00	423.50	0.00	4.50	7.3800	CIRCULAR	12.000	12.000	
7 SL - (18)	141.40	427.00	0.00	424.90	0.00	2.10	1.4900	CIRCULAR	18.000	18.000	
8 SL - (18) (1)	20.22	424.90	0.00	424.50	0.00	0.40	1.9700	CIRCULAR	18.000	18.000	
9 SL - (19)	106.07	429.06	0.00	428.00	0.00	1.06	1.0000	CIRCULAR	12.000	12.000	
10 SL - (20)	19.89	428.00	0.00	427.50	0.50	0.50	2.5100	CIRCULAR	12.000	12.000	
11 SL - (21)	63.64	423.50	0.00	422.50	0.00	1.00	1.5700	CIRCULAR	24.000	24.000	
12 SL - (24)	177.82	424.10	0.00	422.32	0.00	1.78	1.0000	CIRCULAR	30.000	30.000	
13 SL - (25)	52.99	425.10	0.00	424.10	0.00	1.00	1.8900	CIRCULAR	30.000	30.000	
14 SL - (26)	123.36	424.75	0.00	423.50	0.00	1.25	1.0100	CIRCULAR	24.000	24.000	

No. of Barrels

## **Pipe Results**

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity				Peak Flow Depth	Peak Flow To Depth/ Sur Total Depth Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (24)	0.36	0 00:05	0.00	0.00	0.00		0.00	0.00
2 L-SL-14	2.77	0 00:05	0.00	0.00	0.00		0.00	0.00
3 SL - (14)	4.16	0 00:05	16.75	0.25	7.71	0.28	0.68	0.34
4 SL - (15)	35.50	0 00:05	44.48	0.80	10.14	0.18	1.68	0.67
5 SL - (16)	0.57	0 00:05	3.86	0.15	5.59	0.31	0.26	0.26
6 SL - (17)	1.12	0 00:05	10.49	0.11	8.73	0.12	0.22	0.22
7 SL - (18)	1.76	0 00:05	13.88	0.13	5.45	0.43	0.36	0.24
8 SL - (18) (1)	2.52	0 00:05	15.96	0.16	6.59	0.05	0.40	0.27
9 SL - (19)	0.57	0 00:05	3.86	0.15	5.60	0.32	0.26	0.26
10 SL - (20)	1.12	0 00:05	6.12	0.18	5.94	0.06	0.29	0.29
11 SL - (21)	7.11	0 00:18	30.72	0.23	7.96	0.13	0.65	0.33
12 SL - (24)	23.44	0 00:05	44.46	0.53	9.28	0.32	1.29	0.51
13 SL - (25)	21.93	0 00:05	61.04	0.36	11.83	0.07	1.04	0.41
14 SL - (26)	7.11	0 00:18	24.67	0.29	7.20	0.29	0.73	0.37

## **Inlet Input**


SN	I Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
	ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
				(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(%)
1	CB-1	On Grade	1	423.42	429.56	6.14	423.42	0.00	N/A	0.00
2	2 CB-2	On Sag	1	422.32	426.95	4.63	422.32	0.00	10.00	0.00
3	3 CB-3	On Grade	1	424.10	430.66	6.56	424.10	0.00	N/A	0.00
4	I CB-4	On Grade	1	424.90	431.93	7.03	424.90	0.00	N/A	0.00
5	CB-5	On Sag	1	427.00	432.00	5.00	427.00	0.00	10.00	0.00
6	CB-6	On Sag	1	423.50	427.34	3.84	423.50	0.00	10.00	0.00

# **Roadway & Gutter Input**

SN Element	Roadway	Roadway	Roadway	Gutter	Gutter	Gutter	Allowable
ID	Longitudinal	Cross	Manning's	Cross	Width	Depression	Spread
	Slope	Slope	Roughness	Slope			
	(ft/ft)	(ft/ft)		(ft/ft)	(ft)	(in)	(ft)
1 CB-1	0.0100	0.0200	0.0150	0.0200	1.50	0.1312	10.00
2 CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3 CB-3	0.0380	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4 CB-4	0.0175	0.0200	0.0150	0.0200	1.50	0.1312	10.00
5 CB-5	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
6 CB-6	N/A	0.0350	0.0150	0.0200	1.50	0.1312	10.00

### **Inlet Results**

SN Element	Peak	Peak	Peak Flow	Peak Flow	Inlet	Max Gutter	Max Gutter	Max Gutter	٦
ID	Flow	Lateral	Intercepted	Bypassing	Efficiency	Spread	Water Elev.	Water Depth	Max
		Inflow	by	Inlet	during Peak	during Peak	during Peak	during Peak	Occı
			Inlet		Flow	Flow	Flow	Flow	
	(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days h
1 CB-1	6.99	6.99	4.21	2.77	60.33	14.61	429.85	0.29	(
2 CB-2	8.48	5.35	N/A	N/A	N/A	9.70	427.49	0.54	(
3 CB-3	2.26	2.26	1.90	0.36	84.14	5.89	430.82	0.16	(
4 CB-4	0.82	0.82	0.82	0.00	100.00	5.89	432.05	0.12	(
5 CB-5	0.67	0.67	N/A	N/A	N/A	2.33	432.32	0.32	(
6 CB-6	5.10	5.10	N/A	N/A	N/A	7.76	427.86	0.52	(



## **Project Description**

File Name ...... Collective Church Drainage 4-23-25.SPF

### **Project Options**

Flow Units	CFS
Elevation Type	Elevation
Hydrology Method	Rational
Time of Concentration (TOC) Method	SCS TR-55
Link Routing Method	Kinematic Wave
Enable Overflow Ponding at Nodes	YES
Skip Steady State Analysis Time Periods	NO

## **Analysis Options**

Start Analysis On	Apr 23, 2025	00:00:00
End Analysis On	Apr 24, 2025	00:00:00
Start Reporting On	Apr 23, 2025	00:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

#### **Number of Elements**

	Qty
Rain Gages	0
Subbasins	12
Nodes	16
Junctions	6
Outfalls	4
Flow Diversions	0
Inlets	6
Storage Nodes	0
Links	15
Channels	1
Pipes	14
Pumps	0
Orifices	0
Weirs	0
Outlets	0
Pollutants	0
Land Uses	0

### **Rainfall Details**

Return Period...... 10 year(s)

## **Subbasin Summary**

SN Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
	(ac)	Coomoioni	(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 Sub-AD- (24)	0.10	0.9500	0.68	0.65	0.06	0.78	0 00:05:00
2 Sub-AD- (25)	0.10	0.9500	0.68	0.65	0.06	0.78	0 00:05:00
3 Sub-AD- (29)	0.10	0.9500	0.68	0.65	0.06	0.78	0 00:05:00
4 Sub-AD- (30)	0.10	0.9500	0.68	0.65	0.06	0.78	0 00:05:00
5 Sub-CB-1	1.20	0.9500	0.68	0.65	0.78	9.34	0 00:05:00
6 Sub-CB-2	0.92	0.9500	0.68	0.65	0.60	7.15	0 00:05:00
7 Sub-CB-3	0.39	0.9500	0.68	0.65	0.25	3.03	0 00:05:00
8 Sub-CB-4	0.14	0.9500	0.68	0.65	0.09	1.09	0 00:05:00
9 Sub-CB-5	0.11	0.9500	0.68	0.65	0.07	0.89	0 00:05:00
10 Sub-CB-6	0.87	0.9500	0.68	0.65	0.57	6.82	0 00:05:00
11 Sub-FES-5	3.78	0.9500	0.68	0.65	2.46	29.47	0 00:05:00
12 Sub-FES-6	3.03	0.7000	1.36	0.96	2.89	9.55	0 00:18:13

## **Node Summary**

SN Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Water	Surcharge Elevation			Max HGL Elevation Attained	Ma Surcharg Dept Attaine
		(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(ft)	(f
1 AD- (24)	Junction	429.05	432.47	429.05	432.47	10.00	0.78	429.36	0.0
2 AD- (25)	Junction	428.00	432.46	428.00	432.46	10.00	1.50	428.30	0.0
3 AD- (29)	Junction	429.06	432.45	429.06	432.45	10.00	0.78	429.36	0.0
4 AD- (30)	Junction	428.00	432.46	428.00	432.46	10.00	1.51	428.34	0.0
5 FES-5	Junction	425.10	427.00	425.10	427.50	0.00	29.47	426.32	0.0
6 FES-6	Junction	424.75	426.99	424.75	426.99	0.00	9.55	425.61	0.0
7 Out-1SL - (15)	Outfall	421.25					48.12	423.54	
8 Out-1SL - (17)	Outfall	423.50					1.50	423.76	
9 Out-1SL - (18) (1)	Outfall	424.50					3.38	424.97	
10 Out-1SL - (21)	Outfall	422.50					9.51	423.26	

# **Link Summary**

SN Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness		Design Flow Capacity		Peak Flow Velocity	
				(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	
1 L-SL - (24)	Pipe	CB-3	CB-2	201.23	430.66	426.94	1.8500	0.000	0.0320	0.73	0.00	0.00	0.00	
2 L-SL-14	Pipe	CB-1	CB-2	251.73	423.42	422.50	0.3700	0.000	0.0150	4.42	0.00	0.00	0.00	
3 SL - (14)	Pipe	CB-1	CB-2	127.64	423.42	422.72	0.5500	24.000	0.0130	4.87	16.75	0.29	8.20	
4 SL - (15)	Pipe	CB-2	Out-1SL - (15)	106.78	422.32	421.25	1.0000	30.000	0.0120	48.12	44.48	1.08	10.64	
5 SL - (16)	Pipe	AD- (24)	AD- (25)	105.49	429.05	428.00	1.0000	12.000	0.0120	0.75	3.86	0.20	5.92	
6 SL - (17)	Pipe	AD- (25)	Out-1SL - (17)	60.96	428.00	423.50	7.3800	12.000	0.0120	1.50	10.49	0.14	9.47	
7 SL - (18)	Pipe	CB-5	CB-4	141.40	427.00	424.90	1.4900	18.000	0.0120	2.36	13.88	0.17	5.92	
8 SL - (18) (1)	Pipe	CB-4	Out-1SL - (18) (1)	20.22	424.90	424.50	1.9700	18.000	0.0120	3.38	15.96	0.21	7.17	
9 SL - (19)	Pipe	AD- (29)	AD- (30)	106.07	429.06	428.00	1.0000	12.000	0.0120	0.76	3.86	0.20	5.93	
10 SL - (20)	Pipe	AD- (30)	CB-5	19.89	428.00	427.50	2.5100	12.000	0.0120	1.50	6.12	0.25	6.45	
11 SL - (21)	Pipe	CB-6	Out-1SL - (21)	63.64	423.50	422.50	1.5700	24.000	0.0120	9.51	30.72	0.31	8.62	
12 SL - (24)	Pipe	CB-3	CB-2	177.82	424.10	422.32	1.0000	30.000	0.0120	31.08	44.46	0.70	9.92	
13 SL - (25)	Pipe	FES-5	CB-3	52.99	425.10	424.10	1.8900	30.000	0.0120	29.34	61.04	0.48	12.41	
14 SL - (26)	Pipe	FES-6	CB-6	123.36	424.75	423.50	1.0100	24.000	0.0120	9.51	24.67	0.39	7.69	
15 L-SL - (18) (1)	Channel	CB-4	CB-6	272.73	431.93	427.30	1.7000	6.000	0.0150	0.01	7.95	0.00	0.90	

# **Inlet Summary**

SN Element ID	Inlet Location	Number of Inlets	Catchbasin Invert	Max (Rim) Elevation		Ponded Area		Peak Flow Intercepted			Allowable Spread	Max Gutter Spread	Max Gutter Water Elev.
			Elevation		Elevation			by	Inlet	during Peak	•	during Peak	during Peak
								Inlet		Flow		Flow	Flow
			(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1 CB-1	On Grade	1	423.42	429.56	423.42	N/A	9.34	4.92	4.42	52.73	10.00	16.29	429.88
2 CB-2	On Sag	1	422.32	426.95	422.32	10.00	12.30	N/A	N/A	N/A	10.00	12.42	427.57
3 CB-3	On Grade	1	424.10	430.66	424.10	N/A	3.03	2.29	0.73	75.84	10.00	6.55	430.84
4 CB-4	On Grade	1	424.90	431.93	424.90	N/A	1.09	1.09	0.00	100.00	10.00	6.57	432.06
5 CB-5	On Sag	1	427.00	432.00	427.00	10.00	0.89	N/A	N/A	N/A	10.00	2.83	432.34
6 CB-6	On Sag	1	423.50	427.34	423.50	10.00	6.81	N/A	N/A	N/A	10.00	9.41	427.92

#### **Subbasin Hydrology**

# Subbasin: Sub-AD- (24) **Time of Concentration** TOC Method: SCS TR-55 Sheet Flow Equation : $Tc = (0.007 * ((n * Lf)^0.8)) / ((P^0.5) * (Sf^0.4))$ Where: Tc = Time of Concentration (hr) n = Manning's roughness Lf = Flow Length (ft) P = 2 yr, 24 hr Rainfall (inches) Sf = Slope (ft/ft) Shallow Concentrated Flow Equation: V = 16.1345 \* (Sf^0.5) (unpaved surface) V = 20.3282 \* (Sf^0.5) (paved surface) V = 15.0 \* (Sf^0.5) (grassed waterway surface) V = 10.0 \* (Sf^0.5) (nearly bare & untilled surface) V = 9.0 \* (Sf^0.5) (cultivated straight rows surface) V = 7.0 \* (Sf^0.5) (short grass pasture surface) V = 5.0 \* (Sf^0.5) (woodland surface) V = 2.5 \* (Sf^0.5) (forest w/heavy litter surface) Tc = (Lf / V) / (3600 sec/hr)Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) Channel Flow Equation : $V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n$ R = Aq / WpTc = (Lf / V) / (3600 sec/hr) Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) R = Hydraulic Radius (ft) Aq = Flow Area (ft²) Wp = Wetted Perimeter (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) n = Manning's roughness

Subbasin: Sub-AD- (25)

**Time of Concentration** 

Subbasin: Sub-AD- (29)

**Time of Concentration** 

Subbasin: Sub-AD- (30)

Time of Concentration

#### **Time of Concentration**

Subbasin : Sub-FES-5

**Time of Concentration** 

## Subbasin : Sub-FES-6

#### **Time of Concentration**

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0.00	0.00
Flow Length (ft):	85.71195638	0.00	0.00
Slope (%):	2.4	0.00	0.00
2 yr, 24 hr Rainfall (in):	4.36	0.00	0.00
Velocity (ft/sec):	0.12	0.00	0.00
Computed Flow Time (min) :	12.01	0.00	0.00
	Subarea	Subarea	Subarea
Shallow Concentrated Flow Computations	Α	В	С
Flow Length (ft):	253.76684919	31.2339863	0.93388558
Slope (%):	1.8	0.4	1.25
Surface Type :	Paved	Paved	Unpaved
Velocity (ft/sec):	2.73	1.29	1.80
Computed Flow Time (min) :	1.55	4.29	0.38
Total TOC (min)18.23			

### **Junction Input**

SN Element	Invert	Ground/Rim	Ground/Rim	Initial	Initial	Surcharge	Surcharge	Ponded	Minimum
ID	Elevation	(Max)	(Max)	Water	Water	Elevation	Depth	Area	Pipe
		Elevation	Offset	Elevation	Depth				Cover
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(in)
1 AD- (24)	429.05	432.47	3.41	429.05	0.00	432.47	0.00	10.00	28.92
2 AD- (25)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.57
3 AD- (29)	429.06	432.45	3.39	429.06	0.00	432.45	0.00	10.00	28.73
4 AD- (30)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.55
5 FES-5	425.10	427.00	1.90	425.10	0.00	427.50	0.50	0.00	0.00
6 FES-6	424.75	426.99	2.24	424.75	0.00	426.99	0.00	0.00	2.85

#### **Junction Results**

SN Element	Peak	Peak	Max HGL	Max HGL	Max	Min	Average HGL	Average HGL	Time
ID	Inflow	Lateral	Elevation	Depth	Surcharge	Freeboard	Elevation	Depth	Max H(
		Inflow	Attained	Attained	Depth	Attained	Attained	Attained	Occurren
					Attained				
	(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:m
1 AD- (24)	0.78	0.78	429.36	0.31	0.00	3.11	429.06	0.01	0 00:
2 AD- (25)	1.50	0.78	428.30	0.30	0.00	4.16	428.00	0.00	0 00:
3 AD- (29)	0.78	0.78	429.36	0.30	0.00	3.09	429.06	0.00	0 00:
4 AD- (30)	1.51	0.78	428.34	0.34	0.00	4.12	428.00	0.00	0 00:
5 FES-5	29.47	29.47	426.32	1.22	0.00	1.28	425.11	0.01	0 00:
6 FES-6	9.55	9.55	425.61	0.86	0.00	1.37	424.76	0.01	0 00:

## **Channel Input**

SN Element	Length	Inlet	Inlet	Outlet	Outlet	Total	Average	Shape	Height	Width	Manı
ID		Invert	Invert	Invert	Invert	Drop	Slope				Rough
		Elevation	Offset	Elevation	Offset						
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)	
1 L-SL - (18) (1)	272.73	431.93	7.03	427.30	3.80	4.63	1.7000	User-Defined	0.500	17.000	0

### **Channel Results**

;	SN Element	Peak	Time of	Design Flow	Peak Flow/	Peak Flow	Travel	Peak Flow	Peak Flow	Т
	ID	Flow	Peak Flow	Capacity	Design Flow	Velocity	Time	Depth	Depth/	Sı
			Occurrence		Ratio				Total Depth	
									Ratio	
_		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
	1 L-SL - (18) (1)	0.01	0 00:05	7.95	0.00	0.90	5.05	0.02	0.05	

# Pipe Input

SN Element	Length	Inlet	Inlet				Average		Pipe	Pipe	Ma
ID		Invert	Invert	Invert	Invert	Drop	Slope	Shape	Diameter or	Width	Rou
		Elevation	Offset	Elevation	Offset				Height		
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1 L-SL - (24)	201.23	430.66	6.56	426.94	4.62	3.72	1.8500	Dummy	0.000	0.000	
2 L-SL-14	251.73	423.42	0.00	422.50	0.18	0.92	0.3700	Dummy	0.000	0.000	
3 SL - (14)	127.64	423.42	0.00	422.72	0.40	0.70	0.5500	CIRCULAR	24.000	24.000	
4 SL - (15)	106.78	422.32	0.00	421.25	0.00	1.07	1.0000	CIRCULAR	30.000	30.000	
5 SL - (16)	105.49	429.05	0.00	428.00	0.00	1.05	1.0000	CIRCULAR	12.000	12.000	
6 SL - (17)	60.96	428.00	0.00	423.50	0.00	4.50	7.3800	CIRCULAR	12.000	12.000	
7 SL - (18)	141.40	427.00	0.00	424.90	0.00	2.10	1.4900	CIRCULAR	18.000	18.000	
8 SL - (18) (1)	20.22	424.90	0.00	424.50	0.00	0.40	1.9700	CIRCULAR	18.000	18.000	
9 SL - (19)	106.07	429.06	0.00	428.00	0.00	1.06	1.0000	CIRCULAR	12.000	12.000	
10 SL - (20)	19.89	428.00	0.00	427.50	0.50	0.50	2.5100	CIRCULAR	12.000	12.000	
11 SL - (21)	63.64	423.50	0.00	422.50	0.00	1.00	1.5700	CIRCULAR	24.000	24.000	
12 SL - (24)	177.82	424.10	0.00	422.32	0.00	1.78	1.0000	CIRCULAR	30.000	30.000	
13 SL - (25)	52.99	425.10	0.00	424.10	0.00	1.00	1.8900	CIRCULAR	30.000	30.000	
14 SL - (26)	123.36	424.75	0.00	423.50	0.00	1.25	1.0100	CIRCULAR	24.000	24.000	

No. of Barrels

### **Pipe Results**

SN Element ID	Peak Flow	Time of Peak Flow Occurrence		Peak Flow/ Design Flow Ratio			Peak Flow Depth	Peak Flow To Depth/ Sur Total Depth Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (24)	0.73	0 00:05	0.00	0.00	0.00		0.02	0.05
2 L-SL-14	4.42	0 00:05	0.00	0.00	0.00		0.02	0.05
3 SL - (14)	4.87	0 00:05	16.75	0.29	8.20	0.26	0.74	0.37
4 SL - (15)	48.12	0 00:05	44.48	1.08	10.64	0.17	2.32	0.93
5 SL - (16)	0.75	0 00:05	3.86	0.20	5.92	0.30	0.30	0.30
6 SL - (17)	1.50	0 00:05	10.49	0.14	9.47	0.11	0.26	0.26
7 SL - (18)	2.36	0 00:05	13.88	0.17	5.92	0.40	0.42	0.28
8 SL - (18) (1)	3.38	0 00:05	15.96	0.21	7.17	0.05	0.47	0.31
9 SL - (19)	0.76	0 00:05	3.86	0.20	5.93	0.30	0.30	0.30
10 SL - (20)	1.50	0 00:05	6.12	0.25	6.45	0.05	0.34	0.34
11 SL - (21)	9.51	0 00:18	30.72	0.31	8.62	0.12	0.76	0.38
12 SL - (24)	31.08	0 00:05	44.46	0.70	9.92	0.30	1.54	0.62
13 SL - (25)	29.34	0 00:05	61.04	0.48	12.41	0.07	1.22	0.49
14 SL - (26)	9.51	0 00:18	24.67	0.39	7.69	0.27	0.86	0.43

### **Inlet Input**


	SN Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
	ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
_				(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(%)
	1 CB-1	On Grade	1	423.42	429.56	6.14	423.42	0.00	N/A	0.00
	2 CB-2	On Sag	1	422.32	426.95	4.63	422.32	0.00	10.00	0.00
	3 CB-3	On Grade	1	424.10	430.66	6.56	424.10	0.00	N/A	0.00
	4 CB-4	On Grade	1	424.90	431.93	7.03	424.90	0.00	N/A	0.00
	5 CB-5	On Sag	1	427.00	432.00	5.00	427.00	0.00	10.00	0.00
	6 CB-6	On Sag	1	423.50	427.34	3.84	423.50	0.00	10.00	0.00

## **Roadway & Gutter Input**

SN Element	Roadway	Roadway	Roadway	Gutter	Gutter	Gutter	Allowable
ID	Longitudinal	Cross	Manning's	Cross	Width	Depression	Spread
	Slope	Slope	Roughness	Slope			
	(ft/ft)	(ft/ft)		(ft/ft)	(ft)	(in)	(ft)
1 CB-1	0.0100	0.0200	0.0150	0.0200	1.50	0.1312	10.00
2 CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3 CB-3	0.0380	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4 CB-4	0.0175	0.0200	0.0150	0.0200	1.50	0.1312	10.00
5 CB-5	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
6 CB-6	N/A	0.0350	0.0150	0.0200	1.50	0.1312	10.00

### **Inlet Results**

SN Element	Peak	Peak	Peak Flow	Peak Flow	Inlet	Max Gutter	Max Gutter	Max Gutter	
ID	Flow	Lateral	Intercepted	Bypassing	Efficiency	Spread	Water Elev.	Water Depth	Max
		Inflow	by	Inlet	during Peak	during Peak	during Peak	during Peak	Occi
			Inlet		Flow	Flow	Flow	Flow	
	(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days I
1 CB-1	9.34	9.34	4.92	4.42	52.73	16.29	429.88	0.33	-
2 CB-2	12.30	7.15	N/A	N/A	N/A	12.42	427.57	0.62	1
3 CB-3	3.03	3.03	2.29	0.73	75.84	6.55	430.84	0.18	1
4 CB-4	1.09	1.09	1.09	0.00	100.00	6.57	432.06	0.13	1
5 CB-5	0.89	0.89	N/A	N/A	N/A	2.83	432.34	0.33	- (
6 CB-6	6.81	6.81	N/A	N/A	N/A	9.41	427.92	0.58	1



## **Project Description**

File Name ...... Collective Church Drainage 4-23-25.SPF

### **Project Options**

Flow Units	CFS
Elevation Type	Elevation
Hydrology Method	Rational
Time of Concentration (TOC) Method	SCS TR-55
Link Routing Method	Kinematic Wave
Enable Overflow Ponding at Nodes	YES
Skip Steady State Analysis Time Periods	NO

## **Analysis Options**

Start Analysis On	Apr 23, 2025	00:00:00
End Analysis On	Apr 24, 2025	00:00:00
Start Reporting On	Apr 23, 2025	00:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

#### **Number of Elements**

anibor or Elomonic	
	Qty
Rain Gages	. 0
Subbasins	
Nodes	16
Junctions	6
Outfalls	4
Flow Diversions	0
Inlets	6
Storage Nodes	0
Links	15
Channels	1
Pipes	14
Pumps	0
Orifices	0
Weirs	0
Outlets	0
Pollutants	0
Land Uses	0

#### **Rainfall Details**

Return Period...... 50 year(s)

## **Subbasin Summary**

SN Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
	(ac)	Occinicioni	(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 Sub-AD- (24)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
2 Sub-AD- (25)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
3 Sub-AD- (29)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
4 Sub-AD- (30)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
5 Sub-CB-1	1.20	0.9500	0.86	0.82	0.98	11.72	0 00:05:00
6 Sub-CB-2	0.92	0.9500	0.86	0.82	0.75	8.97	0 00:05:00
7 Sub-CB-3	0.39	0.9500	0.86	0.82	0.32	3.80	0 00:05:00
8 Sub-CB-4	0.14	0.9500	0.86	0.82	0.11	1.37	0 00:05:00
9 Sub-CB-5	0.11	0.9500	0.86	0.82	0.09	1.12	0 00:05:00
10 Sub-CB-6	0.87	0.9500	0.86	0.82	0.71	8.55	0 00:05:00
11 Sub-FES-5	3.78	0.9500	0.86	0.82	3.08	36.97	0 00:05:00
12 Sub-FES-6	3.03	0.7000	1.72	1.20	3.64	12.03	0 00:18:13

## **Node Summary**

SN Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation			Max HGL Elevation Attained	Ma Surcharg Dept Attaine
		(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(f
1 AD- (24)	Junction	429.05	432.47	429.05	432.47	10.00	0.97	429.40	0.0
2 AD- (25)	Junction	428.00	432.46	428.00	432.46	10.00	1.89	428.34	0.0
3 AD- (29)	Junction	429.06	432.45	429.06	432.45	10.00	0.97	429.40	0.0
4 AD- (30)	Junction	428.00	432.46	428.00	432.46	10.00	1.89	428.38	0.0
5 FES-5	Junction	425.10	427.00	425.10	427.50	0.00	36.97	426.50	0.0
6 FES-6	Junction	424.75	426.99	424.75	426.99	0.00	12.03	425.74	0.0
7 Out-1SL - (15)	Outfall	421.25					48.11	423.75	
8 Out-1SL - (17)	Outfall	423.50					1.89	423.79	
9 Out-1SL - (18) (1)	Outfall	424.50					4.23	425.03	
10 Out-1SL - (21)	Outfall	422.50					11.98	423.37	

# **Link Summary**

SN Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness		Design Flow Capacity		Peak Flow Velocity	F
				(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	
1 L-SL - (24)	Pipe	CB-3	CB-2	201.23	430.66	426.94	1.8500	0.000	0.0320	1.17	0.00	0.00	0.00	_
2 L-SL-14	Pipe	CB-1	CB-2	251.73	423.42	422.50	0.3700	0.000	0.0150	6.18	0.00	0.00	0.00	
3 SL - (14)	Pipe	CB-1	CB-2	127.64	423.42	422.72	0.5500	24.000	0.0130	5.48	16.75	0.33	8.60	
4 SL - (15)	Pipe	CB-2	Out-1SL - (15)	106.78	422.32	421.25	1.0000	30.000	0.0120	48.11	44.48	1.08	10.82	
5 SL - (16)	Pipe	AD- (24)	AD- (25)	105.49	429.05	428.00	1.0000	12.000	0.0120	0.95	3.86	0.25	6.31	
6 SL - (17)	Pipe	AD- (25)	Out-1SL - (17)	60.96	428.00	423.50	7.3800	12.000	0.0120	1.89	10.49	0.18	10.12	
7 SL - (18)	Pipe	CB-5	CB-4	141.40	427.00	424.90	1.4900	18.000	0.0120	2.96	13.88	0.21	6.31	
8 SL - (18) (1)	Pipe	CB-4	Out-1SL - (18) (1)	20.22	424.90	424.50	1.9700	18.000	0.0120	4.23	15.96	0.26	7.63	
9 SL - (19)	Pipe	AD- (29)	AD- (30)	106.07	429.06	428.00	1.0000	12.000	0.0120	0.95	3.86	0.25	6.31	
10 SL - (20)	Pipe	AD- (30)	CB-5	19.89	428.00	427.50	2.5100	12.000	0.0120	1.89	6.12	0.31	6.86	
11 SL - (21)	Pipe	CB-6	Out-1SL - (21)	63.64	423.50	422.50	1.5700	24.000	0.0120	11.98	30.72	0.39	9.17	
12 SL - (24)	Pipe	CB-3	CB-2	177.82	424.10	422.32	1.0000	30.000	0.0120	38.91	44.46	0.88	10.36	
13 SL - (25)	Pipe	FES-5	CB-3	52.99	425.10	424.10	1.8900	30.000	0.0120	36.76	61.04	0.60	13.23	
14 SL - (26)	Pipe	FES-6	CB-6	123.36	424.75	423.50	1.0100	24.000	0.0120	11.98	24.67	0.49	8.11	
15 L-SL - (18) (1)	Channel	CB-4	CB-6	272.73	431.93	427.30	1.7000	6.000	0.0150	0.02	7.95	0.00	1.51	

# **Inlet Summary**

SN Element			Catchbasin	( )		Ponded					Allowable		Max Gutter
ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
			Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
								Inlet		Flow		Flow	Flow
			(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1 CB-1	On Grade	1	423.42	429.56	423.42	N/A	11.72	5.54	6.18	47.29	10.00	17.73	429.91
2 CB-2	On Sag	1	422.32	426.95	422.32	10.00	16.31	N/A	N/A	N/A	10.00	15.00	427.65
3 CB-3	On Grade	1	424.10	430.66	424.10	N/A	3.80	2.63	1.16	69.34	10.00	7.11	430.86
4 CB-4	On Grade	1	424.90	431.93	424.90	N/A	1.37	1.35	0.02	98.50	10.00	7.15	432.07
5 CB-5	On Sag	1	427.00	432.00	427.00	10.00	1.12	N/A	N/A	N/A	10.00	3.29	432.35
6 CB-6	On Sag	1	423.50	427.34	423.50	10.00	8.55	N/A	N/A	N/A	10.00	10.95	427.97

#### **Subbasin Hydrology**

```
Subbasin: Sub-AD- (24)
      Time of Concentration
              TOC Method: SCS TR-55
              Sheet Flow Equation :
                  Tc = (0.007 * ((n * Lf)^0.8)) / ((P^0.5) * (Sf^0.4))
              Where:
                  Tc = Time of Concentration (hr)
                  n = Manning's roughness
                  Lf = Flow Length (ft)
                  P = 2 yr, 24 hr Rainfall (inches)
Sf = Slope (ft/ft)
              Shallow Concentrated Flow Equation:
                 V = 16.1345 * (Sf^0.5) (unpaved surface)
V = 20.3282 * (Sf^0.5) (paved surface)
V = 15.0 * (Sf^0.5) (grassed waterway surface)
V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
V = 7.0 * (Sf^0.5) (short grass pasture surface)
V = 5.0 * (Sf^0.5) (woodland surface)
V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
                  Tc = (Lf / V) / (3600 sec/hr)
                          Where:
                  Tc = Time of Concentration (hr)
                  Lf = Flow Length (ft)
                  V = Velocity (ft/sec)
                  Sf = Slope (ft/ft)
              Channel Flow Equation :
                  V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n
                  R = Aq / Wp
Tc = (Lf / V) / (3600 sec/hr)
              Where:
                  Tc = Time of Concentration (hr)
                  Lf = Flow Length (ft)
R = Hydraulic Radius (ft)
                  Aq = Flow Area (ft²)
                  Wp = Wetted Perimeter (ft)
                  V = Velocity (ft/sec)
                  Sf = Slope (ft/ft)
n = Manning's roughness
```

Subbasin: Sub-AD- (25)

**Time of Concentration** 

Subbasin: Sub-AD- (29)

**Time of Concentration** 

Subbasin: Sub-AD- (30)

**Time of Concentration** 

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

Subbasin : Sub-FES-5

**Time of Concentration** 

# Subbasin : Sub-FES-6

### **Time of Concentration**

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0.00	0.00
Flow Length (ft):	85.71195638	0.00	0.00
Slope (%):	2.4	0.00	0.00
2 yr, 24 hr Rainfall (in):	4.36	0.00	0.00
Velocity (ft/sec):	0.12	0.00	0.00
Computed Flow Time (min) :	12.01	0.00	0.00
	Subarea	Subarea	Subarea
Shallow Concentrated Flow Computations	Α	В	С
Flow Length (ft):	253.76684919	31.2339863	0.93388558
Slope (%):	1.8	0.4	1.25
Surface Type :	Paved	Paved	Unpaved
Velocity (ft/sec):	2.73	1.29	1.80
Computed Flow Time (min) :	1.55	4.29	0.38
Total TOC (min)18.23			

# **Junction Input**

SN Element	Invert	Ground/Rim	Ground/Rim	Initial	Initial	Surcharge	Surcharge	Ponded	Minimum	
ID	Elevation	(Max)	(Max)	Water	Water	Elevation	Depth	Area	Pipe	
		Elevation	Offset	Elevation	Depth				Cover	
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(in)	
1 AD- (24)	429.05	432.47	3.41	429.05	0.00	432.47	0.00	10.00	28.92	
2 AD- (25)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.57	
3 AD- (29)	429.06	432.45	3.39	429.06	0.00	432.45	0.00	10.00	28.73	
4 AD- (30)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.55	
5 FES-5	425.10	427.00	1.90	425.10	0.00	427.50	0.50	0.00	0.00	
6 FES-6	424.75	426.99	2.24	424.75	0.00	426.99	0.00	0.00	2.85	

## **Junction Results**

SN Element ID	Peak Inflow	Peak Lateral	Max HGL Elevation		Max Surcharge		Average HGL Elevation	Average HGL Depth	Time Max H
		Inflow	Attained	Attained	Depth	Attained	Attained	Attained	Occurren
					Attained				
	(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:m
1 AD- (24)	0.97	0.97	429.40	0.35	0.00	3.07	429.06	0.01	0 00:
2 AD- (25)	1.89	0.97	428.34	0.34	0.00	4.13	428.00	0.00	0 00:
3 AD- (29)	0.97	0.97	429.40	0.34	0.00	3.05	429.06	0.00	0 00:
4 AD- (30)	1.89	0.97	428.38	0.38	0.00	4.08	428.00	0.00	0 00:
5 FES-5	36.97	36.97	426.50	1.40	0.00	1.10	425.11	0.01	0 00:
6 FES-6	12.03	12.03	425.74	0.99	0.00	1.25	424.77	0.02	0 00:

# **Channel Input**

SN Element	Length	Inlet	Inlet	Outlet	Outlet	Total	Average Sha	аре	Height	Width	Manı
ID		Invert	Invert	Invert	Invert	Drop	Slope				Rough
		Elevation	Offset	Elevation	Offset						
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)	
1 L-SL - (18) (1)	272.73	431.93	7.03	427.30	3.80	4.63	1.7000 Use	er-Defined	0.500	17.000	0

## **Channel Results**

SN Element	Peak	Time of	Design Flow	Peak Flow/	Peak Flow	Travel	Peak Flow	Peak Flow	Т
ID	Flow	Peak Flow	Capacity	Design Flow	Velocity	Time	Depth	Depth/	Sı
		Occurrence		Ratio				Total Depth	
								Ratio	
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (18) (1)	0.02	0 00:06	7.95	0.00	1.51	3.01	0.04	0.08	

# Pipe Input

SN Element	Length	Inlet	Inlet				Average		Pipe	Pipe	Ma
ID		Invert	Invert	Invert	Invert	Drop	Slope	Shape	Diameter or	Width	Rou
		Elevation	Offset	Elevation	Offset				Height		
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1 L-SL - (24)	201.23	430.66	6.56	426.94	4.62	3.72	1.8500	Dummy	0.000	0.000	
2 L-SL-14	251.73	423.42	0.00	422.50	0.18	0.92	0.3700	Dummy	0.000	0.000	
3 SL - (14)	127.64	423.42	0.00	422.72	0.40	0.70	0.5500	CIRCULAR	24.000	24.000	
4 SL - (15)	106.78	422.32	0.00	421.25	0.00	1.07	1.0000	CIRCULAR	30.000	30.000	
5 SL - (16)	105.49	429.05	0.00	428.00	0.00	1.05	1.0000	CIRCULAR	12.000	12.000	
6 SL - (17)	60.96	428.00	0.00	423.50	0.00	4.50	7.3800	CIRCULAR	12.000	12.000	
7 SL - (18)	141.40	427.00	0.00	424.90	0.00	2.10	1.4900	CIRCULAR	18.000	18.000	
8 SL - (18) (1)	20.22	424.90	0.00	424.50	0.00	0.40	1.9700	CIRCULAR	18.000	18.000	
9 SL - (19)	106.07	429.06	0.00	428.00	0.00	1.06	1.0000	CIRCULAR	12.000	12.000	
10 SL - (20)	19.89	428.00	0.00	427.50	0.50	0.50	2.5100	CIRCULAR	12.000	12.000	
11 SL - (21)	63.64	423.50	0.00	422.50	0.00	1.00	1.5700	CIRCULAR	24.000	24.000	
12 SL - (24)	177.82	424.10	0.00	422.32	0.00	1.78	1.0000	CIRCULAR	30.000	30.000	
13 SL - (25)	52.99	425.10	0.00	424.10	0.00	1.00	1.8900	CIRCULAR	30.000	30.000	
14 SL - (26)	123.36	424.75	0.00	423.50	0.00	1.25	1.0100	CIRCULAR	24.000	24.000	

No. of Barrels

## **Pipe Results**

SN Element ID	Peak Flow	Time of Peak Flow Occurrence		Peak Flow/ Design Flow Ratio			Peak Flow Depth	Peak Flow To Depth/ Sur Total Depth Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (24)	1.17	0 00:05	0.00	0.00	0.00		0.04	0.08
2 L-SL-14	6.18	0 00:05	0.00	0.00	0.00		0.04	0.08
3 SL - (14)	5.48	0 00:05	16.75	0.33	8.60	0.25	0.79	0.39
4 SL - (15)	48.11	0 00:04	44.48	1.08	10.82	0.16	2.50	1.00
5 SL - (16)	0.95	0 00:05	3.86	0.25	6.31	0.28	0.34	0.34
6 SL - (17)	1.89	0 00:05	10.49	0.18	10.12	0.10	0.29	0.29
7 SL - (18)	2.96	0 00:05	13.88	0.21	6.31	0.37	0.47	0.31
8 SL - (18) (1)	4.23	0 00:05	15.96	0.26	7.63	0.04	0.53	0.35
9 SL - (19)	0.95	0 00:05	3.86	0.25	6.31	0.28	0.34	0.34
10 SL - (20)	1.89	0 00:05	6.12	0.31	6.86	0.05	0.38	0.38
11 SL - (21)	11.98	0 00:18	30.72	0.39	9.17	0.12	0.87	0.43
12 SL - (24)	38.91	0 00:05	44.46	0.88	10.36	0.29	1.81	0.72
13 SL - (25)	36.76	0 00:05	61.04	0.60	13.23	0.07	1.40	0.56
14 SL - (26)	11.98	0 00:18	24.67	0.49	8.11	0.25	0.98	0.49

## **Inlet Input**


	SN Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
	ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
_				(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(%)
	1 CB-1	On Grade	1	423.42	429.56	6.14	423.42	0.00	N/A	0.00
	2 CB-2	On Sag	1	422.32	426.95	4.63	422.32	0.00	10.00	0.00
	3 CB-3	On Grade	1	424.10	430.66	6.56	424.10	0.00	N/A	0.00
	4 CB-4	On Grade	1	424.90	431.93	7.03	424.90	0.00	N/A	0.00
	5 CB-5	On Sag	1	427.00	432.00	5.00	427.00	0.00	10.00	0.00
	6 CB-6	On Sag	1	423.50	427.34	3.84	423.50	0.00	10.00	0.00

# **Roadway & Gutter Input**

SN Element	Roadway	Roadway	Roadway	Gutter	Gutter	Gutter	Allowable
ID	Longitudinal	Cross	Manning's	Cross	Width	Depression	Spread
	Slope	Slope	Roughness	Slope			
	(ft/ft)	(ft/ft)		(ft/ft)	(ft)	(in)	(ft)
1 CB-1	0.0100	0.0200	0.0150	0.0200	1.50	0.1312	10.00
2 CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3 CB-3	0.0380	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4 CB-4	0.0175	0.0200	0.0150	0.0200	1.50	0.1312	10.00
5 CB-5	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
6 CB-6	N/A	0.0350	0.0150	0.0200	1.50	0.1312	10.00

## **Inlet Results**

SN Element	Peak	Peak	Peak Flow	Peak Flow	Inlet	Max Gutter	Max Gutter	Max Gutter	
ID	Flow	Lateral	Intercepted	Bypassing	Efficiency	Spread	Water Elev.	Water Depth	Max
		Inflow	by	Inlet	during Peak	during Peak	during Peak	during Peak	Occi
			Inlet		Flow	Flow	Flow	Flow	
	(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days I
1 CB-1	11.72	11.72	5.54	6.18	47.29	17.73	429.91	0.35	- (
2 CB-2	16.31	8.97	N/A	N/A	N/A	15.00	427.65	0.70	(
3 CB-3	3.80	3.80	2.63	1.16	69.34	7.11	430.86	0.20	(
4 CB-4	1.37	1.37	1.35	0.02	98.50	7.15	432.07	0.14	(
5 CB-5	1.12	1.12	N/A	N/A	N/A	3.29	432.35	0.35	(
6 CB-6	8.55	8.55	N/A	N/A	N/A	10.95	427.97	0.63	(



# **Project Description**

File Name ...... Collective Church Drainage 4-23-25.SPF

## **Project Options**

Flow Units	CFS
Elevation Type	Elevation
Hydrology Method	Rational
Time of Concentration (TOC) Method	SCS TR-55
Link Routing Method	Kinematic Wave
Enable Overflow Ponding at Nodes	YES
Skip Steady State Analysis Time Periods	NO

# **Analysis Options**

Start Analysis On	Apr 23, 2025	00:00:00
End Analysis On	Apr 24, 2025	00:00:00
Start Reporting On	Apr 23, 2025	00:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

## **Number of Elements**

anibor or Elomonic	
	Qty
Rain Gages	. 0
Subbasins	
Nodes	16
Junctions	6
Outfalls	4
Flow Diversions	0
Inlets	6
Storage Nodes	0
Links	15
Channels	1
Pipes	14
Pumps	0
Orifices	0
Weirs	0
Outlets	0
Pollutants	0
Land Uses	0

## **Rainfall Details**

Return Period...... 50 year(s)

# **Subbasin Summary**

SN Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
	(ac)	Occinicioni	(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 Sub-AD- (24)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
2 Sub-AD- (25)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
3 Sub-AD- (29)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
4 Sub-AD- (30)	0.10	0.9500	0.86	0.82	0.08	0.97	0 00:05:00
5 Sub-CB-1	1.20	0.9500	0.86	0.82	0.98	11.72	0 00:05:00
6 Sub-CB-2	0.92	0.9500	0.86	0.82	0.75	8.97	0 00:05:00
7 Sub-CB-3	0.39	0.9500	0.86	0.82	0.32	3.80	0 00:05:00
8 Sub-CB-4	0.14	0.9500	0.86	0.82	0.11	1.37	0 00:05:00
9 Sub-CB-5	0.11	0.9500	0.86	0.82	0.09	1.12	0 00:05:00
10 Sub-CB-6	0.87	0.9500	0.86	0.82	0.71	8.55	0 00:05:00
11 Sub-FES-5	3.78	0.9500	0.86	0.82	3.08	36.97	0 00:05:00
12 Sub-FES-6	3.03	0.7000	1.72	1.20	3.64	12.03	0 00:18:13

# **Node Summary**

SN Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation			Max HGL Elevation Attained	Ma Surcharg Dept Attaine
		(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(f
1 AD- (24)	Junction	429.05	432.47	429.05	432.47	10.00	0.97	429.40	0.0
2 AD- (25)	Junction	428.00	432.46	428.00	432.46	10.00	1.89	428.34	0.0
3 AD- (29)	Junction	429.06	432.45	429.06	432.45	10.00	0.97	429.40	0.0
4 AD- (30)	Junction	428.00	432.46	428.00	432.46	10.00	1.89	428.38	0.0
5 FES-5	Junction	425.10	427.00	425.10	427.50	0.00	36.97	426.50	0.0
6 FES-6	Junction	424.75	426.99	424.75	426.99	0.00	12.03	425.74	0.0
7 Out-1SL - (15)	Outfall	421.25					48.11	423.75	
8 Out-1SL - (17)	Outfall	423.50					1.89	423.79	
9 Out-1SL - (18) (1)	Outfall	424.50					4.23	425.03	
10 Out-1SL - (21)	Outfall	422.50					11.98	423.37	

# **Link Summary**

SN Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness		Design Flow Capacity		Peak Flow Velocity	F
				(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	
1 L-SL - (24)	Pipe	CB-3	CB-2	201.23	430.66	426.94	1.8500	0.000	0.0320	1.17	0.00	0.00	0.00	_
2 L-SL-14	Pipe	CB-1	CB-2	251.73	423.42	422.50	0.3700	0.000	0.0150	6.18	0.00	0.00	0.00	
3 SL - (14)	Pipe	CB-1	CB-2	127.64	423.42	422.72	0.5500	24.000	0.0130	5.48	16.75	0.33	8.60	
4 SL - (15)	Pipe	CB-2	Out-1SL - (15)	106.78	422.32	421.25	1.0000	30.000	0.0120	48.11	44.48	1.08	10.82	
5 SL - (16)	Pipe	AD- (24)	AD- (25)	105.49	429.05	428.00	1.0000	12.000	0.0120	0.95	3.86	0.25	6.31	
6 SL - (17)	Pipe	AD- (25)	Out-1SL - (17)	60.96	428.00	423.50	7.3800	12.000	0.0120	1.89	10.49	0.18	10.12	
7 SL - (18)	Pipe	CB-5	CB-4	141.40	427.00	424.90	1.4900	18.000	0.0120	2.96	13.88	0.21	6.31	
8 SL - (18) (1)	Pipe	CB-4	Out-1SL - (18) (1)	20.22	424.90	424.50	1.9700	18.000	0.0120	4.23	15.96	0.26	7.63	
9 SL - (19)	Pipe	AD- (29)	AD- (30)	106.07	429.06	428.00	1.0000	12.000	0.0120	0.95	3.86	0.25	6.31	
10 SL - (20)	Pipe	AD- (30)	CB-5	19.89	428.00	427.50	2.5100	12.000	0.0120	1.89	6.12	0.31	6.86	
11 SL - (21)	Pipe	CB-6	Out-1SL - (21)	63.64	423.50	422.50	1.5700	24.000	0.0120	11.98	30.72	0.39	9.17	
12 SL - (24)	Pipe	CB-3	CB-2	177.82	424.10	422.32	1.0000	30.000	0.0120	38.91	44.46	0.88	10.36	
13 SL - (25)	Pipe	FES-5	CB-3	52.99	425.10	424.10	1.8900	30.000	0.0120	36.76	61.04	0.60	13.23	
14 SL - (26)	Pipe	FES-6	CB-6	123.36	424.75	423.50	1.0100	24.000	0.0120	11.98	24.67	0.49	8.11	
15 L-SL - (18) (1)	Channel	CB-4	CB-6	272.73	431.93	427.30	1.7000	6.000	0.0150	0.02	7.95	0.00	1.51	

# **Inlet Summary**

SN Element			Catchbasin	( )		Ponded					Allowable		Max Gutter
ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
			Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
								Inlet		Flow		Flow	Flow
			(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1 CB-1	On Grade	1	423.42	429.56	423.42	N/A	11.72	5.54	6.18	47.29	10.00	17.73	429.91
2 CB-2	On Sag	1	422.32	426.95	422.32	10.00	16.31	N/A	N/A	N/A	10.00	15.00	427.65
3 CB-3	On Grade	1	424.10	430.66	424.10	N/A	3.80	2.63	1.16	69.34	10.00	7.11	430.86
4 CB-4	On Grade	1	424.90	431.93	424.90	N/A	1.37	1.35	0.02	98.50	10.00	7.15	432.07
5 CB-5	On Sag	1	427.00	432.00	427.00	10.00	1.12	N/A	N/A	N/A	10.00	3.29	432.35
6 CB-6	On Sag	1	423.50	427.34	423.50	10.00	8.55	N/A	N/A	N/A	10.00	10.95	427.97

## **Subbasin Hydrology**

# Subbasin: Sub-AD- (24) **Time of Concentration** TOC Method: SCS TR-55 Sheet Flow Equation : $Tc = (0.007 * ((n * Lf)^0.8)) / ((P^0.5) * (Sf^0.4))$ Where: Tc = Time of Concentration (hr) n = Manning's roughness Lf = Flow Length (ft) P = 2 yr, 24 hr Rainfall (inches) Sf = Slope (ft/ft) Shallow Concentrated Flow Equation: V = 16.1345 \* (Sf^0.5) (unpaved surface) V = 20.3282 \* (Sf^0.5) (paved surface) V = 15.0 \* (Sf^0.5) (grassed waterway surface) V = 10.0 \* (Sf^0.5) (nearly bare & untilled surface) V = 9.0 \* (Sf^0.5) (cultivated straight rows surface) V = 7.0 \* (Sf^0.5) (short grass pasture surface) V = 5.0 \* (Sf^0.5) (woodland surface) V = 2.5 \* (Sf^0.5) (forest w/heavy litter surface) Tc = (Lf / V) / (3600 sec/hr)Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) Channel Flow Equation : $V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n$ R = Aq / WpTc = (Lf / V) / (3600 sec/hr) Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) R = Hydraulic Radius (ft) Aq = Flow Area (ft²) Wp = Wetted Perimeter (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) n = Manning's roughness

Subbasin: Sub-AD- (25)

**Time of Concentration** 

Subbasin: Sub-AD- (29)

**Time of Concentration** 

Subbasin: Sub-AD- (30)

**Time of Concentration** 

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

### **Time of Concentration**

Subbasin : Sub-FES-5

**Time of Concentration** 

# Subbasin : Sub-FES-6

### **Time of Concentration**

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0.00	0.00
Flow Length (ft):	85.71195638	0.00	0.00
Slope (%):	2.4	0.00	0.00
2 yr, 24 hr Rainfall (in):	4.36	0.00	0.00
Velocity (ft/sec):	0.12	0.00	0.00
Computed Flow Time (min) :	12.01	0.00	0.00
	Subarea	Subarea	Subarea
Shallow Concentrated Flow Computations	Α	В	С
Flow Length (ft):	253.76684919	31.2339863	0.93388558
Slope (%):	1.8	0.4	1.25
Surface Type :	Paved	Paved	Unpaved
Velocity (ft/sec):	2.73	1.29	1.80
Computed Flow Time (min) :	1.55	4.29	0.38
Total TOC (min)18.23			

# **Junction Input**

SN Element	Invert	Ground/Rim	Ground/Rim	Initial	Initial	Surcharge	Surcharge	Ponded	Minimum	
ID	Elevation	(Max)	(Max)	Water	Water	Elevation	Depth	Area	Pipe	
		Elevation	Offset	Elevation	Depth				Cover	
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(in)	
1 AD- (24)	429.05	432.47	3.41	429.05	0.00	432.47	0.00	10.00	28.92	
2 AD- (25)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.57	
3 AD- (29)	429.06	432.45	3.39	429.06	0.00	432.45	0.00	10.00	28.73	
4 AD- (30)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.55	
5 FES-5	425.10	427.00	1.90	425.10	0.00	427.50	0.50	0.00	0.00	
6 FES-6	424.75	426.99	2.24	424.75	0.00	426.99	0.00	0.00	2.85	

### **Junction Results**

SN Element ID	Peak Inflow	Peak Lateral	Max HGL Elevation		Max Surcharge		Average HGL Elevation	Average HGL Depth	Time Max H
		Inflow	Attained	Attained	Depth	Attained	Attained	Attained	Occurren
					Attained				
	(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:m
1 AD- (24)	0.97	0.97	429.40	0.35	0.00	3.07	429.06	0.01	0 00:
2 AD- (25)	1.89	0.97	428.34	0.34	0.00	4.13	428.00	0.00	0 00:
3 AD- (29)	0.97	0.97	429.40	0.34	0.00	3.05	429.06	0.00	0 00:
4 AD- (30)	1.89	0.97	428.38	0.38	0.00	4.08	428.00	0.00	0 00:
5 FES-5	36.97	36.97	426.50	1.40	0.00	1.10	425.11	0.01	0 00:
6 FES-6	12.03	12.03	425.74	0.99	0.00	1.25	424.77	0.02	0 00:

# **Channel Input**

SN Element	Length	Inlet	Inlet	Outlet	Outlet	Total	Average Sha	аре	Height	Width	Manı
ID		Invert	Invert	Invert	Invert	Drop	Slope				Rough
		Elevation	Offset	Elevation	Offset						
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)	
1 L-SL - (18) (1)	272.73	431.93	7.03	427.30	3.80	4.63	1.7000 Use	er-Defined	0.500	17.000	0

### **Channel Results**

SN Element	Peak	Time of	Design Flow	Peak Flow/	Peak Flow	Travel	Peak Flow	Peak Flow	Т
ID	Flow	Peak Flow	Capacity	Design Flow	Velocity	Time	Depth	Depth/	Sı
		Occurrence		Ratio				Total Depth	
								Ratio	
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
1 L-SL - (18) (1)	0.02	0 00:06	7.95	0.00	1.51	3.01	0.04	0.08	

# Pipe Input

SN Element	Length	Inlet	Inlet				Average		Pipe	Pipe	Ma
ID		Invert	Invert	Invert	Invert	Drop	Slope	Shape	Diameter or	Width	Rou
		Elevation	Offset	Elevation	Offset				Height		
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1 L-SL - (24)	201.23	430.66	6.56	426.94	4.62	3.72	1.8500	Dummy	0.000	0.000	
2 L-SL-14	251.73	423.42	0.00	422.50	0.18	0.92	0.3700	Dummy	0.000	0.000	
3 SL - (14)	127.64	423.42	0.00	422.72	0.40	0.70	0.5500	CIRCULAR	24.000	24.000	
4 SL - (15)	106.78	422.32	0.00	421.25	0.00	1.07	1.0000	CIRCULAR	30.000	30.000	
5 SL - (16)	105.49	429.05	0.00	428.00	0.00	1.05	1.0000	CIRCULAR	12.000	12.000	
6 SL - (17)	60.96	428.00	0.00	423.50	0.00	4.50	7.3800	CIRCULAR	12.000	12.000	
7 SL - (18)	141.40	427.00	0.00	424.90	0.00	2.10	1.4900	CIRCULAR	18.000	18.000	
8 SL - (18) (1)	20.22	424.90	0.00	424.50	0.00	0.40	1.9700	CIRCULAR	18.000	18.000	
9 SL - (19)	106.07	429.06	0.00	428.00	0.00	1.06	1.0000	CIRCULAR	12.000	12.000	
10 SL - (20)	19.89	428.00	0.00	427.50	0.50	0.50	2.5100	CIRCULAR	12.000	12.000	
11 SL - (21)	63.64	423.50	0.00	422.50	0.00	1.00	1.5700	CIRCULAR	24.000	24.000	
12 SL - (24)	177.82	424.10	0.00	422.32	0.00	1.78	1.0000	CIRCULAR	30.000	30.000	
13 SL - (25)	52.99	425.10	0.00	424.10	0.00	1.00	1.8900	CIRCULAR	30.000	30.000	
14 SL - (26)	123.36	424.75	0.00	423.50	0.00	1.25	1.0100	CIRCULAR	24.000	24.000	

No. of Barrels

## **Pipe Results**

SN Element ID	Peak Flow	Time of Peak Flow Occurrence		Peak Flow/ Design Flow Ratio			Peak Flow Depth	Peak Flow To Depth/ Sur Total Depth Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (24)	1.17	0 00:05	0.00	0.00	0.00		0.04	0.08
2 L-SL-14	6.18	0 00:05	0.00	0.00	0.00		0.04	0.08
3 SL - (14)	5.48	0 00:05	16.75	0.33	8.60	0.25	0.79	0.39
4 SL - (15)	48.11	0 00:04	44.48	1.08	10.82	0.16	2.50	1.00
5 SL - (16)	0.95	0 00:05	3.86	0.25	6.31	0.28	0.34	0.34
6 SL - (17)	1.89	0 00:05	10.49	0.18	10.12	0.10	0.29	0.29
7 SL - (18)	2.96	0 00:05	13.88	0.21	6.31	0.37	0.47	0.31
8 SL - (18) (1)	4.23	0 00:05	15.96	0.26	7.63	0.04	0.53	0.35
9 SL - (19)	0.95	0 00:05	3.86	0.25	6.31	0.28	0.34	0.34
10 SL - (20)	1.89	0 00:05	6.12	0.31	6.86	0.05	0.38	0.38
11 SL - (21)	11.98	0 00:18	30.72	0.39	9.17	0.12	0.87	0.43
12 SL - (24)	38.91	0 00:05	44.46	0.88	10.36	0.29	1.81	0.72
13 SL - (25)	36.76	0 00:05	61.04	0.60	13.23	0.07	1.40	0.56
14 SL - (26)	11.98	0 00:18	24.67	0.49	8.11	0.25	0.98	0.49

## **Inlet Input**


	SN Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
	ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
_				(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(%)
	1 CB-1	On Grade	1	423.42	429.56	6.14	423.42	0.00	N/A	0.00
	2 CB-2	On Sag	1	422.32	426.95	4.63	422.32	0.00	10.00	0.00
	3 CB-3	On Grade	1	424.10	430.66	6.56	424.10	0.00	N/A	0.00
	4 CB-4	On Grade	1	424.90	431.93	7.03	424.90	0.00	N/A	0.00
	5 CB-5	On Sag	1	427.00	432.00	5.00	427.00	0.00	10.00	0.00
	6 CB-6	On Sag	1	423.50	427.34	3.84	423.50	0.00	10.00	0.00

# **Roadway & Gutter Input**

SN Element	Roadway	Roadway	Roadway	Gutter	Gutter	Gutter	Allowable
ID	Longitudinal	Cross	Manning's	Cross	Width	Depression	Spread
	Slope	Slope	Roughness	Slope			
	(ft/ft)	(ft/ft)		(ft/ft)	(ft)	(in)	(ft)
1 CB-1	0.0100	0.0200	0.0150	0.0200	1.50	0.1312	10.00
2 CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3 CB-3	0.0380	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4 CB-4	0.0175	0.0200	0.0150	0.0200	1.50	0.1312	10.00
5 CB-5	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
6 CB-6	N/A	0.0350	0.0150	0.0200	1.50	0.1312	10.00

## **Inlet Results**

SN Element	Peak	Peak	Peak Flow	Peak Flow	Inlet	Max Gutter	Max Gutter	Max Gutter	
ID	Flow	Lateral	Intercepted	Bypassing	Efficiency	Spread	Water Elev.	Water Depth	Max
		Inflow	by	Inlet	during Peak	during Peak	during Peak	during Peak	Occi
			Inlet		Flow	Flow	Flow	Flow	
	(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days I
1 CB-1	11.72	11.72	5.54	6.18	47.29	17.73	429.91	0.35	- (
2 CB-2	16.31	8.97	N/A	N/A	N/A	15.00	427.65	0.70	(
3 CB-3	3.80	3.80	2.63	1.16	69.34	7.11	430.86	0.20	(
4 CB-4	1.37	1.37	1.35	0.02	98.50	7.15	432.07	0.14	(
5 CB-5	1.12	1.12	N/A	N/A	N/A	3.29	432.35	0.35	(
6 CB-6	8.55	8.55	N/A	N/A	N/A	10.95	427.97	0.63	(



# **Project Description**

File Name ...... Collective Church Drainage 4-23-25.SPF

## **Project Options**

Flow Units	CFS
Elevation Type	Elevation
Hydrology Method	Rational
Time of Concentration (TOC) Method	SCS TR-55
Link Routing Method	Kinematic Wave
Enable Overflow Ponding at Nodes	YES
Skip Steady State Analysis Time Periods	NO

# **Analysis Options**

Start Analysis On	Apr 23, 2025	00:00:00
End Analysis On	Apr 24, 2025	00:00:00
Start Reporting On	Apr 23, 2025	00:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step		days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

### **Number of Elements**

	Qty
Rain Gages	0
Subbasins	12
Nodes	16
Junctions	6
Outfalls	4
Flow Diversions	0
Inlets	6
Storage Nodes	0
	15
Channels	1
Pipes	14
Pumps	0
Orifices	0
Weirs	0
Outlets	0
Pollutants	0
Land Uses	0

## **Rainfall Details**

# **Subbasin Summary**

SN Subbasin ID	Area	Weighted Runoff Coefficient	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
	(ac)	Occincient	(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 Sub-AD- (24)	0.10	0.9500	0.93	0.89	0.09	1.06	0 00:05:00
2 Sub-AD- (25)	0.10	0.9500	0.93	0.89	0.09	1.06	0 00:05:00
3 Sub-AD- (29)	0.10	0.9500	0.93	0.89	0.09	1.06	0 00:05:00
4 Sub-AD- (30)	0.10	0.9500	0.93	0.89	0.09	1.06	0 00:05:00
5 Sub-CB-1	1.20	0.9500	0.93	0.89	1.06	12.74	0 00:05:00
6 Sub-CB-2	0.92	0.9500	0.93	0.89	0.81	9.75	0 00:05:00
7 Sub-CB-3	0.39	0.9500	0.93	0.89	0.34	4.13	0 00:05:00
8 Sub-CB-4	0.14	0.9500	0.93	0.89	0.12	1.49	0 00:05:00
9 Sub-CB-5	0.11	0.9500	0.93	0.89	0.10	1.22	0 00:05:00
10 Sub-CB-6	0.87	0.9500	0.93	0.89	0.77	9.30	0 00:05:00
11 Sub-FES-5	3.78	0.9500	0.93	0.89	3.35	40.20	0 00:05:00
12 Sub-FES-6	3.03	0.7000	1.86	1.30	3.95	13.04	0 00:18:13

# **Node Summary**

SN Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation			Max HGL Elevation Attained	Ma Surcharg Dept Attaine
		(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(ft)	(f
1 AD- (24)	Junction	429.05	432.47	429.05	432.47	10.00	1.06	429.41	0.0
2 AD- (25)	Junction	428.00	432.46	428.00	432.46	10.00	2.05	428.35	0.0
3 AD- (29)	Junction	429.06	432.45	429.06	432.45	10.00	1.06	429.42	0.0
4 AD- (30)	Junction	428.00	432.46	428.00	432.46	10.00	2.06	428.40	0.0
5 FES-5	Junction	425.10	427.00	425.10	427.50	0.00	40.20	426.58	0.0
6 FES-6	Junction	424.75	426.99	424.75	426.99	0.00	13.04	425.78	0.0
7 Out-1SL - (15)	Outfall	421.25					48.12	423.75	
8 Out-1SL - (17)	Outfall	423.50					2.05	423.80	
9 Out-1SL - (18) (1)	Outfall	424.50					4.59	425.05	
10 Out-1SL - (21)	Outfall	422.50					12.99	423.41	

# **Link Summary**

SN Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Invert	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	F
				(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	
1 L-SL - (24)	Pipe	CB-3	CB-2	201.23	430.66	426.94	1.8500	0.000	0.0320	1.36	0.00	0.00	0.00	_
2 L-SL-14	Pipe	CB-1	CB-2	251.73	423.42	422.50	0.3700	0.000	0.0150	6.96	0.00	0.00	0.00	
3 SL - (14)	Pipe	CB-1	CB-2	127.64	423.42	422.72	0.5500	24.000	0.0130	5.72	16.75	0.34	8.76	
4 SL - (15)	Pipe	CB-2	Out-1SL - (15)	106.78	422.32	421.25	1.0000	30.000	0.0120	48.12	44.48	1.08	10.84	
5 SL - (16)	Pipe	AD- (24)	AD- (25)	105.49	429.05	428.00	1.0000	12.000	0.0120	1.03	3.86	0.27	6.40	
6 SL - (17)	Pipe	AD- (25)	Out-1SL - (17)	60.96	428.00	423.50	7.3800	12.000	0.0120	2.05	10.49	0.20	10.37	
7 SL - (18)	Pipe	CB-5	CB-4	141.40	427.00	424.90	1.4900	18.000	0.0120	3.22	13.88	0.23	6.47	
8 SL - (18) (1)	Pipe	CB-4	Out-1SL - (18) (1)	20.22	424.90	424.50	1.9700	18.000	0.0120	4.59	15.96	0.29	7.80	
9 SL - (19)	Pipe	AD- (29)	AD- (30)	106.07	429.06	428.00	1.0000	12.000	0.0120	1.03	3.86	0.27	6.41	
10 SL - (20)	Pipe	AD- (30)	CB-5	19.89	428.00	427.50	2.5100	12.000	0.0120	2.06	6.12	0.34	7.03	
11 SL - (21)	Pipe	CB-6	Out-1SL - (21)	63.64	423.50	422.50	1.5700	24.000	0.0120	12.99	30.72	0.42	9.38	
12 SL - (24)	Pipe	CB-3	CB-2	177.82	424.10	422.32	1.0000	30.000	0.0120	42.20	44.46	0.95	10.49	
13 SL - (25)	Pipe	FES-5	CB-3	52.99	425.10	424.10	1.8900	30.000	0.0120	40.05	61.04	0.66	13.66	
14 SL - (26)	Pipe	FES-6	CB-6	123.36	424.75	423.50	1.0100	24.000	0.0120	13.00	24.67	0.53	8.28	
15 L-SL - (18) (1)	Channel	CB-4	CB-6	272.73	431.93	427.30	1.7000	6.000	0.0150	0.03	7.95	0.00	1.61	

# **Inlet Summary**

SN Element	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
ID	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
			Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
								Inlet		Flow		Flow	Flow
			(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1 CB-1	On Grade	1	423.42	429.56	423.42	N/A	12.74	5.79	6.96	45.40	10.00	18.29	429.92
2 CB-2	On Sag	1	422.32	426.95	422.32	10.00	18.08	N/A	N/A	N/A	10.00	16.06	427.68
3 CB-3	On Grade	1	424.10	430.66	424.10	N/A	4.13	2.76	1.36	66.97	10.00	7.33	430.87
4 CB-4	On Grade	1	424.90	431.93	424.90	N/A	1.49	1.45	0.04	97.12	10.00	7.38	432.08
5 CB-5	On Sag	1	427.00	432.00	427.00	10.00	1.22	N/A	N/A	N/A	10.00	3.48	432.36
6 CB-6	On Sag	1	423.50	427.34	423.50	10.00	9.30	N/A	N/A	N/A	10.00	11.58	427.99

### **Subbasin Hydrology**

# Subbasin: Sub-AD- (24) **Time of Concentration** TOC Method: SCS TR-55 Sheet Flow Equation : $Tc = (0.007 * ((n * Lf)^0.8)) / ((P^0.5) * (Sf^0.4))$ Where: Tc = Time of Concentration (hr) n = Manning's roughness Lf = Flow Length (ft) P = 2 yr, 24 hr Rainfall (inches) Sf = Slope (ft/ft) Shallow Concentrated Flow Equation: V = 16.1345 \* (Sf^0.5) (unpaved surface) V = 20.3282 \* (Sf^0.5) (paved surface) V = 15.0 \* (Sf^0.5) (grassed waterway surface) V = 10.0 \* (Sf^0.5) (nearly bare & untilled surface) V = 9.0 \* (Sf^0.5) (cultivated straight rows surface) V = 7.0 \* (Sf^0.5) (short grass pasture surface) V = 5.0 \* (Sf^0.5) (woodland surface) V = 2.5 \* (Sf^0.5) (forest w/heavy litter surface) Tc = (Lf / V) / (3600 sec/hr)Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) Channel Flow Equation : $V = (1.49 * (R^{(2/3)}) * (Sf^{0.5})) / n$ R = Aq / WpTc = (Lf / V) / (3600 sec/hr) Where: Tc = Time of Concentration (hr) Lf = Flow Length (ft) R = Hydraulic Radius (ft) Aq = Flow Area (ft²) Wp = Wetted Perimeter (ft) V = Velocity (ft/sec) Sf = Slope (ft/ft) n = Manning's roughness

Subbasin: Sub-AD- (25)

**Time of Concentration** 

Subbasin: Sub-AD- (29)

**Time of Concentration** 

Subbasin: Sub-AD- (30)

Time of Concentration

### **Time of Concentration**

Subbasin : Sub-FES-5

**Time of Concentration** 

# Subbasin : Sub-FES-6

### **Time of Concentration**

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0.00	0.00
Flow Length (ft):	85.71195638	0.00	0.00
Slope (%):	2.4	0.00	0.00
2 yr, 24 hr Rainfall (in):	4.36	0.00	0.00
Velocity (ft/sec):	0.12	0.00	0.00
Computed Flow Time (min) :	12.01	0.00	0.00
	Subarea	Subarea	Subarea
Shallow Concentrated Flow Computations	Α	В	С
Flow Length (ft):	253.76684919	31.2339863	0.93388558
Slope (%):	1.8	0.4	1.25
Surface Type :	Paved	Paved	Unpaved
Velocity (ft/sec):	2.73	1.29	1.80
Computed Flow Time (min):	1.55	4.29	0.38
Total TOC (min)18.23			

## **Junction Input**

SN Element	Invert	Ground/Rim	Ground/Rim	Initial	Initial	Surcharge	Surcharge	Ponded	Minimum
ID	Elevation	(Max)	(Max)	Water	Water	Elevation	Depth	Area	Pipe
		Elevation	Offset	Elevation	Depth				Cover
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(in)
1 AD- (24)	429.05	432.47	3.41	429.05	0.00	432.47	0.00	10.00	28.92
2 AD- (25)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.57
3 AD- (29)	429.06	432.45	3.39	429.06	0.00	432.45	0.00	10.00	28.73
4 AD- (30)	428.00	432.46	4.46	428.00	0.00	432.46	0.00	10.00	41.55
5 FES-5	425.10	427.00	1.90	425.10	0.00	427.50	0.50	0.00	0.00
6 FES-6	424.75	426.99	2.24	424.75	0.00	426.99	0.00	0.00	2.85

### **Junction Results**

SN Element ID	Peak Inflow	Peak Lateral	Max HGL Elevation		Max Surcharge		Average HGL Elevation	Average HGL Depth	Time Max H
		Inflow	Attained	Attained	Depth	Attained	Attained	Attained	Occurren
					Attained				
	(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:m
1 AD- (24)	1.06	1.06	429.41	0.36	0.00	3.05	429.06	0.01	0 00:
2 AD- (25)	2.05	1.06	428.35	0.35	0.00	4.11	428.00	0.00	0 00:
3 AD- (29)	1.06	1.06	429.42	0.36	0.00	3.04	429.06	0.00	0 00:
4 AD- (30)	2.06	1.06	428.40	0.40	0.00	4.06	428.00	0.00	0 00:
5 FES-5	40.20	40.20	426.58	1.48	0.00	1.02	425.11	0.01	0 00:
6 FES-6	13.04	13.04	425.78	1.03	0.00	1.20	424.77	0.02	0 00:

# **Channel Input**

SN Element	Length	Inlet	Inlet	Outlet	Outlet	Total	Average	Shape	Height	Width	Manı
ID		Invert	Invert	Invert	Invert	Drop	Slope				Rough
		Elevation	Offset	Elevation	Offset						
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)	
1 L-SL - (18) (1)	272.73	431.93	7.03	427.30	3.80	4.63	1.7000	User-Defined	0.500	17.000	0

## **Channel Results**

;	SN Element	Peak	Time of	Design Flow	Peak Flow/	Peak Flow	Travel	Peak Flow	Peak Flow	Т
	ID	Flow	Peak Flow	Capacity	Design Flow	Velocity	Time	Depth	Depth/	Sı
			Occurrence		Ratio				Total Depth	
									Ratio	
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		
	1 L-SL - (18) (1)	0.03	0 00:06	7.95	0.00	1.61	2.82	0.04	0.09	

# Pipe Input

SN Element	Length	Inlet	Inlet				Average		Pipe	Pipe	Ма
ID		Invert	Invert	Invert	Invert	Drop	Slope	Shape	Diameter or	Width	Rou
		Elevation	Offset	Elevation	Offset				Height		
	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(in)	(in)	
1 L-SL - (24)	201.23	430.66	6.56	426.94	4.62	3.72	1.8500	Dummy	0.000	0.000	
2 L-SL-14	251.73	423.42	0.00	422.50	0.18	0.92	0.3700	Dummy	0.000	0.000	
3 SL - (14)	127.64	423.42	0.00	422.72	0.40	0.70	0.5500	CIRCULAR	24.000	24.000	
4 SL - (15)	106.78	422.32	0.00	421.25	0.00	1.07	1.0000	CIRCULAR	30.000	30.000	
5 SL - (16)	105.49	429.05	0.00	428.00	0.00	1.05	1.0000	CIRCULAR	12.000	12.000	
6 SL - (17)	60.96	428.00	0.00	423.50	0.00	4.50	7.3800	CIRCULAR	12.000	12.000	
7 SL - (18)	141.40	427.00	0.00	424.90	0.00	2.10	1.4900	CIRCULAR	18.000	18.000	
8 SL - (18) (1)	20.22	424.90	0.00	424.50	0.00	0.40	1.9700	CIRCULAR	18.000	18.000	
9 SL - (19)	106.07	429.06	0.00	428.00	0.00	1.06	1.0000	CIRCULAR	12.000	12.000	
10 SL - (20)	19.89	428.00	0.00	427.50	0.50	0.50	2.5100	CIRCULAR	12.000	12.000	
11 SL - (21)	63.64	423.50	0.00	422.50	0.00	1.00	1.5700	CIRCULAR	24.000	24.000	
12 SL - (24)	177.82	424.10	0.00	422.32	0.00	1.78	1.0000	CIRCULAR	30.000	30.000	
13 SL - (25)	52.99	425.10	0.00	424.10	0.00	1.00	1.8900	CIRCULAR	30.000	30.000	
14 SL - (26)	123.36	424.75	0.00	423.50	0.00	1.25	1.0100	CIRCULAR	24.000	24.000	

No. of Barrels

### **Pipe Results**

SN Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity		Peak Flow Velocity		Peak Flow Depth	Peak Flow To Depth/ Sur Total Depth Ratio
	(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)	
1 L-SL - (24)	1.36	0 00:05	0.00	0.00	0.00		0.04	0.09
2 L-SL-14	6.96	0 00:05	0.00	0.00	0.00		0.04	0.09
3 SL - (14)	5.72	0 00:05	16.75	0.34	8.76	0.24	0.80	0.40
4 SL - (15)	48.12	0 00:04	44.48	1.08	10.84	0.16	2.50	1.00
5 SL - (16)	1.03	0 00:05	3.86	0.27	6.40	0.27	0.35	0.35
6 SL - (17)	2.05	0 00:05	10.49	0.20	10.37	0.10	0.30	0.30
7 SL - (18)	3.22	0 00:05	13.88	0.23	6.47	0.36	0.49	0.33
8 SL - (18) (1)	4.59	0 00:05	15.96	0.29	7.80	0.04	0.55	0.37
9 SL - (19)	1.03	0 00:05	3.86	0.27	6.41	0.28	0.35	0.35
10 SL - (20)	2.06	0 00:05	6.12	0.34	7.03	0.05	0.40	0.40
11 SL - (21)	12.99	0 00:18	30.72	0.42	9.38	0.11	0.91	0.45
12 SL - (24)	42.20	0 00:05	44.46	0.95	10.49	0.28	1.94	0.78
13 SL - (25)	40.05	0 00:05	61.04	0.66	13.66	0.06	1.48	0.59
14 SL - (26)	13.00	0 00:18	24.67	0.53	8.28	0.25	1.03	0.52

### **Inlet Input**


SN	I Element	Inlet	Number of	Catchbasin	Max (Rim)	Inlet	Initial	Initial	Ponded	Grate
	ID	Location	Inlets	Invert	Elevation	Depth	Water	Water	Area	Clogging
				Elevation			Elevation	Depth		Factor
				(ft)	(ft)	(ft)	(ft)	(ft)	(ft <sup>2</sup> )	(%)
1	CB-1	On Grade	1	423.42	429.56	6.14	423.42	0.00	N/A	0.00
2	2 CB-2	On Sag	1	422.32	426.95	4.63	422.32	0.00	10.00	0.00
3	3 CB-3	On Grade	1	424.10	430.66	6.56	424.10	0.00	N/A	0.00
4	CB-4	On Grade	1	424.90	431.93	7.03	424.90	0.00	N/A	0.00
5	CB-5	On Sag	1	427.00	432.00	5.00	427.00	0.00	10.00	0.00
6	CB-6	On Sag	1	423.50	427.34	3.84	423.50	0.00	10.00	0.00

### **Roadway & Gutter Input**

SN Element	Roadway	Roadway	Roadway	Gutter	Gutter	Gutter	Allowable
ID	Longitudinal	Cross	Manning's	Cross	Width	Depression	Spread
	Slope	Slope	Roughness	Slope			
	(ft/ft)	(ft/ft)		(ft/ft)	(ft)	(in)	(ft)
1 CB-1	0.0100	0.0200	0.0150	0.0200	1.50	0.1312	10.00
2 CB-2	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
3 CB-3	0.0380	0.0300	0.0150	0.0200	1.50	0.1312	10.00
4 CB-4	0.0175	0.0200	0.0150	0.0200	1.50	0.1312	10.00
5 CB-5	N/A	0.0300	0.0150	0.0200	1.50	0.1312	10.00
6 CB-6	N/A	0.0350	0.0150	0.0200	1.50	0.1312	10.00

### **Inlet Results**

SN Element	Peak	Peak	Peak Flow	Peak Flow	Inlet	Max Gutter	Max Gutter	Max Gutter	
ID	Flow	Lateral	Intercepted	Bypassing	Efficiency	Spread	Water Elev.	Water Depth	Max
		Inflow	by	Inlet	during Peak	during Peak	during Peak	during Peak	Occi
			Inlet		Flow	Flow	Flow	Flow	
	(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days I
1 CB-1	12.74	12.74	5.79	6.96	45.40	18.29	429.92	0.37	-
2 CB-2	18.08	9.75	N/A	N/A	N/A	16.06	427.68	0.73	1
3 CB-3	4.13	4.13	2.76	1.36	66.97	7.33	430.87	0.20	1
4 CB-4	1.49	1.49	1.45	0.04	97.12	7.38	432.08	0.15	(
5 CB-5	1.22	1.22	N/A	N/A	N/A	3.48	432.36	0.35	1
6 CB-6	9.30	9.30	N/A	N/A	N/A	11.58	427.99	0.66	1



### **Table of Contents**

Hydrology Studio v 3.0.0.27 04-23-2025

Basir	n Model Schematic	1
Hydro	ograph by Return Period	2
2 - Ye	ear	
	Hydrograph Summary	3
	Hydrograph Reports	
	Hydrograph No. 1, Rational, Pre-Dev Basin	4
	Tc by TR55 Worksheet	5
	Hydrograph No. 2, Rational, Post-Dev Basin	6
10 - Y	'ear	
	Hydrograph Summary	7
	Hydrograph Reports	
	Hydrograph No. 1, Rational, Pre-Dev Basin	8
	Hydrograph No. 2, Rational, Post-Dev Basin	9
25 - Y	ear	
	Hydrograph Summary	10
	Hydrograph Reports	
	Hydrograph No. 1, Rational, Pre-Dev Basin	11
	Hydrograph No. 2, Rational, Post-Dev Basin	12
50 - Y	'ear	
	Hydrograph Summary	13
	Hydrograph Reports	
	Hydrograph No. 1, Rational, Pre-Dev Basin	14
	Hydrograph No. 2, Rational, Post-Dev Basin	15
100 -	Year	
	Hydrograph Summary	16
	Hydrograph Reports	
	Hydrograph No. 1, Rational, Pre-Dev Basin	17
	Hydrograph No. 2, Rational, Post-Dev Basin	18

Hydrology Studio v 3.0.0.27 04-23-2025

	Pre-Dev Basin	Post-Dev Basin
		POSI-Dev Basili
	***	
	<b>/</b>	7
		,
İ		

# Hydrograph by Return Period

Hydrology Studio v 3.0.0.27

04-23-2025

Hyd.	Hydrograph	Hydrograph	Peak Outflow (cfs)							
No.	Туре	Name	1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr
1	Rational	Pre-Dev Basin		7.340			9.834	11.30	12.35	13.42
2	Rational	Post-Dev Basin		20.30			27.14	31.18	34.05	37.03


# Hydrograph 2-yr Summary

04-23-2025 Hydrology Studio v 3.0.0.27 Hydrograph Volume (cuft) Maximum Peak Time to Inflow Maximum Hyd. Hydrograph Hydrograph Storage (cuft) Flow Peak Hyd(s) Elevation No. Name Type (cfs) (hrs) (ft) 1 Rational Pre-Dev Basin 7.340 0.17 5,879 2 Rational Post-Dev Basin 20.30 0.08 8,130

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Hyd. No. 1

Hydrograph Type	= Rational	Peak Flow	= 7.340 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 5,879 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.47
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 4.49 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	s = 1/1.67



# Tc by TR55 Worksheet

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Rational


Hyd. No. 1

Description	Segments					
Description	Α	В	С	Tc (min)		
Sheet Flow						
Description						
Manning's n	0.300	0.013	0.013			
Flow Length (ft)	100					
2-yr, 24-hr Precip. (in)	4.36	2.28	2.28			
Land Slope (%)	5.5					
Travel Time (min)	9.75	0.00	0.00	9.75		
Shallow Concentrated Flow						
Flow Length (ft)	137					
Watercourse Slope (%)	6.20	0.00	0.00			
Surface Description	Unpaved	Paved	Paved			
Average Velocity (ft/s)	4.02					
Travel Time (min)	0.57	0.00	0.00	0.57		
Channel Flow						
X-sectional Flow Area (sqft)						
Wetted Perimeter (ft)						
Channel Slope (%)						
Manning's n	0.013	0.013	0.013			
Velocity (ft/s)	0.010	0.010	3.010			
Flow Length (ft)						
<b>L</b> ongur ()						
Travel Time (min)	0.00	0.00	0.00	0.00		
Total Travel Time				10 min		

Hydrology Studio v 3.0.0.27 04-23-2025

### Post-Dev Basin Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 20.30 cfs
Storm Frequency	= 2-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 8,130 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.14 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factor	rs = 1/1.67




# Hydrograph 10-yr Summary

04-23-2025 Hydrology Studio v 3.0.0.27 Hydrograph Volume (cuft) Maximum Peak Time to Inflow Maximum Hyd. Hydrograph Hydrograph Storage (cuft) Flow Peak Hyd(s) Elevation No. Name Type (cfs) (hrs) (ft) 1 Rational Pre-Dev Basin 9.834 0.17 7,877 2 Rational Post-Dev Basin 27.14 0.08 10,870

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 9.834 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 7,877 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.47
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.01 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	s = 1/1.67



Hydrology Studio v 3.0.0.27 04-23-2025

### Post-Dev Basin Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 27.14 cfs
Storm Frequency	= 10-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 10,870 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.21 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factor	rs = 1/1.67



04-23-2025


# Hydrograph 25-yr Summary Hydrology Studio v 3.0.0.27

ydrology St	udio v 3.0.0.27		1	1				U4-23-20
Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	Rational	Pre-Dev Basin	11.30	0.17	9,052			
2	Rational	Post-Dev Basin	31.18	0.08	12,486			
	1		1	İ	1		1	

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 11.30 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 9,052 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.47
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 6.91 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	s = 1/1.67



Hydrology Studio v 3.0.0.27 04-23-2025

### Post-Dev Basin Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 31.18 cfs
Storm Frequency	= 25-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 12,486 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 9.43 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	s = 1/1.67




# Hydrograph 50-yr Summary

04-23-2025 Hydrology Studio v 3.0.0.27 Hydrograph Volume (cuft) Maximum Peak Time to Inflow Maximum Hyd. Hydrograph Hydrograph Storage (cuft) Flow Peak Hyd(s) Elevation No. Name Type (cfs) (hrs) (ft) 1 Rational Pre-Dev Basin 12.35 0.17 9,896 2 Rational Post-Dev Basin 34.05 0.08 13,638

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 12.35 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 9,896 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.47
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 7.55 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factors	s = 1/1.67



Hydrology Studio v 3.0.0.27 04-23-2025

### Post-Dev Basin Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 34.05 cfs
Storm Frequency	= 50-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 13,638 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 10.30 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factor	rs = 1/1.67




# Hydrograph 100-yr Summary

04-23-2025 Hydrology Studio v 3.0.0.27 Hydrograph Volume (cuft) Maximum Peak Time to Inflow Maximum Hyd. Hydrograph Hydrograph Storage (cuft) Flow Peak Hyd(s) Elevation No. Name Type (cfs) (hrs) (ft) 1 Rational Pre-Dev Basin 13.42 0.17 10,749 2 Rational Post-Dev Basin 37.03 0.08 14,829

Hydrology Studio v 3.0.0.27 04-23-2025

### Pre-Dev Basin Hyd. No. 1


Hydrograph Type	= Rational	Peak Flow	= 13.42 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.17 hrs
Time Interval	= 1 min	Runoff Volume	= 10,749 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.47
Tc Method	= TR55 (See Worksheet)	Time of Conc. (Tc)	= 10.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 8.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factor	s = 1/1.67



Hydrology Studio v 3.0.0.27 04-23-2025

### Post-Dev Basin Hyd. No. 2

Hydrograph Type	= Rational	Peak Flow	= 37.03 cfs
Storm Frequency	= 100-yr	Time to Peak	= 0.08 hrs
Time Interval	= 1 min	Runoff Volume	= 14,829 cuft
Drainage Area	= 3.48 ac	Runoff Coeff.	= 0.95
Tc Method	= User	Time of Conc. (Tc)	= 5.0 min
IDF Curve	= City of Bryant IDF Curve.idf	Intensity	= 11.20 in/hr
Freq. Corr. Factor	= 1.00	Asc/Rec Limb Factor	rs = 1/1.67





City of Bryant
Development & Review Committee
Attn: Mr. Truett Smith
Director of Community Development

RE: Letter of Request for approval of Site Plan for Collective Church, Saline County, Arkansas

Dear Mr. Smith:

Please accept this letter as a request to approve the Site Plan for Collective Church at the May 12, 2025, Planning Commission Meeting.

We would like DRC to be made aware in regard to Sheet 7 Grading Plan. We are planning on creating a back slope from our project's south line that goes beyond our property line into drainage easement of detention pond. This slope we are creating does not impact the volume of the detention pond.

### **Developer's Information:**

Collective Church Bryant, AR Skylyr Stott contact@gchomesllc.com (501) 658-2095

### **Engineer's Information:**

Tristin Phillips, PE Richardson Engineering, PLLC P.O. Box 192 Benton, AR 72018 <u>Tristin@Richardson-Engrs.com</u> (501) 315-7225

Sincerely,

Tristin Phillips, PE


# DETAILED PLANS:

# STATE FARM – JAMEY SOUTH PROPOSED STORAGE BUILDING

515 N. REYNOLDS ROAD BRYANT, ARKANSAS

PRE-CONSTRUCTION COPY -

PLANS FOR BIDDING PURPOSES.
QUANTITIES TO BE VERIFIED PRIOR
TO CONSTRUCTION. CONTRACTOR
TO VERIFY GRADES WITH ENGINEER
PRIOR TO CONSTRUCTION.



Prepared By:




4/22/2025

PREPARED FOR:

JAMEY SOUTH
515 N. REYNOLDS ROAD
BRYANT, AR 72022



INDEX OF SHEETS	
COVER SHEET	1
SWPPP	2
DEMOLITION PLAN	3
SITE/LANDSCAPE PLAN	4
GRADING PLAN	5



M. CONTRACTOR SHALL CONTACT CITY OF BRYANT PRIOR TO COMMENCEMENT OF UTILITY

CONSTRUCTION OR TIE-INS.

**DEMO NOTES:** 

BRYANT SEWER DEPARTMENT 1019 S.W. 2ND ST. BRYANT, AR 72022

E R I N Gevelopment Consulting

ZAT 10

S


5


51


BRYANT WATER DEPARTMENT 210 S.W. 3RD ST. BRYANT, AR 72022 501-943-0441

LITTLE ROCK, AR 72201 1-800-368-3749

NATURAL GAS:







■ Existing Water Meter Box ○ Computed Corner

Found Monument (Labeled)

Sewer Mnahole © Existing Storm Box

∅ Utility Pole Gas Meter

 Existing Fire Hydrant -**①** Guy Wire


(O) Sewer Stubup

<u>UTILITIES:</u>


SANITARY SEWER: 501-943-0469


**ENTERGY** 425 W. CAPITAL AVE.

SUMMIT UTILITIES 400 WEST CAPITOL #600 LITTLE ROCK, ARKANSAS 888-498-0409



Know what's below. Call before you dig.





ACE Sign Company 11935 Interstate 30 Little Rock, AR 72209

RE: Zoning Variance Application for: Central Arkansas Truck Outfitters LLC

To the City of Bryant Adjustment Board Members:

Please allow this letter to serve as a formal recommendation for a variance in regards to the property for Central Arkansas Truck Outfitters. This property with interstate frontage has a physical address of 25633 I-30 in Bryant Arkansas.

The property ownership group is requesting to erect a lighted single pole cabinet sign with a 300 square foot (10' x30') overall size at an overall height of 40' from grade.

Specific points for your review of this variance application hardship letter are as follows:

- Unique shared plot placement with a completely different business address.
- Interstate frontage with a building setback that requires additional visibility.
- Surrounding businesses with the ability to construct pole signs on their property.

We appreciate the consideration of the board, and we remain optimistic that a fair decision will be made regarding this specific request. Thank you.

Jason McDonald Account Manager ACE Sign Company





PROPERTY BRAND/EXTENSION: Central Arkansas Outfitters PROPERTY LOCATION: 25633 I-30 Bryant, AR 72022

DED BY

**DATE:** 04/21/2025

SALES REP: Jason McDonald PREPARED BY: Victoria Phan


©2022 ACE Company & Ace Signs of Arkansas, LLC. All Rights Reserved. This design is the property of ACE Company and are the result of original work of its employees. They are submitted to your company for the purpose of consideration to purchase from ACE Company, a project according to this design. Exhibition to anyone other that employees of your company or use of this design or to create a design that is similar without written approval from ACE Company is a violation of copyright. In the event that such violation occurs, ACE Company shall be paid for the full amount of any project using a similar design. The colors and dimensions are approximate and may vary from the actual product. Customer must Sign and Date for artwork approval to confirm they are ready for productout. Qustomer must Sign and Date for artwork approval to confirm they are ready for productout. Qustomer must Sign and Date for artwork approval to confirm they are ready for productout.

INITIALS: \_\_\_

TBD

PROPERTY CODE:

# **LOCATION MAP**





PROPERTY BRAND/EXTENSION: Central Arkansas Outfitters PROPERTY LOCATION: 25633 I-30 Bryant, AR 72022 PROPERTY CODE: TBD

**DATE:** 01/13/2025

SALES REP: Jason McDonald PREPARED BY: Victoria Phan

©2022 ACE Company & Ace Signs of Arkansas, LLC. All Rights Reserved. This design is the property of ACE Company and are the result of original work of its employees. They are submitted to your company for the purpose of consideration to purchase from ACE Company, a project according to this design. Exhibition to anyone other that employees of your company or use of this design or to create a design that is similar without written approval from ACE Company is a violation of copyright. In the event that such violation occurs, ACE Company shall be paid for the full amount of any project using a similar design. Toolors and dimensions are approximate and may vary from the actual product. Customer must Sign and Date for artwork approval to confirm they are ready for production. Please double check colors, sizes, placement, description, and spelling errors before signing. After payments and signed approval, the artwork is now owned by the customer.

INITIALS: \_\_


# SITE PLAN

### **PROPOSED SIGNS:**

### **EXISTING SIGNS:**

1 MID-RISE

1 NO SIGN





PROPERTY BRAND/EXTENSION: Central Arkansas Outfitters	PROPERTY LOCATIO 25633 I-30 Bryant, AF		PROPERTY CODE: TBD
<b>DATE:</b> 04/16/2025	SALES REP: Jason McDonald	PREPARED BY: Victoria Phan	
They are submitted to your company for the purpose of employees of your company or use of this design or to	f consideration to purchase from ACE Compan create a design that is similar without written a	y of ACE Company and are the result of original work of its employees, y, a project according to this design. Exhibition to anyone other that proval from ACE Company is a violation of copyright. In the event that	INITIAL C.

### **EXISTING**



### **PROPOSED**



RENDERINGS NOT TO SCALE



H10' x W30' x D2'-8" Cabinet with applied graphics Cabinet 300 Sq. Ft. OAH 40'



TO BE DETERMINED



04/21/2025

TO BE DETERMINED

TO BE DETERMINED

PROPERTY BRAND/EXTENSION: Central Arkansas Outfitters

**PROPERTY LOCATION:** 25633 I-30 Bryant, AR 72022

> PREPARED BY: Victoria Phan

**SALES REP:** Jason McDonald

©2022 ACE Company & Ace Signs of Arkansas, LLC. All Rights Reserved. This design is the property of ACE Company and are the result of original work of its employees. They are submitted to your company for the purpose of consideration to purchase from ACE Company, a project according to this design. Exhibition to anyone other that employees of your company or use of this design or to create a design that is similar without written approval from ACE Company is a violation of copyright. In the event that such violation occurs, ACE Company shall be paid for the full amount of any project using a similar design. To colors and dimensions are approximate and may vary from the actual product. Customer must Sign and Date for artwork approval to confirm they are ready for production. Please double check colors, sizes, placement, description, and spelling errors before signing. After payments and signed approval, the artwork is now owned by the customer.

INITIALS: \_

PROPERTY CODE:

TBD

# Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering in packet.

SIGN	<b>Type</b> (Façade, Pole,	<b>Dimensions</b> (Height, Length, Width)	<b>Sqft</b> (Measurement	Façade Width (Linear Ft of building	He	ight
	Monument, other)		standards found on Pg.7 of Sign Code)	façade where wall sign is being installed)	То Тор	To Bottom
А	Pole Sign	10' x 30'	300 sq ft	N/A	30'	40'
В						
С						
D						
Е						
F						